## Geologic Controls on DNAPL Migration And Preliminary Remedy Evaluation Fields Brook (DETREX) Superfund Site Ashtabula, Ohio



November 2010

## Geologic Controls on DNAPL Migration And Preliminary Remedy Evaluation Fields Brook (DETREX) Superfund Site Ashtabula, Ohio

Prepared For:

U.S. EPA Region 5



#### Prepared By:



S.S. PAPADOPULOS & ASSOCIATES, INC. Environmental & Water-Resource Consultant

November 2010

#### **Executive Summary**

This report has been prepared by S.S. Papadopulos & Associates, Inc. (SSP&A) on behalf of the U.S. Environmental Protection Agency (U.S. EPA), Region V, Groundwater Evaluation and Optimization System (GEOS) program for the Detrex facility that is part of the Fields Brook Superfund Site (the site), located in Ashtabula, Ohio. This report presents: 1) an evaluation of the subsurface geology, with a focus on the interpretation of the upper surface of the compacted glacial till; 2) a summary of dense non-aqueous phase liquid (DNAPL) occurrence and potential stratigraphic controls on DNAPL migration, including an evaluation of remedy components currently in place at the site; and 3) a review of groundwater flow and quality.

SSP&A reviewed over 160 boring logs to define the top surface of the compacted till at the Fields Brook Site and prepared a structure contour map of the till surface based on apparent positive identification in 24 boring logs, in combination with 19 deeper borings/excavations that did not penetrate till but provide a maximum elevation. SSP&A's interpretation of the compacted till surface indicates that it generally slopes towards the north and northeast away from the area of the former lagoons. A depression in the compacted till surface occurs in the southern portion of the site along Fields Brook. Evidence for the presence of a depression below the former lagoon area, or for a ridge capable of preventing migration of DNAPL from the former lagoon area toward Fields Brook, was not observed.

DNAPL has been observed in the clay, sand, and silt sediments of the lacustrine unit in the source area, and along the DS Tributary, State Road and Fields Brook. While some DNAPL near the outfall of the Detrex Tributary and within Fields Brook may be attributed to surface drainage from the former lagoon area, the pooled DNAPL at the source area may also have migrated from the source area to Fields Brook within lenses, fractures and bedding planes in the lacustrine sediments, irrespective of the elevation of the till surface. Evidence of lateral DNAPL migration within the lacustrine sediments is found in monitoring well RMSMW02S, located north of the Detrex property, where an estimated 10 feet of DNAPL was observed in the bottom of the 25-feet deep well (Eckenfelder, 1990). DNAPL has not been identified at the lacustrine/till contact in the source area and DNAPL has not been observed in till or bedrock, although only a limited number of borings penetrate to these underlying geologic units. Furthermore, DNAPL has not been identified at the till/lacustrine contact in the source area. As a result, there is no clear evidence that DNAPL movement from the former lagoon area is being controlled by the till surface: DNAPL may have migrated from the source area within the lacustrine sediments towards Fields Brook, irrespective of the till surface.

Groundwater with significant concentrations of VOCs is not observed outside of the source area. This may be due to a lack of monitoring locations screened at appropriate depths, and/or the presence of limited zones of VOC-contaminated groundwater that are deeper than the South Area Interceptor Trench and/or are not in communication with the existing monitoring wells.

The elevation of the base of the slurry wall located west of the former lagoon area is lower than the DNAPL elevations observed near the source. In addition, the slurry wall appears to be keyed into the compacted till. Assuming that the compacted till restricts the downward migration of DNAPL, the slurry wall depth appears to be adequate. The horizontal extent of the slurry wall however, may not limit the migration of DNAPL around the ends of the slurry wall.

Comparison of the remedy elements that are in place versus the elevation at which DNAPL has been observed indicate that the base of the South Area Groundwater Interceptor Trench is higher in elevation than the base of DNAPL observation in the source zone. The South Area Interceptor trench may therefore not be sufficiently deep to capture DNAPL, should migration of DNAPL from the source area towards Fields Brook occur.

## **Table of Contents**

		Page
List of Tab	les, Figures, Appendices	ii
Executive S	Summary	ES-1
Section 1	Introduction	1-1
	1.1 Background	1-1
Section 2	Geology and Interpretation of Boring Logs	2-1
	2.1 General Site Geology	2-1
	2.2 Interpretations of the Till Unit from Boring Logs	
	2.2.1 Results	2-3
	2.2.2 Regional Till Surface and Structure Contour Map for Till Surface	2-4
	2.2.3 Comparison with Previous Work	2-4
	2.2.4 Conclusions on Till Surface	2-5
Section 3	DNAPL Observations and Preliminary Evaluation of Remedy	3-1
	3.1 Summary of DNAPL Observations	3-1
	3.1.1 DNAPL in Boring Logs, Wells, Test Pits and Trenches	3-1
	3.1.2 DNAPL Presence in Clay and Silt/Sand Lacustrine Sediments	3-2
	3.1.3 Conceptual Model of DNAPL Migration	3-4
	3.2 Preliminary Remedy Evaluation	3-5
	3.2.1 South Area Interceptor Trench	3-5
	3.2.2 Northwest Slurry Wall and Interceptor Trench	3-5
	3.2.3 DNAPL Recovery System	3-5
Section 4	Groundwater Flow and Quality	4-1
Section 5	Summary of Observations	5-1
Section 6	References	6-1

## Figures

## **Tables**

## Appendices

## **List of Figures**


Site Features and Boring Location Map (after URS 2010)	
Site Geology (after URS 2010)	
Illustration of Difference between SSP&A and URS Interpretations of Till in Boring Logs – Location IT0601	
Example of Elevated Blow Counts at Till Unit – Location FBMW-16D	
Regional Structure Contour Map of Compacted Till	
Site Structure Contour Map of Compacted Till	
Comparison between SSP&A and URS (2010) Interpretations of Elevations of Top of Till	
FBAG's Interpretation of Top of Lacustrine Clay	
Map of Elevation of DNAPL Occurrences	
Historic and Current Conditions in the Vicinity of the Detrex Tributary Outfall	
South Area Interceptor Trench Cross-Section (URS, 2008) showing SSP&A and URS Interpretations of Top of Till	
Geologic Cross-Section Showing Remedy Location with respect to DNAPL Contamination (North-South)	
Geologic Cross-Section Showing Remedy Location with respect to DNAPL Contamination (East-West)	
Shallow Groundwater Contour Map March, 2010 (URS, 2010)	
Deep Groundwater Contour Map, March 2010 (URS, 2010)	
Groundwater Monitoring Well Locations and Analytical Detections Map (URS, 2010)	


## **List of Tables**

Table 1	Summary of SSP&A Interpretations of Elevations of Compacted Till
Table 2	Summary of DNAPL Occurrences in Detrex Borings and Excavations

## **List of Appendices**

Appendix A Boring Logs





This report has been prepared by S.S. Papadopulos & Associates, Inc. (SSP&A) on behalf of the U.S. Environmental Protection Agency (U.S. EPA), Region V, Groundwater Evaluation and Optimization System (GEOS) program for the Detrex facility that is part of the Fields Brook Superfund Site (the site), located in Ashtabula, Ohio. This report presents: 1) an evaluation of the subsurface geology, with a focus on the interpretation of the upper surface of the compacted glacial till based on review of site boring logs; 2) a summary of dense non-aqueous phase liquid (DNAPL) occurrences and potential stratigraphic controls on DNAPL migration, including an evaluation of remedial components currently in place at the site; and finally 3) a review of groundwater flow and quality.

#### 1.1 Background

The Detrex facility is located at 1100 North State Road in Ashtabula, Ohio. Free phase DNAPL occurs mainly in the area of the former lagoons located in the northeast corner of the site. This area was identified as impacted by chlorinated volatile organic compounds (VOCs) and semi-volatile organic compounds¹ in the Phase I Source Control Remedial Investigation for the Fields Brook Superfund site (Woodward-Clyde Consultants, 1995). Recent site investigations delineated an area with free-phase DNAPL based on the occurrence of DNAPL in borings and wells in the area of the former lagoons at the Detrex site (URS, 2010). The 2010 delineated DNAPL area, well/boring locations and components of the source area remedy are shown in Figure 1. Components of the source area remedy shown in Figure 1 include DNAPL recovery wells, a slurry wall, the DS Tributary Groundwater Interceptor Trench and the South Area Groundwater Interceptor Trench (located between the source area and Fields Brook), and small excavations/interceptor trenches along DS Tributary and State Road.

The latest Five-Year Review report for the site (U.S. EPA, 2009) indicated that the continued presence of DNAPL is considered a principal threat at the Detrex facility and its presence at the site may present a risk to Fields Brook, located south and west of the facility. Concerns have been raised about the effectiveness of the source control remedy at the Detrex site, and continued migration of DNAPL from the source area. SSP&A's review has focused on DNAPL occurrences at the source area near the former lagoons and along Fields Brook south of the Detrex facility.

Within this context, S.S. Papadopulos & Associates (SSP&A) has reviewed existing boring logs to provide the U.S. EPA with an updated interpretation of the upper surface of the till unit at the Detrex site, and its potential control over DNAPL migration. In addition, SSP&A has

<sup>&</sup>lt;sup>1</sup> Primary VOCs include 1,1,2,2-trichloroethane, 1,2-dichloroethene, tetrachloroethene, and trichloroethene. Primary semi-VOCs include hexachlorobenzene, hexachlorobutadiene, and hexachloroethane.




compiled information on the elevation, geologic unit, and the location of DNAPL occurrences, to compare to the remedial components in place and perform a preliminary assessment of remedy performance. Finally, observations regarding groundwater contamination by VOCs in the site area were made.



## **Section 2 Geology and Interpretation of Boring Logs**

#### 2.1 General Site Geology

The subsurface materials at the Fields Brook site consist of fill, overlying lacustrine clay/silt laying on top of glacial till and shale bedrock (Figure 2). The lacustrine clay/silt deposits represent the lacustrine plain of nearby Lake Erie and the sediments range from massive clay to silt and silty sand with occasional sand lenses. Bedrock consists of shale that is often thinly bedded and fractured. Deep borings in the site area indicate that the bedrock surface slopes northerly towards Lake Erie and is overlain by less than 10 to about 20 feet of till as shown in the figure below (Woodward Clyde Consultants, 1992)<sup>2</sup>.



Bedrock at the Detrex site occurs at elevations of about 590 to 600 feet MSL (mean sea Similar to the underlying bedrock, on a regional scale the surface of the underlying till slopes towards the north.

<sup>&</sup>lt;sup>2</sup> The trace of this cross section extends from the Ashtabula River southeast of the Detrex site to Lake Erie. The section crosses Fields Brook about 1500 feet east of the Detrex property.

#### 2.2 Interpretations of the Till Unit from Boring Logs

The Detrex site is underlain by the Ashtabula till and possibly older till units overlying shale bedrock. The Ashtabula till is described by White and Totten (1979) as a "calcareous silty clay till, sparingly to moderately pebbly". According to Szabo et al. (1988), the Ashtabula till contains multiple lithofacies. Szabo and Bruno (1997) describe two sub-sequences consisting of a massive matrix-supported diamicton overlain by a stratified diamicton. The upper part of the Ashtabula till has been reworked in places along the ancestral lakeshore of Lake Erie during/prior to deposition of the lacustrine sediments. Based on boring log descriptions alone, it is difficult to distinguish between the reworked till, the stratified till, and the overlying lacustrine deposits. This is due in part to the lack of detail and inconsistencies in the boring logs, but also is a result of the variable character of the top of the till and similarity of the upper till to the lacustrine deposits as described in the boring logs. In addition, the Ashtabula till may overlie older till units which may be difficult to distinguish based on boring log descriptions.

Typically, in a boring log a till is indicated by the following characteristics: clay or silty clay, with little or some unsorted gravel, sand, or angular bedrock fragments; very stiff to very hard consistency; high blow counts (or "N-value") or pocket penetrometer (PP) readings; dry conditions; unsorted and/or unlaminated texture; color from brown (indicates oxidation or leaching) to grey (unoxidized/unweathered); and perhaps most importantly, located immediately above bedrock.

SSP&A evaluated over 160 boring logs to identify the depth/elevation of the till surface. Identification of the top of the till surface was problematic due to the clayey nature of the lacustrine sediments and limitations of the information typically included in the boring logs. The top of the till surface was not easily distinguished as a hard, resistant material, possibly due to reworking of the till post deposition and limited data reported in the logs. As a result, the ability to distinguish between the overlying lacustrine deposits and the till was limited and even in cases where bedrock was encountered, the identification of the upper surface of the till was not always straightforward.

For purposes of this investigation, where the presence of a compacted till is being evaluated to assess the potential for downward migration of DNAPL, the upper surface of the till was picked where the material was resistant and hard (usually characterized by elevated blow counts of 20 or more per foot, or pocket penetrometer readings of 4.5 or higher). In addition, a lack of laminations, evidence of bimodal grain size distribution (clay with cobble/gravel/bedrock clasts), very stiff to very hard consistency, driller/geologist notes on the logs, and stratigraphic position immediately above the shale bedrock were also characteristics used to define the top of the compacted till surface. SSP&A's evaluation included the borings and test pit excavations located at the site, along Fields Brook, and in the regional vicinity of the site. Compacted till was not encountered during excavation and remediation of sediments along Fields Brook;



however, the depth of the excavations and borings provide an indication of the minimum depth to the top of the compacted till surface<sup>3</sup>.

SSP&A's picks for the depth to the top of the fill, lacustrine sediments, till, and bedrock surfaces were compiled and the data visualization software EnviroInsite version 7 (HydroAnalysis, 2009) was used to generate cross sections and aid in data interpretation. The top of the compacted till surface elevations were gridded via ordinary kriging using a default linear variogram and no underlying trend. This study also was aided by the construction of a 3dimensional model of the geologic units, remedy components, and DNAPL observations using Leapfrog Hydro, version 1.3.1 (Aranz Geo Limited, 2010).

#### 2.2.1 Results

SSP&A's stratigraphic picks for the till surface are summarized on Table 1 and the boring logs are included in Appendix A. The top of the compacted till unit could be picked with reasonable certainty at six locations on the Detrex site including five bedrock borings (DETMW01D, DETMW02D, DETMW03D, DETMW17D, DETMW18D) and boring DETSB-13. At the remaining locations on the Detrex site and along Fields Brook, it was determined that compacted till was not encountered in the boring and the upper surface of the till occurs below the bottom elevation of the boring; these locations are indicated by "<" on Table 1. The contact between compacted till and the overlying lacustrine sediments/reworked till also was identified at eighteen regional borings located off site. These locations are identified as FBMW-x on Table 1.

Based on SSP&A's interpretation of the boring logs, the unit identified as till by Detrex's consultant, URS, is the lacustrine clay/reworked till and not a compacted lodgement till overlying bedrock. This is often evidenced by relatively soft sediments (low blow counts) and the observation that a nearby boring that penetrated to deeper depths did not encounter bedrock. Figure 3 shows an example where Detrex consultants identified till at a depth of 12 feet BGS (below ground surface) due to a color change and the presence of rock fragments in the boring; however, the blow counts remain relatively low to at least 22 feet depth and below that depth do not increase much above 20 counts/foot. This can be compared to boring FBMW-16D where the blow counts in the till material exceed 30 counts/foot (Figure 4). Identification of the till is difficult as a result of the post-depositional reworking of the till followed by deposition of overlying lacustrine clay/silt.

<sup>&</sup>lt;sup>3</sup> Compacted till elevations were estimated along cross sections presented in Conestoga-Rovers, 2001; however due to poor reproduction quality of maps, specific boring locations could not be deciphered. The maximum compacted till depths were determined based on the Conestoga-Rovers cross sections and point data were assigned based on available/legible information for TT- and TP- locations. These top of compacted till elevation locations are therefore approximate. Additional detail is found in Table 2 for the TT- and TP- locations.

#### 2.2.2 Regional Till Surface and Structure Contour Map for Till Surface

A structure contour map of the surface of the compacted till on a regional scale and the posted data values are shown in Figure 5. The contour lines are based on kriging the top elevation of the compacted till at 24 locations where the till elevation was identified and the 19 locations on or near the site where deeper borings could provide a maximum till elevation. Regionally, the top of the compacted till surface slopes towards the north, with elevations of about 630 feet MSL and higher south of Fields Brook to elevations less than 600 feet MSL north of the Detrex facility. A depression in the top of the till surface occurs along Fields Brook which suggests that the brook may occupy a post-glacial erosional feature or other depression in the till surface. As a result, the thickness of the compacted till may be minimal along Fields Brook. The direction of flow of DNAPL from the source area at the former lagoons, if controlled by the till surface as shown in Figure 5, would be primarily towards the north and possibly northeast.

A structure contour map of the till surface on and near the Detrex site is shown in Figure 6. The elevation of the top of the compacted till surface is about 610 feet MSL in the area of the former lagoons with the surface sloping towards the north and also towards Fields Brook in the southern portion of the site. The till 'picks' shown in Figures 5 and 6 are undeniably based on subjective interpretation of information presented in the boring logs, and these same boring logs could be reinterpreted resulting in a few-foot difference in the top of the till surface elevation. However, several iterations of review of the top of the till surface elevation yielded similar results and re-interpretation of borings where the pick was particularly uncertain did not significantly alter the structure contour map for the compacted till surface. Within this context, we therefore consider that the interpretations presented in Figures 5 and 6 represent an appropriate estimate of the surface elevations of the compacted till.

#### 2.2.3 Comparison with Previous Work

Significant differences exist between the SSP&A till elevations and previous work by URS, as shown in Figure 7. Notable exceptions are that: 1) the SSP&A interpretation does not include an elevated ridge of till between the source area and Fields Brook; and 2) the till surface is significantly lower in elevation in the southwest part of Detrex site, particularly in the area near the South Area Groundwater Interceptor trench and Fields Brook. A comparison of the SSP&A and URS top of the till surface grids indicates that the top of the SSP&A till surface is lower by a mean value of 9.7 feet, within a range of -4.4 (i.e. 4.4 feet higher) to +20 feet lower than the URS till surface.

Following the 2005 discovery of DNAPL along Fields Brook, a number of borings were advanced in the area north of Fields Brook on the Detrex site and FBAG (2005) prepared a structure contour map of the top of the lacustrine clay based on these borings (reproduced as Figure 8). Of note is the observation that top elevation of the lacustrine clay identified by FBAG is similar to the top elevation of the till as identified by URS in the area of the South Interceptor Trench.



#### 2.2.4 Conclusions on Till Surface

SSP&A reviewed over 160 boring logs to define the upper surface of compacted till at the Fields Brook Site. Considerable uncertainty remains in the till elevation stratigraphic picks due to limited details in the boring logs, post-deposition reworking of the till, and similarity with the overlying lacustrine sediments. The SSP&A interpretation of the top of the till surface indicates that regionally, the till surface slopes towards the north-northwest towards Lake Erie. At the site, the surface slopes primarily towards the north and northeast, away from the area of the former lagoons, with a depression in the till surface occurring in the southern portion of the site along Fields Brook. Evidence for the presence of a depression below the former lagoon area or for a significant ridge between the former lagoon area and Fields Brook was not observed.

# **Section 3 DNAPL Observations and Preliminary Evaluation of Remedy**

Several events and investigations have presented evidence of the presence of DNAPL within the subsurface at the Detrex facility and in its vicinity, as reported in several documents, for example:

- Woodward Clyde 1997, Supplemental Site investigation;
- Woodward Clyde 1997, Final SCRI Report, Source Control Operable Unit, Fields Brook Site, Ashtabula, Ohio;.,
- Conestoga-Rovers & Associates 2001, FBAG DNAPL Investigation;
- Fields Brook Action Group 2005, DNAPL investigation;
- URS, 2008. Southern Area Groundwater Interceptor Trench Construction & Installation Report, Detrex; and
- U.S. EPA 2009, Second Five-Year Review Report for Fields Brook Site.

#### 3.1 Summary of DNAPL Observations

#### 3.1.1 DNAPL in Boring Logs, Wells, Test Pits and Trenches

SSP&A compiled observations of DNAPL in boring logs, monitoring wells, test pits, and trenches at the source area and along Fields Brook to determine the elevation of DNAPL in the subsurface in these areas. Soil data were also reviewed to identify soil concentrations that are consistent with the presence of DNAPL<sup>4</sup>. These observations collectively indicate the elevation at which DNAPL was mobile at some point in the past (and possibly present).

In some instances, DNAPL was reported to collect in the bottom of a monitoring well, indicating the minimum elevation of the top of the mobile DNAPL at that location. Such observations can be used to evaluate the potential for DNAPL migration and provide a simple means to evaluate the efficacy of remedial components. The elevations of DNAPL occurrences compiled for the site are summarized in Table 2 and the range of elevations of DNAPL occurrences based on boring logs and/or well observations are shown in Figure 9.

DNAPL currently exists as a mobile phase in the area of the former lagoon, as evidenced by the accumulation of free-phase DNAPL into wells located in this area. Wells with historic

<sup>&</sup>lt;sup>4</sup> Soil concentrations of VOCs and SVOCs were evaluated to determine if the concentrations were consistent with the presence of DNAPL based on the method provided by Kueper and Davies (2009). A soil sample from location GP44-01 was determined to be consistent with the presence of DNAPL at 4.5 to 5 feet BGS. Additional soil samples that were consistent with the presence of DNAPL were located along Fields Brook west of State Road including location GP4-01 (at a sampling depth of 6.5-7 ft), GP11-01 (at a sampling depth of 6.5-7.5 ft), GP21-01 (at a sampling depth of 5-6 ft) and GP25-01 (at a sampling depth of 5-6 ft).



free-phase DNAPL accumulations include DETMW-05S, DETMW-06S, DETMW-07S, DETMW08S, DETMW-10S, and RMSMW02S. The driving hydraulic head of DNAPL in the former lagoon area was at about 632 feet MSL in 1997 (well DETMW07S; Woodward Clyde 1997). In 2010, 2.3 feet of DNAPL were observed in the bottom of boring DPT-7/0209; 0.6 feet of DNAPL in the bottom of well DPT-3/0209, and 1 foot of DNAPL in the bottom of well DETMW-10S. The accumulation of DNAPL in the bottom of these wells indicates that the minimum hydraulic head of DNAPL in the source area is at least 617 feet MSL at DPT-7/0209; at least 622.5 feet MSL at DPT-3/0209; and at least 621 feet MSL in DETMW-10S.

DNAPL with measurable thickness was observed predominantly in the north-east corner of the site near the former lagoon, in well DETMW-12S located in the vicinity of the Detrex Tributary outfall, and along Fields Brook. The upper elevation of observed DNAPL in the former lagoon area was 632 feet MSL measured in well DETMW07S. The elevation of the base of DNAPL observed at locations near the former lagoon ranges from about 623 to 611 feet MSL. Observation of DNAPL in DPT-12/0209 at 611 feet MSL is significant because it identifies the lowest elevation of DNAPL observed near the source area. Borings installed by URS in 2009 did not identify the base depth of DNAPL in the source area since the borings were terminated when DNAPL was encountered (URS, 2010). As a result, the base elevation of occurrence of DNAPL in the source area has not been fully defined.

The upper elevation of DNAPL along Fields Brook occurs at about 617 feet to 606 feet MSL (Figure 9). The base of DNAPL along Fields Brook occurs at elevations from about 617 to about 603 feet MSL.

Following the discovery of DNAPL along Fields Brook during routine maintenance activities in 2005, a number of test pits and borings were installed between the source area and Fields Brook. No observations of free-phase DNAPL were noted in any of these installations. In addition, an approximately 1,200 foot-long linear trench was excavated along Fields Brook on the north side of the floodplain. The depth of excavation of this trench was not reported but it appears to be about 6 feet deep based on a photograph (FBAG, 2006). Free-phase DNAPL was not observed in the trench excavation; however, a sheen was observed at various locations in the trench (FBAG, 2006a), as well as elevated PID readings, and odors consistent with Detrex's DNAPL (FBAG, 2006b). The locations of these observations in the trench are unknown, but if they were observed in the area distal from the Detrex Tributary outfall, this would suggest that DNAPL that had migrated from the upland source area through lacustrine sediments was encountered near the base of the trench.

#### 3.1.2 **DNAPL Presence in Clay and Silt/Sand Lacustrine Sediments**

In all cases, DNAPL has been observed only within the lacustrine unit both at the source Within the lacustrine sediments, the DNAPL was observed in area and along Fields Brook. sand/silt as well as in clay sediments. At locations along Fields Brook, the DNAPL was most commonly observed in silt/sand materials above the lacustrine clay, however, the thickest occurrence of DNAPL along Fields Brook was observed within the lacustrine clay unit (several feet of DNAPL in borings GP31-01 and GP32-01). In the source area, DNAPL has been observed within sediments ranging from sand (e.g., DPT-03/0209) to silty clay (e.g., DPT-10/0209).



The DNAPL observed along Fields Brook either migrated: 1) through lacustrine sediments from the source area, or 2) through lacustrine sediments from the unlined Detrex tributary outfalling near location DETMW-12S, or a combination of both. As discussed below, it may have done both to some extent at various times in the past.

A historical air photo of the Detrex facility (Figure 10) shows that the main channel of Fields Brook near the Detrex Tributary outfall was different from its current location; and the outfall of the Detrex Tributary appears to have flowed westerly towards the confluence with Fields Brook (as indicated by the white-shaded path in Figure 10). These two reaches appear to have been altered so that the current location of Fields Brook occupies a portion of the historic channel of the Detrex Tributary. The 2001 DNAPL removal limits conducted as part of the site remedy excavated the historic channel of the Detrex Tributary. A comparison of the 1970 photo with the occurrences of DNAPL along Fields Brook indicates that some of the DNAPL occurrences are likely due to migration of DNAPL originating along this surface water route.

Test trenches TT19-01 and TT18-01 appear to transect the former location of the Detrex Tributary; the logs for these installations show about four feet of 'clean' silt (PID=0) overlying clay with DNAPL on/near the clay surface. The area is thought to have been regraded/reworked during reconfiguration of the former Detrex Outfall, and it is not known if the 'clean' silt was fill material or if it is native streambed sediments. If the silt is native undisturbed streambed sediments, then the DNAPL did not originate within the stream bed at that locations but it could have migrated as the result of pooling at the former Detrex Outfall and migrated along the clay surface to lower elevations. If this is the case, the migration has not been towards the east as evidenced by location TT17-01 (located east of TT18-01) which had PID readings of 0 in the silt and underlying clay.

The 2005 DNAPL observations along Fields Brook were reported to occur at depths of 6-8 feet below ground surface. If the depth of the 2001 excavations along the former Detrex Tribuary extended below the elevation of the 2005 occurrences of DNPL then these observations are not consistent with a surface water discharge source from the Detrex Tributary for the 2005 DNAPL observations. Unfortunately, information on the depth of the 2001 excavations, in addition to the specific depth of the 2005 observations is sparse and SSP&A has been unable to obtain specific details.

The DNAPL observations along Fields Brook are all lower in elevation, or similar elevation to the DNAPL occurrences attributed to the Detrex Tributary source (Figure 9). This observation is not inconsistent with a source along the Detrex Tributary; however, sufficient details are not available to determine if all the DNAPL observed along Fields Brook can be attributed to this source. The elevations of DNAPL are also consistent with a source through the lacustrine sediments from the former lagoon area.

A number of test pits and borings were installed in the area between the Detrex operations area and Fields Brook following the 2005 discovery of DNAPL along Fields Brook. DNAPL was not identified in any of these installations; however, DNAPL could occur in small, isolated, and highly unpredictable fractures, bedding planes, and lenses in the lacustrine sediments. The likelihood of intercepting such a feature during random excavations is minimal at best. In addition, the stringers of DNAPL appear to be very limited in lateral extent. For



example, at boring GP44-01 DNAPL was determined to be present based on soil concentrations (also consistent with crystalline material observed in the boring log and odor). Boring GP44A-01, presumably located close to GP44-01, did not contain particularly elevated OVA reading and gave no indication of the nearby presence of DNAPL.

#### 3.1.3 Conceptual Model of DNAPL Migration

DNAPL has been observed in the clay, sand, and silt sediments of the lacustrine unit in the source area and along Fields Brook. The lenses, fractures and bedding planes in the lacustrine sediments provide a pathway for migration of pooled DNAPL from the source area, which could potentially reach Fields Brook, irrespective of the till surface. Also, DNAPL near the outfall of the Detrex Tributary may be attributed to surface drainage from the former lagoon area via the former Detrex Tributary.

The sediments underlying the source area are clay-rich lacustrine deposits, with some sandy/silty lenses, overlying till and bedrock. DNAPL migration through such sediments would be expected to first migrate to more permeable materials that are accessible, followed by migration into fractures, bedding planes, and thin lenses as capillary pressures increase. Evidence of lateral DNAPL migration within the lacustrine sediments is found in RMI monitoring well RMSMW02S, located on the adjacent property north of the Detrex site on the adjacent property, where an estimated 10 feet of DNAPL was reported in the bottom of the well. The DNAPL was found within a zone of more permeable clayey silt with silt and fine sand laminations at a depth of about 15 to 24 feet BGS (Eckenfelder, 1990).

DNAPL has not been identified at the lacustrine/till contact in the source area and DNAPL has not been observed in the till or bedrock, however, only a limited number of borings penetrate to these underlying geologic units. As a result, there is no clear evidence that DNAPL movement from the former lagoon area towards Fields Brook is controlled by the till surface.

If the till surface is the lower boundary of DNAPL migration from the source area of the former lagoons, DNAPL may have migrated towards the north beneath and beyond the RMI property. The slight north-eastern slope of the till in the source area suggests that DNAPL migration may have occurred to the northeast beneath the Elkem site and possibly the former TDI site. DNAPL migration could also occur from the source area towards the west-southwest and reach Fields Brook where a depression in till elevation is observed.

The presence of pooled DNAPL at the source area indicates that DNAPL is currently mobile and that migration of DNAPL away from the source area is ongoing. Migration of DNAPL laterally away from the source area will continue to occur within the lacustrine sediments, and possibly through the underlying till and bedrock, until the DNAPL achieves a state of residual saturation. Residual saturation of DNAPL will be achieved by the continued lateral (and possibly vertical) migration of DNAPL away from the source area. Downward migration of DNAPL to the till surface, possibly along the till surface, and into bedrock may have occurred in and near the area of the former lagoons. The ability of the till to impede further downward migration of DNAPL to the bedrock through fractures in the till is unknown.

#### 3.2 Preliminary Remedy Evaluation

To evaluate the adequacy of the remedy at addressing DNAPL present at the site, the elevations of DNAPL observations were compared to the elevations of the remedy components.

#### 3.2.1 South Area Interceptor Trench

A cross-section prepared by URS showing the elevation of the South Area Interceptor Trench is included as Figure 11 (the location of the South Area Interceptor Trench and it's base elevation are shown in Figure 9; base elevations range from 615 to 614.5 feet MSL along segment #3, from 614.5 to 619 feet MSL along middle segment #1, and from 615 to 623 feet MSL along the western segment, segment #2). Figures 12 and 13 show North-South cross-section A-A' and East-West cross-section B-B' (the locations of the cross-sections are shown on Figure 6). The range of elevations where DNAPL was observed in the boring logs and/or wells are shown in Figures 12 and 13 (and described in Table 2). Borings shown on the cross-sections are projected over a maximum distance of 80 feet.

Figure 12 shows that the elevation of the base of the South Area Interceptor Trench is higher in elevation than the DNAPL observed near the Detrex source area (well DPT-12/0209 with DNAPL observed between 611 and 615 feet MSL), and close to the elevation of the DNAPL observed along Fields Brook. The South Area Interceptor trench therefore may not be sufficiently deep to capture migration of DNAPL from the source area towards Fields Brook.

#### 3.2.2 Northwest Slurry Wall and Interceptor Trench

Figure 13 shows that the elevation of the base of the slurry wall located west of the former lagoon area is deeper than the DNAPL elevations observed near the source. In addition, the slurry wall appears to be keyed into compacted till. Assuming the compacted till acts as a confining unit to DNAPL migration, the slurry wall depth appears to be adequate. The horizontal extent of the slurry wall however, may not limit the migration of DNAPL around the ends of the slurry wall. The base elevation of the DS Tributary Groundwater Interceptor Trench at 614 feet appears to be higher in elevation than the elevation of DNAPL observed in the former lagoon area, and is not likely to fully capture DNAPL migrating westward from the source area. Monitoring data are currently not present in close proximity to the extremities of the slurry wall.

#### 3.2.3 **DNAPL Recovery System**

A pilot system of DNAPL recovery wells and SVE system in the area of the former lagoons has been operated at the Detrex site since 2002. The recovery wells have collected a total of approximately 16,000 gallons since operation began. DNAPL recovery from these wells has declined and the system has been plagued by operation and maintenance problems (URS, 2008).

## Section 4

## **Groundwater Flow and Quality**

The results of monitoring during 2010 (URS, 2010) at the Detrex site are summarized in Figures 14 through 16 (water levels measured in wells and results of water quality analyses). The direction of shallow groundwater flow at the site is towards the north (DS Tributary) and south (Fields Brook) from an area of mounded groundwater in the central part of the site. Shallow groundwater flow at the adjacent RMI Titanium Company Sodium Plant, located directly north of the Detrex site, indicates that shallow groundwater generally flows towards the southeast across that property towards the DS Tributary. The direction of groundwater flow in the deeper groundwater is towards Fields Brook; however on a region scale, the deep groundwater flows towards the Ashtabula River and Lake Erie (towards the west and north).

Figure 16 (after URS 2010) shows that in January 2010, in all but one of the monitoring wells that do not contain DNAPL (DETMW-04S), concentrations of the contaminants of concern were below detection limits. Historic concentrations of TCE in well DETMW-04S range from 32,000 to 51,000  $\mu$ g/L. URS (2010) indicates that TCE was found in well DETMW-10S at 70,500  $\mu$ g/L in January 2010, however TCE is not usually detected in other monitoring wells downgradient of this well. Historic detections of TCE include at 20  $\mu$ g/L in well IT-0601 in September 2006, and detections in wells MW-17S (up to 1.6  $\mu$ g/L), MW-17D (26.1  $\mu$ g/L), and MW-18D (1.71  $\mu$ g/L). The presence of TCE in the deep wells MW-17D and MW-18D raises concern that VOC-contaminated groundwater may be present at depth at the site and not currently monitored by existing wells.

The concentration of VOCs detected in groundwater collected in the South Area Interceptor trench sumps indicate that concentration of VOCs captured in South Area Interceptor Trench Sump #1 and #3 are minimal (excluding concentrations impacted by Frac tank water pumped into sump #1 during 2009). The concentration of VOCs detected in groundwater collected in Sump #2 is up to about 300  $\mu$ g/L.

The presence of DNAPL at the site is not reflected in the groundwater quality of currently monitored wells. This may be due to the wells not screened at sufficient depth to capture the plume, and/or the plume exists in isolated zones within the subsurface that are not in hydraulic connection to the existing monitoring wells.

## **Section 5 Summary of Observations**

A summary of observations made as part of this study is listed below:

- 1. SSP&A reviewed over 160 boring logs to define the top of the compacted till surface at the Fields Brook Site. SSP&A prepared a structure contour map of the till surface based on the identification of the compacted till in 24 boring logs, in combination with 19 deeper borings/excavations that did not penetrate the till, but provided a maximum till elevation
- 2. Considerable uncertainty remains in the till elevation stratigraphic picks due to incomplete details in the boring logs, post-depositional reworking of the till, and similarity with the lacustrine sediments. SSP&A's interpretation of the compacted till surface indicates that the surface slopes primarily towards the north and northeast away from the area of the former lagoons. A depression in the till surface occurs in the southern portion of the site along Fields Brook.
- 3. Evidence for the presence of a till depression below the former lagoon area, or for a significant ridge between the former lagoon area and Fields Brook, was not observed.
- 4. Interceptor trench borings by URS identified till based on geoprobe borings at an elevation of about 620 feet MSL. FBAG (2005) conducted a geoprobe investigation in 2005 and identified the top of the lacustrine clay at about the same elevation as URS picks the top of the till in the area of interceptor trench.
- 5. SSP&A compiled data on the elevation of DNAPL observed in borings/test pits. DNAPL is found within the lacustrine unit at elevations ranging from 632 to about 603 feet MSL. Elevations in the source area range from 632 to 611 feet MSL. Elevations of DNAPL near Fields Brook range from about 617 to 603 feet MSL.
- 6. DNAPL has not been observed at the lacustrine/till contact, or within the till or bedrock, although there are few sufficiently deep borings to identify this. As a result, there is no clear evidence that DNAPL movement from the former lagoon area is controlled by the till surface. DNAPL may have migrated from the source area within the lacustrine sediments toward Fields Brook, irrespective of the till surface.
- 7. DNAPL currently exists as a mobile phase in the area of the former lagoon, as evidenced by the accumulation of free-phase DNAPL in wells located in this area. Wells with historic free-phase DNAPL accumulation include DETMW-05S, DETMW-06S, DETMW-07S, DETMW08S, DETMW-10S, and RMSMW-02S.
- 8. Evidence of lateral DNAPL migration within the lacustrine sediments is found in monitoring well RMSMW02S, located north of the Detrex site on the adjacent property, where an estimated 10 feet of DNAPL was reported in the bottom of the well. DNAPL was found within a zone of more permeable clayey silt with silt and fine sand laminations.
- DNAPL migration may be ongoing through silt/sand lenses, which occur throughout the lacustrine sediments, and also through fractures and bedding planes in the lacustrine sediments.




- 10. The former Detrex Outfall and Detrex Tributary is a very likely source of some DNAPL found along the historic channel of the Detrex Tributary: however, the extent of DNAPL migration from this documented source is unknown.
- 11. The elevation of DNAPL observations along Fields Brook are all lower, or similar to, the elevation of DNAPL occurrences attributed to the Detrex Tributary source. This observation is not inconsistent with a source along the Detrex Tributary; however, sufficient detail is not available to determine if all DNAPL observed along Fields Brook can be attributed to this source, and the elevations of DNAPL can also be interpreted as consistent with a source through the lacustrine sediments from the former lagoon area.
- 12. The base of the South Area Groundwater Interceptor Trench is higher in elevation than the base of DNAPL observation in the source zone. The South Area Interceptor trench may not, therefore, be sufficiently deep to capture DNAPL migrating from the source area toward Fields Brook. In addition, DNAPL may have migrated through the lacustrine clay towards Fields Brook at an elevation lower than the bottom of the South Area Groundwater Interceptor Trench.
- 13. The elevation of the base of the slurry wall located west of the former lagoon area is deeper than the DNAPL elevations observed near the source. In addition, the slurry wall appears to be keyed into compacted till. Assuming the till acts as a barrier to further vertical (downward) DNAPL migration, the slurry wall depth appears to be adequate. The horizontal extent of the slurry wall however, may not limit the migration of DNAPL around the ends of the slurry wall: this is particularly salient given the broadly northward dipping character of the till surface.
- 14. The direction of shallow groundwater flow at the site is toward the north (DS Tributary) and south (Fields Brook) from an area of mounded groundwater in the central part of the site. The vertical hydraulic gradient is downward.
- 15. Groundwater with significant concentrations of VOCs is not observed outside of the source area. This may be due to a lack of monitoring points screened at appropriate depths, or the presence of limited zones of VOC-contaminated groundwater that are deeper than the South Area Interceptor Trench and/or are not in communication with the existing monitoring wells.

## Section 6 References

- Limited Hydro Aranz Geo (2010)Leapfrog version 1.3.1, http://www.leapfroghydro.com/hydro/about-hydro
- Conestoga-Rovers, 2001. Summary of DNAPL Investigations Activities, Fields Brook superfund Site, Ashtabula, Ohio. (SDMS 369208)
- Conestoga-Rovers, 2003. Final Construction Report Sediment Operable Unit and Floodplain/Wetlands Operable Unit, Volume 4, Fields Brook Superfund Site, Ashtabula, Ohio. (SDMS 323723)
- Eckenfelder, 1990. RCRA Facility Investigation Report, RMI Sodium Plant, Ashtabula, Ohio. June.
- Fields Brook Action Group (FBAG). Fields Brook Superfund Site, Ashtabula, Ohio, Fields Brook Action Group Report of 2005 DNAPL Investigation, September 30, 2005. (SDMS 276917)
- FBAG 2006a. Presentation by Fields Brook Action Group Regarding DNAPL Delinaeation Study/ Detrex Source Control. February 8, 2006. (SDMS 259528)
- FBAG 2006b. Statement of Position to the United States Environmental Protection Agency on Behalf of the Members of the Fields Brook Action Group Concerning Detrex DNAPL Contamination in Exposurure Unit 8, Fields Brook Superfund Site. September 5. (SDMS 259530)
- HydroAnalysis (2009) EnviroInsite version 7. www.enviroinsite.com
- Kueper, B.H. and K.L. Davies. 2009. Assessment and delineation of DNAPL source zones at hazardous waste sites. http://www.epa.gov/nrmrl/pubs/600r09119/600r09119.pdf (October 14, 2010).
- Szabo, J. P., C. H. Carter, P. W. Bruno, and E. J. Jones, 1988. Glacial and Postglacial Deposits of Northeastern Ohio. Ohio Journal Science, volume 88, number 1, pages 66-74.
- Szabo J. P., and P. W. Bruno, 1997. Interpretation of Lithofacies of the Ashtabula Till along the south shore of Lake Erie, northeastern Ohio. Canadian Jour. Earth Sci., Vol. 34, no. 1, pages 66-75.
- U.S. EPA, 2001. Explanation of Significant Differences Modifying the Decision for the sedimanet and Floodplain/Wetland Operable Units to Address DNAPL-Impacted Soils and Sediments, Fields Brook Superfund Site. Ashatabula, Ohio.



- U.S. EPA, 2009. Second Five-Year Review Report for Fields Brook Site. Ashatabula, Ohio, June.
- URS, 2008. Interim Operations and Maintenance Manual, Detrex RD/RA Source Control Area, Detrex Facility, Ashtabula, OH. June 2008. (SDMS 325300).
- URS, 2008. Southern Area Groundwater Interceptor Trench Construction & Installation Report, Detrex January 2008 (SDMS 325292)
- URS, 2009. Subsurface Mapping of Top of Ashtabula Till (Revised). Letter to U.S. EPA dated April 2.
- URS, 2010. Sediment and DNAPL Delineation Report, Detrex Facility, Detrex Source Control Area, Fields Brook Superfund Site, Ashtabula, Ohio, Docket No. V-W-98-C-450, May 2010.
- White, G. W., and S. M. Totten, 1979. Glacial Geology of Ashtabula County, Ohio. State of Ohio Department of Natural Resources, Division of Geological Survey, Report of Investigations Number 112, 48 pages.
- Woodward-Clyde Consultants, 1992. Fields Brook Ashtabula, Ohio, Source Control Operable Unit Remedial Investigation Phase 0. (SDMS 91835)
- Source Control Operable Unit RI/FS, Fields Brook Woodward-Clyde Consultants, 1995. Superfund Site, November 1995.
- Woodward Clyde, 1997. Supplemental Site investigation, March (SDMS 91844)
- Woodward Clyde, Final SCRI Report, Source Control Operable Unit, Fields Brook Site, Ashtabula, Ohio. May, 30, 1997 (SDMS 91855)






Figure 1 Site Features and Boring Location Map (after URS 2010)




Figure 2 Site Geology (after URS 2010)



Project: - Detrex Project Location:

Project Number: Detrex

## Log of Boring IT0612

Sheet 1 of 1

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 18.00 bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		




Figure 3 Illustration of Difference Between SSPA and URS Interpretation of Till in Boring Logs - Boring IT-0612

Report: URS\_CLEV\_3COL\_S; File: DETREX IT BORINGS.GPJ; 9/20/2006 | IT0812

Figure 4 Example of Elevated Blow Counts at Till Unit, Boring FBMW-16D




Figure 5 Regional Structure Contour Map of Compacted Till





Figure 6 Site Structure Contour Map of Compacted Till








Figure 7 Comparison between SSP&A and URS (2010) Interpretations of Elevations of Top of Till





Figure 8 FBAG's Interpretation of Top of Lacustrine Clay





Note: 1) The exact location of DNAPL observation in trenches is unkown. The center of the trenches was picked as a reference.

2) Elevations of 2005 DNAPL observations are approximate (see Table 2)

Figure 9 Map of Elevation of DNAPL Occurrences




Figure 10 Historic and Current Conditions in the Vicinity of the Detrex Tributary Outfall





Figure 11 South Area Interceptor Trench Cross-Section (URS, 2007) showing SSP&A and URS Interpretations of Top of Till




Notes:

Figure 12 Geologic Cross-Section Showing Remedy Location with respect to DNAPL Contamination (North-South)

<sup>1-</sup> See Table 2 for details regarding DNAPL elevations. Elevations of 2005 DNAPL observations (2005 obs x) are approximate.

<sup>2-</sup> Borings are projected over a distance of 80 ft.



#### Notes

- 1- See Table 2 for details regarding DNAPL elevations.
- 2- Borings are projected over a distance of 80 ft.

Figure 13 Geologic Cross-Section Showing Remedy Location with respect to DNAPL Contamination (East-West)




Figure 14 Shallow Groundwater Contour Map, March 2010 (after URS, 2010)




Figure 15 Deep Groundwater Contour Map, March 2010 (after URS, 2010)




Figure 16 Groundwater Monitoring Well Locations and Analytical Detections Map (after URS, 2010)




Table 1
Summary of SSPA Interpretations of Elevations of Compacted Till

Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Till Depth (feet, bgs)	Boring Depth (feet, bgs)	Bottom Boring Elevation (feet, MSL)	Till Elevation (feet, MSL)	Comment
DETMW-01D	2470441	817045	635.41	19	53.50	581.91	616	Hard, moist, gray with trace red mottling, Silty Clay. Trace sand and gravel. Hits bedrock (shale); same loc as FBMW11D
DETMW-02D	2470436	816486	633.63	27	50.30	583.33	607	very stiff, dry to moist gray Silty Clay; trace sand and coarse gravel. Hits bedrock (shale) Bedrock well; same as FBMW12D
DETMW-03D	2470442	816084	625.95	14	40.10	585.85	612	p.p increases from (.2-1.5) to ~5. Hard, moist gray silty clay; trace sand and f-m gravel. Hits bedrock (shale); same loc as FBMW13D
DETMW-04S	2470831	817241	633.00		15.00	618.00	< 609	no till
DETMW-05S	2471432	817240	636.50		20.00	616.50	< 617	no till
DETMW-06S	2471758	817151	636.25		17.50	618.75	< 618	no till
DETMW-07S	2471479	816948	635.50		20.00	615.50	< 617	no till
DETMW-08S	2471271	817072	636.25		20.00	616.25	< 619	no till
DETMW-09S	2471410	816738	634.50		17.50	617.00	< 616	no till
DETMW-10S	2471429	816632	634.50		17.50	617.00	< 617	no till
DETMW-11S	2471117	816449	634.00		20.00	614.00	< 614	no till
DETMW-12S	2471474	815843	622.20		12.00	610.20	< 610	possible till; hard clay tr c sand f angular gravel
DETMW-17D	2471429	816337	633.00	21	48.00	585.00	612	Boring extends to BR, but till pick not clear and picked at 21' based on nearby boring DETMW18D Top of bedrock at 36' = 597'; High PID w/in this till unit @ 22 to 25' BGS
DETMW-17S	2471451	816381	634.30		15.00	619.30	< 609	hard, moist, FID=100
DETMW-18D	2471846	816428	635.00	23	49.00	586.00	612	Bedrock well; very stiff, moist, gray clay with sand, trace gravel (becomes very stiff to hard at 612). Hits bedrock (shale) coord obtained by digitizing Feb17 1997 Woodward Clyde Fig. 5
DETMW-18S	2471843	816388	634.50		15.00	619.50	< 620	till possible
DETMW-20S	2470919	817316	632.00		20.00	612.00	< 612	didn't hit bedrock; till possible at 18.5 feet
DETMWS-1D	2470397	816178	630.21					no log
DETMWS-1S	2470400	816179	630.21					no log
DETMWS-2D	2470388	816369	632.05					no log
DETMWS-2S	2470392	816370	632.05					no log

Table 1
Summary of SSPA Interpretations of Elevations of Compacted Till

Location ID	Easting	Northing	Ground Surface	Till Depth	Boring Depth	Bottom Boring	Till Elevation	Comment
	(NAD_1927)	(NAD_1927)	Elevation (feet, MSL)	(feet, bgs)	(feet, bgs)	Elevation (feet, MSL)	(feet, MSL)	
DETMWS-3D	2470387	816573	634.49	2907	290/	(1001, 11102)		no log
DETMWS-3S	2470388	816577	634.49					no log
DETMWS-4D	2470381	816952	637.79					no log
DETMWS-4S	2470381	816957	638.22					no log
DETSB-13	2470735	815988	629.20	15	20.00	609.20	614	Hard, moist, gray Clay with f-c gravel. (underlying firm, moist to wet silty clay). FID decreases from ~1000 to ~0 at 614 ft.  Doesn't hit bedrock. Till picked based on hard, clay, fc gravel no blow counts or pp though
DETSB-14	2470577	817104	634.00		20.00	614.00	< 614	no till
DETSB-15	2471149	817176	635.80		20.00	615.80	< 616	no till
DETSB-16	2470938	816735	636.01		20.00	616.01	< 616	no till
DETSB-19	2471739	817297	635.20		15.00	620.20	< 620	no till
DETWMW-1R	2470440	816190	630.00		15.00	615.00	< 615	no till
DETWMW-2R	2470443	816397	632.00		15.00	617.00	< 617	no till
DETWMW-3R	2470427	816600	636.00		19.00	617.00	< 616	no till
DETWSB-1	2470317	815893	623.20			623.20	< 623	no log
DETWSB-2	2470316	816014	624.88			624.88	< 625	no log
DETWSB-3	2470389	816758	635.53			635.53	< 636	no log
DETWSB-4	2470361	817166	632.30			632.30	< 632	no log
DETWSB-5	2470390	817210	632.63			632.63	< 633	no log
DP-01	2471872	817081	635.50		24.00	611.50	< 612	low blow counts, wet, v stiff tr sand and silt
DP-02	2471891	816988	635.50		24.00	611.50	< 612	higher blow counts at 21', hard clay some silt f sand
DP-03	2471854	816926	635.50		24.00	611.50	< 612	low blow counts, sitff wet clay some silt and f sand
DP-04	2471287	816848	634.50		24.00	610.50	< 612	higher blow counts at 21' v stiff
DP-05	2470950	816927	633.00		24.00	609.00	< 609	low blow counts, till possible at ~22'
DP-06	2470950	817237	633.00		24.00	609.00	< 906	higher blow counts at 21', but wet
DPT-01	2470526	817473	636.70		12.00	624.70	< 625	m stiff, sity clay maybe till @9.5 ?
DPT-02	2470488	817406	636.70		16.00	620.70	< 621	till possible v stiff to hard, clay some rx frag low plasticity
DPT-03	2470501	817368	635.80		16.00	619.80	< 620	till possible m stiff clay some rx frag low plasticity homogeneous
DPT-04	2470389	817367	634.10		20.00	614.10	< 614	till possible at 18.5', m stiff moist silty clay
DPT-05	2470657	817416	635.20		16.00	619.20	< 619	possible till at14.5 but moist, brown silty clay

Table 1
Summary of SSPA Interpretations of Elevations of Compacted Till

			Ground	Till	Boring	Bottom		
1 4i ID	Easting	Northing	Surface	Depth	Depth	Boring	Till Elevation	0
Location ID	(NAD_1927)	(NAD_1927)	Elevation	(feet,	(feet,	Elevation	(feet, MSL)	Comment
	, – ,	. – ,	(feet, MSL)	bgs)	bgs)	(feet, MSL)	,	
DPT-06	2470730	817428	634.80		20.00	614.80	< 615	possible till at13' with increasing gravel
DPT-07	2470811	817427	632.80		16.00	616.80	< 617	no till, soft laminated
DPT-08	2470947	817502	637.00		16.00	621.00	< 621	no till
DPT-09	2470109	817187	626.70		14.00	612.70	< 613	no till, soft laminated
DPT-1/0209	2471661	816753	634.00		20.00	614.00	< 614	no till
DPT-10	2470192	817212	628.50		16.00	612.50	< 613	no till, soft laminated
DPT-10/0209	2471226	817195	633.00		15.00	618.00	< 618	no till
DPT-11	2470243	817216	628.20		13.00	615.20	< 615	no till, soft, silty
DPT-11/0209	2471060	817279	634.00		25.00	609.00	< 609	no till
DPT-12	2470350	817172	632.40		27.00	605.40	< 605	till possible, stiff silty clay, little rx frag tr gravel
DPT-12/0209	2470980	817091	633.00		25.00	608.00	< 608	no till
DPT-13	2470407	817216	630.80		24.00	606.80	< 607	till possible, m stiff tr rx frag
DPT-13/0209	2470815	817244	634.00		25.00	609.00	< 609	no till
DPT-14	2470470	817190	632.30		22.00	610.30	< 610	no till, v soft
DPT-14/0209	2470672	817154	635.00		25.00	610.00	< 610	no till
DPT-15	2470517	817234	631.80		22.00	609.80	< 610	loose silty sand
DPT-16	2470618	817246	632.80		24.00	608.80	< 609	no till, soft laminated
DPT-17	2470725	817260	633.00		26.00	607.00	< 607	till possible stiff silty clay tr rx frag
DPT-18	2470417	817038	634.40		22.00	612.40	< 612	till possible stiff silty clay rx frag some fc gravel
DPT-19	2470516	817113	632.97		28.00	604.97	< 605	till possible, stiff moist silty clay, tr fc gravel
DPT-2/0209	2471655	816892	634.00		25.00	609.00	< 609	no till
DPT-20	2470389	817255	632.70		28.00	604.70	< 605	no till, soft wet
DPT-21	2470338	817230	633.00		22.00	611.00	< 611	no till, v soft wet silt
DPT-22	2470519	817034	633.70		20.00	613.70	< 614	no till, soft silt layers
DPT-23	2470534	817170	634.00		18.00	616.00	< 616	till possible,but inconsistent w/ nearby borings; v stiff silty clay moist w/ sat. silt seam
DPT-24	2470252	817168	631.90		15.50	616.40	< 616	v stiff silt no till
DPT-25	2470256	817095	634.50		15.00	619.50	< 619	no till, soft
DPT-26	2470265	817029	633.80		16.00	617.80	< 618	no till, soft
DPT-28	2470415	817089	632.70		20.00	612.70	< 613	no till, soft
DPT-3/0209	2471362	817019	633.50		15.00	618.50	<619	no till

Table 1
Summary of SSP&A Interpretations of Elevations of Compacted Till

Location ID	, – ,	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Till Depth (feet, bgs)	Boring Depth (feet, bgs)	Bottom Boring Elevation (feet, MSL)	Till Elevation (feet, MSL)	Comment
DPT-6/0209	2471933	816991	635.00		25.00	610.00	< 610	no till
DPT-7/0209	2471442	817296	632.00		25.00	607.00	< 607	no till
DPT-9/0209	2471869	817233	632.50		25.00	607.50	< 608	stiff, moist gray silty clay with fine shale fragments and gravel. Trace sand. Doesn't hit bedrock. Value represents Max. till elevation
FBMW-10D	2471081	817814	637.4	?	64.35	573.05		Information in boring log is insuffient to pick till surface
FBMW-14D	2470452	814475	639.9	9	42.5	597.4	631	
FBMW-15D	2470689	815648	627.1	18	38.8	588.3	609	
FBMW-16D	2472183	817525	636.1	32	53	583.1	604	
FBMW-17D	2472275	815668	637.63	27	42.7	594.93	611	
FBMW-18D	2472293	815183	628.49	4	30	598.49	624	
FBMW-19D	2472301	814396	643.1	17	36.8	606.3	626	
FBMW-20D	2473723	817393	638.9	26	51	587.9	613	
FBMW-21D	2474248	815264	639.21	17	31.6	607.61	622	
FBMW-22D	2474760	819600	639.97	?	54	585.97		Information in boring log is insuffient to pick till surface
FBMW-23D	2475232	818329	641.53	?	47.5	594.03		Information in boring log is insuffient to pick till surface
FBMW-24D	2474827	815965	639.26	17	40	599.26	622	
FBMW-25D	2475533	815219	642.8	12	28.5	614.3	631	
FBMW-26D	2476485	817556	638.3	24	45	593.3	614	
FBMW-28D	2477293	815612	643.2	9	18.3	624.9	634	
FBMW-2D	2469059	818525	634.49	46	60.5	573.99	588	
FBMW-3D	2468992	816922	635.61	27	56	579.61	609	
FBMW-4D	2469608	816321	630.92	14	48.8	582.12	617	
FBMW-5D	2468944	815508	629.16	15	42.5	586.66	614	
FBMW-6D	2468837	815016	630.3	?	29.5	600.8		Information in boring log is insuffient to pick till surface
FBMW-7D	2469054	813448	637.85	11	33	604.85	627	
FBMW-8D	2470125	813283	644.38	9	35.4	608.98	635	
FBMW-9D	2470801	818872	641.30	?	76.65	564.65		Information in boring log is insuffient to pick till surface
GP06-01	2470659	815832	615.40		10.00	605.40	< 605	Doesn't hit till or bedrock. Represents max till elevation.
GP08-01	2470635	815758	615.40		15.00	600.40	<600	Doesn't hit till or bedrock. Represents max till elevation.
GP-1	2470992	816627	635.00		20.00	615.00	< 615	no clear till contact
GP-10	2470601	817499	636.00		20.00	616.00	< 616	silt @ 18', not till

Table 1
Summary of SSP&A Interpretations of Elevations of Compacted Till

Location ID	, _ ,	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Till Depth (feet, bgs)	Boring Depth (feet, bgs)	Bottom Boring Elevation (feet, MSL)	Till Elevation (feet, MSL)	Comment
GP-11	2470740	817815	638.00		16.00	622.00	< 622	silty clay @ 14' maybe till
GP-2	2470872	816733	635.00		20.00	615.00	< 615	PP values and silt laminea not consistent with till; silty sand at BOB
GP-3	2470631	816773	637.00		20.00	617.00	< 617	pp values may indicate till, but wet
GP31-01	2470399	815885	624.2		20.00	604.20	< 604	Doesn't hit till or bedrock. Represents max till elevation.
GP32-01	2470398	815827	617.0		15.00	602.00	< 602	Doesn't hit till or bedrock. Represents max till elevation.
GP-4	2470545	816960	636.00		16.00	620.00	< 620	pp values may indicate till, but wet
GP44-01	2470879	815758	618.00		13.00	605.00		Doesn't hit till or bedrock. Represents max till elevation.
GP-5	2470519	817059	635.00		16.00	619.00	< 619	pp values not consistent w/ till, wet
GP-500	2471836	816411	634.45		12.00	622.45		till possible at 11.5' ?
GP-501	2471794	816377	634.00		15.00	619.00	< 619	silt layers present, but dry, hard, till possible
GP-502	2471751	816383	634.00		12.00	622.00	< 622	
GP-503	2471722	816350	634.00		12.00	622.00		till possible at 11.5
GP-504	2471509	816543	634.54		12.00	622.54		hard clay at 11.5'
GP-505	2471465	816395	633.29		12.00	621.29		till possible at 11.75'; based on dry, tr gravel;
GP-506	2471564	816364	630.55		12.00	618.55	< 619	soft moist silty clay not till
GP-507	2470927	816409	633.54		12.00	621.54	< 622	till possible at 11.75' ; hard dry clayey silt
GP-508	2471028	816440	634.00		16.00	618.00	< 618	no evidence for till; silty
GP-509	2471234	816296	633.24		12.00	621.24	< 621	soft, wet at 11', becomes hard at 11.5 (possibly till?)
GP-510	2471346	816288	632.66		16.00	616.66	< 617	soft wet silty clay at 12-16'
GP-511	2471454	816260	632.00		12.00	620.00	< 620	no evidence for till
GP-512	2471557	816235	632.37		12.00	620.37		hard, dry at 10', possibly till
GP-513	2471672	816214	633.72		12.00	621.72	< 622	wet silty sand at 11.5' not till
GP-514	2471774	816203	634.21		16.00	618.21	< 618	hard, but moist, possibly till
GP-515	2471912	816202	635.81		12.00	623.81	< 624	moist silty clay @11' maybe till but no hardness/stiff indicated
GP-516	2471494	815860	623.98		16.00	607.98	< 608	till possible at 15.5, v hard, dry tr grav
GP-517	2471485	815834	621.52		12.00	609.52	< 610	till possible, v hard, dry silty clay w/ fine gravel,becomes dry brittle w/ shale fragments; doesn't hit bedrock
GP-518	2471471	815876	624.00		16.00	608.00	< 608	till possible at 15'; v hard dry silty clay
GP-519	2471807	817085	636.69		12.00	624.69	< 625	till picked not present, but possible at 11.5' dry gray silty clay, not certain

Table 1
Summary of SSP&A Interpretations of Elevations of Compacted Till

Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Till Depth (feet, bgs)	Boring Depth (feet, bgs)	Bottom Boring Elevation (feet, MSL)	Till Elevation (feet, MSL)	Comment	
GP-520	2471882	816901	635.76		12.00	623.76	< 624	till picked as not present but at 10' hard dry silty clay	
GP-521	2471894	817223	635.42		12.00	623.42	< 623	maybe till @ 10' at silty clay but no hardness/stiff indicated	
GP-6	2470482	817164	634.00		20.00	614.00	< 614	pp values not consistent w/ till, wet	
GP-7	2470464	817245	633.00		16.00	617.00	< 617	silt laminae at 10' not consistent w/ till	
GP-8	2470434	817309	637.00		24.00	613.00	< 613	silt laminae not consistent w/ till, PP too low also	
GP-9	2470500	817379	638.00		20.00	618.00	< 618	silt laminae not consistent w/ till, PP too low also	
IT-0601	2471459	816025	631.40		32.00	599.40	< 600	blow counts low but lith maybe indicate till, m stiff to soft	
IT-0602	2471564	816066	631.20		20.00	611.20	< 611	maybe till, blow counts low but blow counts higher at >15"	
IT-0603	2471675	816075	632.40		16.00	616.40	< 616	maybe till, but blow counts low	
IT-0604	2471747	816126	633.20		14.00	619.20	< 619	maybe till but blow counts low until >10'	
IT-0605	2471849	816139	634.90		16.00	618.90	< 619	maybe till, but blow counts low	
IT-0606	2471364	815997	632.00		14.00	618.00	< 618	maybe till, but blow counts low	
IT-0607	2471267	815976	631.00		14.00	617.00	< 617	maybe till, but blow counts low	
IT-0608	2471166	815996	631.00		14.00	617.00	< 617	maybe till, but blow counts low	
IT-0609	2471077	816025	631.00		14.00	617.00	< 617	maybe till, but blow counts low	
IT-0610	2470979	816032	630.70		24.00	606.70	< 607	blow counts higher at about 22'; possible till at22'	
IT-0611	2470875	816057	630.60		18.00	612.60	< 613	maybe till, but blow counts low	
IT-0612	2470778	816059	632.00		18.00	614.00	< 614	maybe till, but blow counts low	
IT-0613	2470674	816073	632.00		18.00	614.00	< 614	maybe till, but blow counts low	
IT-0614	2470579	816093	627.40		22.00	605.40	< 605	blow counts higher at about 18'; possible till	
IT-0615	2470475	816099	628.00		18.00	610.00	< 610	maybe till, but blow counts low	
MP-1	2471502	816979	635.00		22.00	613.00	< 613	gse approx based on TOC elev; all soft clay	
MP-2	2471480	816929	635.00		22.00	613.00	< 613	gse approx based on TOC elev; blow counts hgher at 21'	
MP-3	2471447	816976	635.00		24.00	611.00	< 611	gse approx based on TOC elev;till uncertain due to wet, low blow counts, HNU reading; sand lense?	
MP-4	2471483	817025	635.00		24.00	611.00	< 611	gse approx based on TOC elev;not likely till based on wet, blow counts, 10' silty sand at bottom	
NSPZ-1	2470292	815926	623.00		16.00	607.00	< 607	gse from DEM; pick based on log pick, not much detail	
NSPZ-2	2470292	815822	622.00		15.00	607.00	< 607	gse from DEM; pick based on log pick, not much detail	

Table 1
Summary of SSP&A Interpretations of Elevations of Compacted Till

Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Till Depth (feet,	Boring Depth (feet,	Bottom Boring Elevation (feet, MSL)	Till Elevation (feet, MSL)	Comment
NSTB-1	2470290	816009	624.81	bgs)	<b>bgs)</b> 12.00	612.81	< 613	gse from DEM; pick based on log pick, not much detail
NSTB-2	2470290	815979	624.61		16.00	608.16	< 608	gse from DEM; pick based on log pick, not much detail
NSTB-3	2470293	815954	623.53		16.00	607.53	< 608	gse from DEM; pick based on log pick, not much detail
NSTB-4	2470290	815905	623.23		16.00	607.23	< 607	gse from DEM; pick based on log pick, not much detail
NSTB-5	2470293	815875	622.37		14.00	608.37	< 608	gse from DEM; pick based on log pick, not much detail
NSTB-6	2470291	815846	622.50		15.00	607.50	< 608	gse from DEM; pick based on log pick, not much detail
RMSMW02S	2471386	817348	637.33		25.00	612.33	<612	3,7
RMSMW-05S	2470472	817385	635.60			635.60	< 615	no till
TP31-01	2469893	815457	613.8		4.5	609.3	< 603.5	Based on nearby boring GP19-01. Boring doesn't penetrate till or bedrock. Represents max till elevation.
TP37-01	2469696	815440	613.7		5.5	608.2	< 602.5	Based on nearby boring GP27-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TP38-01	2469702	815495	612.7		7	605.7	< 602.5	Based on nearby boring GP27-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TT06-01	2471229	815783	620.2		6	614.2	< 610	Based on nearby boring GP51-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TT13-01	2470423	815796	617.2		6.5	610.7	<601.5	Based on nearby boring GP31-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TT18-01	2471420	815830	620.9		6	614.9	< 606	Based on nearby boring GP54-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TT23-01	2470222	815855	617.7		15	602.7	< 603	Based on nearby boring GP10-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TT42-01	2470094	815570	615.3		7.5	607.8	<600.5	Based on nearby boring GP7-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.
TT43-01	2470173	815682	616.1		5	611.1	< 603	Based on nearby boring GP16-01.Boring doesn't penetrate till or bedrock. Represents max till elevation.

Note: The till elevations in a bold font were used to make the top of till contours.




Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Bottom elevation of Boring (feet, MSL)	Total Depth Drilled/ Excavated (feet, BGS)	Depth to Top DNAPL (feet, BGS)	Depth to Bottom DNAPL (feet, BGS)	Elevation of Top of DNAPL (feet, MSL)	Elevation of Bottom of DNAPL (feet, MSL)	Geologic Unit	Comments on DNAPL Observation	Data Source
2005 obs 1	2469546	815441	612.5	612.5		6	8	607	605	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
2005 obs 2	2469935	815453	613.5	613.5		6	8	608	606	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
2005 obs 3	2470040	815619	615.2	?	?	6	8	609	607	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
2005 obs 4	2470262	815835	617.0	?	?	6	8	611	609	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	1 1 1
2005 obs 5	2470599	815819	618.0	?	?	6	8	612	610	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
2005 obs 6	2470729	815753	618.3	?	?	6	8	612	610	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
2005 obs 7	2470971	815830	618.8	?	?	6	8	613	611	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
2005 obs 8	2471016	815834	619.0	?	?	6	8	613	611	unknown	DNAPL 2005 observation described at 6-8' BGS; elevation is approximate	
DETMW-10S	2471429	816632	637.9	618.0	19.9	19	20	622	621	Lacustrine - clay/silt	DNAPL measured in well Jan 2010	2

Summary of DNAPL Occurrences in Detrex Borings and Excavations

Table 2
Summary of DNAPL Occurrences in Detrex Borings and Excavations

Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Bottom elevation of Boring (feet, MSL)	Total Depth Drilled/ Excavated (feet, BGS)	Depth to Top DNAPL (feet, BGS)	Depth to Bottom DNAPL (feet, BGS)	Elevation of Top of DNAPL (feet, MSL)	Elevation of Bottom of DNAPL (feet, MSL)	Geologic Unit	Comments on DNAPL Observation	Data Source
DETMW-12S	2471465	815833	623.0	611.0	12.0	6	9	617	614	Lacustrine - clay w/ silt	DNAPL at 6' to 9' in boring log	3
DETMW-05S	2471432	817240	637.0	617.0	20.0	14	20	625	619	Lacustrine - laminated clay/silt	DNAPL measured in well in 1997	4
DETMW-06S	2471758	817151	636.3	618.8	17.5	10	18	629	621	Lacustrine - laminated clay/silt	DNAPL noted at 9.9 feet in boring log; DNAPL measured in well in 1997 from 11 to 17.5 feet BGS	3
DETMW-07S	2471479	816948	636.5	616.5	20.0	7	20	632	619	Lacustrine - laminated silt/sand/clay	DNAPL measured in well in 1997	4
DETMW-08S	2471271	817072	636.4	616.4	20.0	17	20	622	619	Lacustrine - laminated clay/silt	DNAPL noted at 17.5' to 20' in boring log; DNAPL measured in well from 16.9' to 20' in 1997	3
DETMW-09S	2471410	816738	638.4	620.9	17.5	17	18	623	623	Lacustrine - laminated clay/silt/sand	DNAPL measured in well in 1997	4
DETSB-19	2471739	817297	635.2	620.2	15.0	14	14	621	621	Lacustrine - clay w/ silt	DNAPL at 14' in boring log	3
DPT-10/0209	2471226	817195	633.0	618.0	15.0	5	14	628	620	Lacustrine - silty clay	DNAPL noted between 5' and 13.5' in boring log	3
DPT-12/0209	2470980	817091	633.0	608.0	25.0	18	22	615	611	Lacustrine - sandy silt	18' to 22' a chemical odor and sheen is detected, with PID readings of >9999. A 3" layer of DNAPL is recorded at 21'.	3



Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Bottom elevation of Boring (feet, MSL)	Total Depth Drilled/ Excavated (feet, BGS)	Depth to Top DNAPL (feet, BGS)	Depth to Bottom DNAPL (feet, BGS)	Elevation of Top of DNAPL (feet, MSL)	Elevation of Bottom of DNAPL (feet, MSL)	Geologic Unit	Comments on DNAPL Observation	Data Source
DPT-2/0209	2471655	816892	634.0	609.0	25.0	10	12	624	622	Lacustrine - silty sand	DNAPL at 10-12' in boring log	3
DPT-3/0209	2471362	817019	633.5	618.5	15.0	5	13	629	621	Lacustrine - silt, sand	DNAPL at 5'- 12.5' in boring log': 0.6' DNAPL measured in well March 2010	3
DPT-7/0209	2471442	817296	632.0	607.0	25.0	5	19	630	616	Lacustrine - silty sand to silty clay	DNAPL at 5'- 19' in boring log; 2.3' DNAPL measured in well bottom March 2010	3
GP31-01	2470399	815885	624.2	604.2	20.0	17	20	608	604	Lacustrine- clayey silt, sand	DNAPL observed in boring log	5
GP32-01	2470398	815827	617.0	602.0	15.0	11	15	606	603	Lacustrine- laminated clayey silt	DNAPL observed in boring log	5
GP44-01	2470914	815768	618.0	605.0	13.0	4	4.5	614	613.5	Lacustrine- silt	Soil concentrations are consistent with presence of DNAPL	7
RMSMW02S	2471386	817348	637.3	612.3	25.0	15	25	622	612	lacustrine- clayey silt with silt and fine sand laminations	10' of DNAPL observed in bottom of well	6
TP31-01	2469893	815457	613.8	609.3	4.5	4	4	610	610	Lacustrine- silt w/sand	DNAPL observed in test pit; approximate depth	7
TP37-01	2469696	815440	613.7	608.2	5.5	3.8	4	609.9	609.7	Lacustrine- silt	DNAPL observed in test pit; approximate depth	7
TP38-01	2469702	815495	612.7	605.7	7	4.8	5	607.9	607.7	Lacustrine- silt w/sand	DNAPL observed in test pit; approximate depth	7
TT06-01	2471229	815783	620.2	614.2	6.0	6	6	615	615	Lacustrine- silty clay	DNAPL in pockets and cracks	5
TT13-01	2470423	815796	617.2	610.7	6.5	4.5	4.5	613	613	Lacustrine- silt w/sand	DNAPL present on clay (4.5 ft)	5

Table 2
Summary of DNAPL Occurrences in Detrex Borings and Excavations

Location ID	Easting (NAD_1927)	Northing (NAD_1927)	Ground Surface Elevation (feet, MSL)	Bottom elevation of Boring (feet, MSL)	Total Depth Drilled/ Excavated (feet, BGS)	Depth to Top DNAPL (feet, BGS)	Depth to Bottom DNAPL (feet, BGS)	Elevation of Top of DNAPL (feet, MSL)	Elevation of Bottom of DNAPL (feet, MSL)	Geologic Unit	Comments on DNAPL Observation	Data Source
TT18-01	2471420	815830	620.9	614.9	6.0	4	4	617	617	Lacustrine- silt w/sand	DNAPL present on clay (4ft)	5
TT23-01	2470222	815855	617.7	602.7	15.0	7	7	611	611	Lacustrine- sandy silt	DNAPL present on clay (7ft)	5
TT42-01	2470094	815570	615.3	607.8	7.5	7	7	608	608	Lacustrine- silty clay, stratified w/ f. sand lenses	DNAPL pockets @ 7 ft	5
TT43-01	2470173	815682	616.1	611.1	5.0	4	4	612	612	Lacustrine- silt, sand	DNAPL, patchy @ 4 ft	5
TT22-01	2470998	815875	619.2	612.2	7.0	5	5	614	614	Lacustrine- silt	DNAPL present on clay (5 ft)	5
TT19-01	2471404	815763	620.9	615.4	5.5	4	4	617	617	Lacustrine- clay with silt	DNAPL pockets on clay (4 ft)	5

Data Sources:

- 1) 2005 DNAPL observations from Gradient Corporation, 2006
- 2) URS, 2010 (Table 2)
- 3) Boring Log
- 4) Document SDMS 91844, page 23 Table 1
- 5) Boring logs from Doc 369208 also shown in Gradient Corp 2006 Figures 2-8
- 6) Eckenfelder, 1990
- 7) Conestoga-Rovers & Associates, 2003

# Appendix A

**BORING LOGS** 

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

### Key to Log of Boring

	1	-	SA	MPLES				is	
Elevation, feet	ㅁ쏗	Type	!	Headspace, ppm	Recovery, inches	Graphic Log	MATERIAL DESCRIPTION	Well Detail	FIELD NOTES AND WELL DETAILS
1	2	3 4		5	6	7	8	9	10

#### **COLUMN DESCRIPTIONS**

- <u>Elevation:</u> Elevation in feet referenced to mean sea level (MSL) or site datum. 1
- 2 **Depth:** Depth in feet below the ground surface.
- <u>Sample Type:</u> Type of soil sample collected at depth interval shown; sampler symbols are explained below. 3
- 4 Sample Number: Sample identification number.
- 5 MiniRae 11.7eV Photo-Ionization Detector Headspace, ppm MiniRae 11.7eV Photo-Ionization Detector (PID) reading in headspace of sealable plastic bag after several minutes of vapor accumulation.
- Amount of material recovered in sampler, expressed Recovery: Amount of material recovered in sampler, expressed as percentage of sampled interval; NA indicates data not available.
- <u>Graphic Log:</u> Graphic depiction of subsurface material encountered; typical symbols are explained below.
- Material Description: Description of material encountered; may nclude color, moisture, grain size, and density/consistency.
- Well Details: Schematic of plezometer or well installation; materials are listed alongside well schematic; graphic Well Details: symbols are explained below.
- Field Notes and Well Details: Comments regarding drilling sampling made by driller or field personnel. Details about well Comments regarding drilling or construction materials and depths placed.

#### TYPICAL SOIL GRAPHIC SYMBOLS



**ASPHALT** 

Silty SAND



GRASS / TOPSOIL







GRAVEL







#### TYPICAL WELL GRAPHIC SYMBOLS



Riser in filter sand



0.010-inch slotted screen in filter sand

### TYPICAL SAMPLER GRAPHIC SYMBOLS



Hand Auger



Geoprobe Macrocore Sampler



Sample submitted for laboratory analysis

#### OTHER GRAPHIC SYMBOLS

- First water encountered at time of drilling and sampling (ATD)
- Static water level measured using electronic water level indicator
- Minor change in material properties within a lithologic stratum

#### **GENERAL NOTES**

- 1. Soil classifications are based on the Unified Soil Classification System. Descriptions and stratum lines are interpretive; actual lithologic changes may be gradual. Field descriptions may have been modified to reflect results of lab tests.
- Descriptions on these logs apply only at the specific boring locations and at the time the borings were advanced. They are not warranted to be representative of subsurface conditions at other locations or times.

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

120111112 00102

### Log of Boring DETWMW-1R

Date(s) Drilled	11/23/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	15.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Lev- and Date Measur		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

		Ι	SA	MPLES				_	
Elevation, feet	Depth, feet	Туре	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION		FIELD NOTES
	0		DP-1	60	N/A		GRASS / TOPSOIL  Soft; moist, brown, clayey SILT (ML) with sand and gravel  Medium stiff, moist, orange brown and gray mottled, silty CLAY (CL-ML) with sand, trace gravel	-	
	-		DP-2	60	N/A		Medium dense, wet, brown, sandy SILT (ML)  becomes moist  Medium stiff, moist, grayish brown, varved silty CLAY (CL-ML) trace black shale fragments, with sand and silt stringers  Medium stiff, moist, brownish gray, lean CLAY (CL) trace gray shale fragments and brown mottling		
	10		DP-3	60	N/A 0.0				Re-Sample from 12.0 to 14.0 feet bgs submitted for laboratory analysis.
	15-				N/A		Stiff, moist, gray, silty CLAY (CL-ML) with shale fragments and fine sand [TILL]  End of Boring at 15' bgs		
	20-						URS		

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

### Log of Boring DETWMW-2R

Sheet 1 of 1

Date(s) Drilled	11/23/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	15.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater and Date Me		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

	SA	MPLES				
Elevation, feet  Depth, feet	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
5	DP-1	50	N/A		GRASS / TOPSOIL  Soft, moist, orange brown and gray mottled, sandy silty CLAY (CL-ML)  with trace gravel and organics  becomes medium stiff  becomes brown and gray mottled, without sand and with coarse	
17.000 DELYMMY2A	DP-2	60	N/A		becomes brown and gray mottled, without sand and with coarse gravel  Medium dense, wet, brown, sandy SILT (ML)  becomes gray  Medium stiff, moist, gray, silty CLAY (CtML) trace fine sand, trace fine gray shale fragments	7
בא סברוארבא ווסאר סירו דיטר ויא יסדי	DP-3	60	N/A 0.0 N/A		- Stiff, moist, gray, silty CLAY (CL-ML) with black shale fragments and fine sand [TILL]	Re-Sample from 12.0 to 14.0 feet bgs submitted for laboratory analysis.
15					End of Boring at 15' bgs	

Report GEOPROBE\_5FT\_LINER\_SB; File: DETREX DELINEATION\_DPT1-DPT14.GPJ; 1/13/2010\_DETWMW-2R

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

### Log of Boring DETWMW-3R

Date(s) Drilled	11/23/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	19.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater L and Date Mea		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

1				SA	AMPLES				
	Elevation, feet	Depth, feet	Туре	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
		0- - - - - -		DP-1	58	N/A		GRASS / TOPSOIL  Soft, moist, dark brown, sandy CLAY (CL) with gravel  Soft, moist, orange brown and gray, lean CLAY (CL) trace organics  becames medium stiff	-
3/2010 DETWMW-3R		5		DP-2	60	N/A		Medium stiff, moist, brown, silty CLAY (CL-ML)	
Report: GEOPROBE_5FT_LINER_SB; File: DETREX DELINEATION_DPT1-DPT14.GPJ; 1/13/2010_DETWAMW-3R		10-		DP-3	60	0.0 N/A		Medium stiff, moist, gray, lean CLAY (CL) trace fine sand and fine rock fragments  Medium dense, wet, brown, sandy SILT (ML)  Medium dense, wet, brown, sandy SILT (ML)  Stiff, moist, gray, lean CLAY (CL) with silt varves, trace fine sand, trace fine gray shale fragments	
ROBE_SFT_LINER_SB; File: DET				DP-4	48	0.0 N/A		-	Re-Sample from 16.0 to 18.0 feet bgs submitted for laboratory analysis.
Report: GEOPF		20						End of Boring at 19' bgs	νο τ'!)

### Equivalent to DETMW-01D

IND ATION: 135.41	DEPTH (Ft)		TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	
		1	CS	_	3.8	Stiff, moist, dark gray with brown mottling, Silty CLAY (CL); trace to few sand and gravel	Lacustrine	
						Very stiff, dry to moist, light gray and brown mottled CLAY (CL); trace sand		
	5	2	CS		5.0	Hard, dry to moist, light gray and brown mottled		
						CLAY; trace sand and grave!		
							1	-mad-
	10	3	CS	l	5.0	Hard, dry to moist, light brown CLAY; trace sand		
		•	•		0.0	and gravel		
						Hard, dry to moist, gray CLAY; trace coarse sand and fine gravel		
						and mid graves		١.
	15	4	CS		5.0	Dry to moist varves of fine gray Silty SAND (SM)	1	-worter
						and gray SILT (ML)		
						Very stiff, dry to moist, gray CLAY (CL); some fine sand partings	Lacustrine	
	20	5	cs		5.0	Hard, moist, gray with trace red mottling, Silty CLAY (CL-ML); trace sand and gravel	Till	
	·					CLAY (CL-ML); trace sand and graver		/8
								77/
	25	6	CS	ĺ	5.0	dark gray, coarse, angular, shale gravel		19/
						Approximation to State of Approximation		
	30	7	CS	l	5.0	Hard, moist, gray Silty CLAY; few gravel	OVA = 90 ppm	
		ĺ			5.5	1-inch gray, medium sand layer		
		١.	L					
	35	8	CS		5.0	Hard, moist to dry, gray Silty CLAY; few gravel	OVA = 390 ppm	
								-
	40	9	CS		5.0	LOG OF BORING FBMW-11D		

### Equivalent to DETMW-01D

Page 2 of 2	ОЕРТН	20101		_	Γ-		
	(Ft)			P. <b>P</b> .	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
Page 2 of 2		10			5.0	DESCRIPTION OF STRATIGRAPHY  Hard, dry to moist gray Silty CLAY (CL-ML); few gravel  Gray SHALE (45.2 ft.)  Slightly weathered, thin bedded, moderately hard, fractured  Unweathered to slightly weathered, thin bedded moderately hard, fractured, gray SHALE  End of boring at 53.5 feet.  Water found in sampler at 9 and 14 feet.	COMMENTS  Till  Bedrock  RQD = 53%  RQD = 74%
	60 						
	80 ————————————————————————————————————					LOC OF POPING FRANK 11D	
				FIELL	DS RI	LOG OF BORING FBMW-11D ROOK SOURCE CONTROL - ASHTABULA, OHIO	J
CHECKED BY: J	CL D	ATE	: 1 N	OV 199	30 30		FIGURE No.: 14
					_		

Equivalent to DETMW-02D

ELEVATION TOP OF RISER PIPE: 636.53 ft.	DRIL	LIN	3 FIF		fatec	DATE DRILLED D Drilling Company INSPECTOR: S. Basi	: 5,6 June 1990 nam, N. Bigman	]
GPOUND ELEVATION: 633.63	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	
			CS	4.5	4.0	Very soft, moist, brn CLAY (CL); roots, trace sand Hard, moist, gray and brown mottled CLAY (CL); trace sandbecomes hard, moist to dry, brown with gray mottling	Lacustrine	
		2	CS	3.0 4.0	4.8	Very stiff, dry to moist, brown with gray mottling Silty CLAY (CL); varved with numerous silt partings		l E
	10	3	cs	4.2	5.0	4-inch orange-brown silt layer Hard,dry/moist,gray Silty CLAY; 5 inches of silt and sand interbeds2-inch gray fine sand layer		
	15	4	CS	2.5	4.6	Stiff, moist, gray with trace red mottling CLAY (CL); 5-inch sand pocket; planar partings on 1/4-inch scale		
	<u>20</u>	5	cs	2.2	5.2	Very stiff, dry to moist gray Silty CLAY (CL-ML); trace sand and gravel	Lacustrine Till	
	<u>25</u>	6	cs		4.6	planar partings oriented 0-30°, one fine sand parting		
	30	7	CS/	4.5	5.0	Very stiff, dry to moist gray Silty CLAY; trace sand and coarse gravel Hard, dry to moist gray Silty CLAY; trace sand and coarse gravel		T,(()
	35 ————————————————————————————————————		CS	4.5	4.7 5.3	Hard, dry to moist gray Silty CLAY; trace sand and few coarse gravel		
<u> </u>	<u></u>	_		FIEL		LOG OF BORING FBMW-12D ROOK SOURCE CONTROL - ASHTABULA, OHIO	1	
ECKED BY: ,	JCL [	DATE	: 1 N	OV 19	90	PROJECT No.: 86C3609D-230	FIGURE No.: 16	7

Woodward-Clyde Consultants

Equivalent to DETMW-02D

Page 2 of 2	DEPTH	SMP			_		-
Fage 2 01 2	(Ft)		TYPE	B/Ft	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						Very stiff, dry to moist, gray Silty CLAY (CL-ML)	Till
	_		_			Gray SHALE (41.1 ft.)	Bedrock
==		[				Soft, highly weathered, thin bedded	RQD=60%
	_					Weathered, moderately soft, thin bedded, gray	
==	45	10	CS		5.2	SHALE	RQD=82%
==  '		1					
==							
==							
==	_	ļ					
	50	11	cs		1.5	Mod. hard, slightly weath., thin bedded, gray SHALE	RQD=0%
						End of boring at 50.3 feet	
		l	ĺ				
		ļ					
	55						
ļ .		ł					
			1				
i i	60						
	60						
	<del></del>	l					
		l					
	65						
		1					
	_						
	70		]				
		1					
1							
	75						
(			( )				
_			_				
	80						
	—						
	85						
	00					LOG OF BORING FBMW-12D	
				FIEL	DS BI	ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL D	ATE:	1 N	OV 199	0	PROJECT No.: 86C3609D-230	FIGURE No.: 16

### Equivalent to DETMW-03D


VATION TOP RISER PIPE: 628.45	DRIL	LIN	3 FIF	Petrex RM: N G TYI	latec		): 11 June 1990 FOR: N. Bigman
VATION: 625.95	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	cs	1.5	3.7	Stiff, moist, mottled gray and brown Sandy CLAY (CL); trace cinders, gravel, brick fragments organic material and black sand pockets	Fill
	5_	2	CS	2.0	4.3	Bik Sandy CLAY;trace cinder,grvl,sand,brick frags Interbedded brown and gray medium sand (SW);	Fill Lacustrine
		)   				trace organic layers	
	10	3	cs	0.2	4.3	Firm, moist, black CLAY (CL); with organic material trace roots3-inch gray clay layer	,
	<u> </u>		•			Firm, moist, dark gray CLAY; trace organic mat. Firm, moist, black Sandy CLAY; w/ organic mat. Moist, gray, medium SAND (SW)	Lacustrine
	15	4	CS	4.2	5.0	Hard, moist, gray Silty CLAY (CL-ML); trace sand and fine to medium gravel	Till
	20	5	CS	4.5	5.0	Hard, moist, gray Silty CLAY (CL-ML); trace sand and fine gravelone 3-inch shale fragment. Hard, dry to moist	
						gray Silty CLAY; trace sand and fine gravel	
	25	6	CS	4.5	5.0		
	30	7	CS	4.5	5.0	Grav SHALE (31.0 ft.)	Till Bedrock
==						Highly weathered, thinly bedded, blocky to fractured, soft	Dec/ock
	35	8	CS	-		Weathered, thinly bedded, blocky to fractured, soft	
==						6-inch very soft, highly weathered zone	End of boring a
	40	9	CS		1.6	two 1-inch, very soft, highly weathered zones LOG OF BORING FBMW-13D	40.1 ft.
				FIELI	DS B	ROOK SOURCE CONTROL ~ ASHTABULA, OHIO	

Log of Boring DETMW04S

Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

Date(s) Drilled	1/4/93, 1/5/93	Logged M.T. Schmidt	Checked J.A. Ozimek
Drilling Method	Hollow stern auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 632.9
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 15.0
Groundwater Elevation (feet,	MSL) 627.30 7/27/93	Number of Samples Collected: 6 Analyzed: 2	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of Well (inches)	Type of Well Casing PVC riser /Stainless Steel Screen	Screen 0.010 in.
Type of Send Pack	20 mesh	Type/Thickness 1 ft bentonite pellets.	
Comments			Top of Well Casing Elevation (feet, MSL) 634.44




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

## Log of Boring DETMW05S


	1.15·1-1	
Data(s) 1/20/93, 1/21/93 Drilled	Lugged G.R. Lunt	Checked By J.A. Ozimek
Drilling Hollow etern auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 637.0
Drift Rig Failing F-7	Drilled Lehti Drilling	Total Depth Drilled (faet) 20.0
Groundwater Elevation (feet, MSL) 633.74 7/28/93	Number of Samples Collected: 8 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches) 8.25 Diameter of Walt (inches) 2	Type of PVC Well Casing	Screen 0.010 in.
Type of 20 mesh	Type/Thickness 2 ft bentonite pellets.	
Comments		Top of Well Casing Elevation (feet, MSL) 639.35



Project Number: 86C3609K
Boring Location: Detrex Corporation

## Log of Boring DETMW06S

Date(s) Drilled	1/12/93, 1/13/93	Logged G.R. Lunt	Checked By J.A. Ozimek
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. 1.D.) 4.25	Approx. Surface Elevation (feet, MSL) 636.3
Drill Rig Type	Failing F-7	Orilled Lahti Drilling	Total Depth Drilled (feet) 17.6
Groundwater Elevation (fee	t, MSL) 631.55 7/28/93	Number of Samples Collected: 7 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of Well (inches) 2	Type of Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 2 ft bentonite pellete of Seal(s)	
Commenta			Top of Well Casing Elevation (feet, MSL) 638.56




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

## Log of Boring DETMW07S

Date(s) Drilled	1/12/93, 1/13/93	Logged G.R. Lunt	Checked J.A. Ozimek
Drilling Method	Hollow etern auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 636.5
Driff Rig Type	Failing F-7	Drilled Lehti Drilling	Total Depth Drilled (feet) 20.0
Groundwater Elevation (feet	t, MSL) N/A	Number of Samples Collected: 8 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of Well (Inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 2 ft bentonite pellets of Seal(s)	
Comments			Top of Well Casing Elevation (feet, MSL) 638.71




Project Number: 86C3609K

**Boring Location: Detrax Corporation** 

## Log of Boring DETMW08S

Date(s) Orilled	1/11/93	Logged G.R. Lunt	Checked J.A. Ozimek
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 636.4
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 20.0
Groundwater Elevation (feet	MSL) 633.16 7/28/93	Number of Samples Collected: 8 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Dismeter of 2 Well (inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 2 ft bentonite pellete of Seal(s)	
Comments			Top of Well Casing Elevation (feet, MSL) 638.79




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

## Log of Boring DETMW09S

Date(s) Drilled	1/9/93	Logged G.R. Lunt	Checked J.A. Ozimek
Drilling Method	Hollow stem suger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 638.4
Drill Rig Type	Failing F-7	Drilled By Lahti Drilling	Total Depth Drilled (feet) 17.5
Groundwater Elevation (fee	t, MSL) 633.25 7/27/93	Number of Samples Collected: 7 Analyzed: 4	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of Well (inches) 2	Type of Well Casing Stainless Staal	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 2 ft bentonite pellets of Seal(s)	
Comments	<del>-</del>		Top of Well Casing Elevation (feet, MSL) 640.79



Project Number: 86C3609K Boring Location: Detrex Corporation


(1997) DOC ID 91857 (254)

## Log of Boring DETMW10S

Sheet 1 of 1

1180

Date(s) Drilled	1/7/93	Logged G.R. Lunt	Checked J.A.Ozimek
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 637.9
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 17.5
Groundwater Elevation (feet	, MSL) 631.65 7/27/93	Number of Samples Collected: 7 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Dismeter of Well (inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 2 ft bentonite pellets of Seal(s)	
Comments			Top of Well Casing Elevation (feet, MSL) 640.43




Project Number: 86C3609K

Boring Location: Detrex Corporation

## Log of Boring DETMW11S

Date(s) Drilled	1/6/93, 1/7/93	Logged M.T. Schmidt	Checked J.A. Ozimek
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 635.0
Drill Rig Type	Failing F-7	Drilled Lehti Drilling	Total Depth Drilled (feet) 20.0
Groundwater Elevation (feet	, MSL) 629.32 7/27/93	Number of Samples Collected: 8 Analyzed: 2	Sampler Type Continuous sample
Diameter of Hole (inches)	8.25 Diameter of Well (Inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 meeh	Type/Thickness 1 ft bentonite pallets of Seal(s)	
Comments			Top of Well Casing 637.28




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

### Log of Boring DETMW12S

Date(s) Drilled	2/7/93	Logged E. Page	Checked J.A. Ozimek
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 622.2
Drill Rig Type	Failing F-7	Drilled Lehti Drilling	Total Depth 12.0 Drilled (feet)
Groundwater Elevation (fee	t, MSL) 620.93 7/27/93	Number of Samples Collected: 4 Analyzed: 2	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of Well (inches) 2	Type of Stainless Stael	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 1 ft bentonite pellets of Seal(s)	
Comments	<u>_</u>		Top of Well Casing 624.03




Project Number: 86C3609K

Boring Location: Detrex Corporation

# Log of Boring DETMW17D

Date(s) Drilled	5/27/93, 6/7/93	Logged L.J. Mazer By	Checked J.A. Ozimek	
Orllling Method	Hollow stem auger (0-38 ft) Wet rotary (38-48 ft)	Auger Bit 8.25 (0-20 ft) Size/Type (in. i.D.) 4.25 (20-38ft)	Approx. Surface Elevation (feet, MSL) 634.2	
Drill Rig Type	Failing F-7	Drilled Lehti Drilling	Total Depth Drilled (faet) 48.0	
Groundwater Elevation (feet	, MSL) 604.48 7/27/93	Number of Samples Collected: 20 Analyzed: 2	Sampler Continuous sample NX core barrel	
Dismeter of Hole (inches)	8.25 Diameter of Well (inches)	Type of Stainless Steel	Screen 0.010 in.	
Type of Sand Pack	20 mesh	Type/Thickness 4 ft. Bentonite sturry. of Seal(s)		
Comments	10 in. I.D. steel casing from 0-2	Top of Well Casing Elevation (feet, MSL) 635.83		




Log of Boring DETMW17D

Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

Sheet 2 of 2




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

# Log of Boring DETMW17S

Date(s) Drilled	6/4/93	Logged G.R. Lunt		
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 634.3	
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 15.0	
Groundwater Elevation (feet	, MSL) 628.58 7/27/93	Number of Samples Collected: 6 Analyzed: 2	Sampler Continuous sample	
Diameter of Hole (inches)	8.25 Diameter of Well (inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.	
Type of Sand Pack	20 mesh	Type/Thickness 2 ft. Bentonite pellets.		
Comments			Top of Well Casing Elevation (feet, MSL) 635.90	




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

# Log of Boring DETMW18D

Date(s) Drilled	5/28/93, 6/1/93	Logged L.J. Mazer By	Checked J.A. Ozimek
Drilling Method	Hollow stem auger (0-38.5 ft) Wet rotary (38.5-48.5 ft)	Auger Bit 8.25 (0-17.5 ft) Size/Type (in. I.D.) 4.25 (17.5-38.5 ft)	Approx. Surface Elevation (feet, MSL) 635.0
Drill Rig Type	Falling F-7	Orifled Lehti Drilling	Total Depth Drilled (feet) 49.0
Groundwater Elevation (feet	, <sub>MSL)</sub> 589.59 7/27/93	Number of Samples Collected: 20 Analyzed: 2	Sampler Continuous sample Type NX core barrel
Diameter of Hole (inches)	8.25 Diameter of 2 Well (inches)	Type of Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 3 ft. Bentonite slurry.	
Comments			Top of Well Casing Elevation (feet, MSL) 637.01




Log of Boring DETMW18D

Project Number: 86C3609K

Boring Location: Detrex Corporation

Sheet 2 of 2




Project Number: 86C3609K

Boring Location: Detrex Corporation

# Log of Boring DETMW18S

Date(s) Drilled	6/2/93	Logged G.R. Lunt	Checked By J.A. Ozimek	
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 634.8	
Drill Rig Type	Failing F-7	Drilled By Lahti Drilling	Total Depth Drilled (feet) 15.0	
Groundwater Elevation (feet	t, MSL) 629.84 7/27/93	Number of Samples Collected: 6 Analyzed: 1	Sampler Continuous sample	
Diameter of Hole (inches)	8.25 Diameter of Well (inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.	
Type of Sand Pack	20 mesh	Type/Thickness 2 ft. Bentonite pellets.		
Comments			Top of Well Casing Elevation (feet, MSL) 636.46	




# Log of Boring DETMW20S

Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

Date(s) Drilled	6/10/93	Logged L.J. Mazer	Checked J.A. Ozimek	
Orilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 632.5	
Drill Rig Type	Failing F-7	Orilled By Lahti Drilling	Total Depth Drilled (feet) 20.0	
Groundwater Elevation (feet	, MSL) 629.85 7/26/93	Number of Samples Collected: 8 Analyzed: 2	Sampler Continuous eample	
Diameter of Hole (inches)	8.25 Diameter of Well (Inches)	Type of Stainless Steel Well Casing	Screen 0.010 in.	
Type of Sand Pack	20 mesh	Type/Thickness 2 ft. Bentonite pallets. of Seal(s)		
Comments			Top of Well Casing Elevation (feet, MSL) 633.75	




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

# Log of Boring DETMW21S

Date(s) Drilled	6/10/93	Logged L.J. Mazer	Checked J.A. Ozimek
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 635.1
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 20.0
Groundwater Elevation (feet	t, MSL) 633.63 7/26/93	Number of Samples Collected: 8 Analyzed: 2	Sampler Continuous cample
Diameter of Hole (inches)	8.25 Diameter of Well (inches) 2	Type of Well Casing Stainless Steel	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/fhickness 2 ft. Bentonite pellets.	
Comments			Top of Well Casing Elevation (feet, MSL) 636.77




Project Number: 86C3609K

Boring Location: Detrex Corporation

# Log of Boring DETSB13

Date(s) Drilled	1/20/93	Logged G.R. Lunt	Checked J.A. Ozimek	
Drilling Method	Hollow stem suger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 629.2	
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 20.0	
Groundwater Elevation (feet	, MSL) N/A	Number of Samples Collected: 8 Analyzed: 3	Sampler Continuous sample	
Diameter of Hole (inches)	8.25 Diameter of N/A Well (inches)	Type of Well Casing N/A	Screen N/A Perforation	
Type of Sand Pack	N/A	Type/Thickness N/A of Seal(s)		
Comments	No well installed, borehole tremie	Top of Well Casing Elevation (feet, MSL) N/A		




Log of Boring DETSB14

Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

Date(s) Drilled	1/21/93	Logged G.R. Lunt By	Checked J.A. Ozimek
Drilling Method	Hollow stem suger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 634.0
Drill Rig Type	Failing F-7	Drilled Lehtl Drilling	Total Depth Drilled (feet) 20,0
Groundwater Elevation (feet	, MSL) N/A	Number of Samples Collected: 8 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of N/A Well (Inches)	Type of Well Casing N/A	Screen N/A
Type of Sand Pack	N/A	Type/Thickness N/A of Seal(s)	
Comments	No well installed, borehole tremie g	Top of Well Casing N/A Elevation (feet, MSL)	




Log of Boring DETSB15

Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

Date(s) Drilled	1/22/93	Logged G.R. Lunt	Checked J.A. Ozimek
Drilling Hollow stem suger		Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 635.8
Drill Rig Type	Failing F-7	Drilled By Lehti Drilling	Total Depth Drilled (feet) 20.0
Groundwater Elevation (feet	, MSL) N/A	Number of Samples   Collected: 8   Analyzed: 3	Sampler Type Continuous sample
Diameter of Hole (inches)	8.25 Diameter of N/A Well (inches)	Type of N/A Well Casing	Screen N/A Perforation
Type of Sand Pack	N/A	Type/Thickness N/A of Seal(s)	
Comments	No well installed, borahole tremie	Top of Well Casing N/A	




# Log of Boring DETSB16

Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

Date(s) Drilled	1/18/93	Logged G.R. Lunt	Checked J.A. Ozimek By J.A. Ozimek Approx. Surface Elevation (feet, MSL) 636.1	
Drilling Method	Hollow stem auger	Auger Bit Size/Type (in. I.D.) 4.25		
Drill Rig Type	Failing F-7	Drilled Lahti Drilling	Total Depth Drilled (feet) 20.0	
Groundwater Elevation (feet	, MSL) N/A	Number of Samples   Collected: 8   Analyzed: 3	Sampler Continuous sample	
Diameter of Hole (inches)	8.25 Diameter of Well (inches)	Type of Well Casing N/A	Screen N/A Perforation	
Type of Sand Pack	N/A	Type/Thickness N/A of Seal(s)		
Comments	No well installed, barehole tremie g	Top of Well Casing Elevation (feat, MSL)		




Project Number: 86C3609K

**Boring Location: Detrex Corporation** 

# Log of Boring DETSB19

Date(s) Drilled	6/9/93	Logged G.R. Lunt	Checked J.A. Ozimek	
Drilling Method	Hollow etern auger	Auger Bit Size/Type (in. t.D.) 4.25	Approx. Surface Elevation (feet, MSL) 635.2	
Drill Rig Type	Failing F-7	Drilled By Lahti Drilling	Total Depth Drilled (feet) 15.0	
Groundwater Elevation (feet,	MSL) N/A	Number of Samples Collected: 6 Analyzed: 2	Sampler Type Continuous sample	
Diameter of Hole (inches)	8.25 Diameter of Well (inches) N/A	Type of Well Casing N/A	Screen N/A Perforation	
Type of Sand Pack	N/A	Type/Thickness N/A of Seal(s)		
Comments	No well installed, borshole tremis g	Top of Well Casing N/A Elevation (feet, MSL)		




Project: Detrex Corporation
Project Location: Ashtabula, Ohio

Project Number: 5E06680

## Log of Boring DETDB01

Date(s) Drilled	1/31/97	Logged By	R. Fabian	Checked By	N. Sauer
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	2-1/4-inch-ID / 5-inch-OD euger	Surface Elevation	Not available
Drill Rig Type	Failing F-7	Drilling Contractor	Lahti Drilling	Total Depth	12.0 feet
Groundwater I and Date Mea	Dapth Not messured	Sampler Type	2 x 24-inch split spoon	Hammer Date	140 ibs, 30-inch drop
Diameter of Hole (inches)	5 Diameter of Well (inches) None	Type of Well Casing	Not applicable	Screen Perforation	Not applicable
Type of Sand Pack	Not applicable	Type/Depth of Seal(s) No plezometer installed; borshole backfilled to surface with grout			
Comments	See site plan for location.				




Project: Detrex Corporation

Project Location: Ashtabula, Ohio

Project Number: 5E06680

## Log of Boring DETDB02

Date(s) Drilled	1/31/97			Logged By	R. Fabian	Checked By	N. Sauer	
Drilling Method	Hollow-Ste	em Auger		Drill Bit Size/Type	2-1/4-inch-ID / 5-inch-OD auger	Surface Elevation	Not svallable	
Drill Rig Type	Failing F-7			Drilling Contractor	Lahti Drilling	Total Depth	7.0 feet	
Groundwater I		measured		Sampler Type	2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop	
Diameter of Hole (inches)	5	Diameter of Well (inches)	None	Type of Well Casing	Not applicable	Screen Perforation	Not applicable	
Type of Sand Pack	Not applica	eble		Type/Depth of Seal(s)				
Comments	See site pi	an for location	n,					




Project: Detrex Corporation

Project Location: Ashtabula, Ohio

Project Number: 5E06680

### Log of Boring DETDP01

Date(s) Drilled	1/30/97			Logged By	R. Fabian	Checked By	N. Sauer	
Drilling Method	Hollow-St	em Auger		Orill Bit Size/Type 2-1/4-inch-ID / 5-inch-OD auger	Top of Casin Elevation	Top of Casing 636.03 feet MSL Elevation		
Drill Rig Type	Failing F-7	,		Orilling Contractor Lahti Drilling		Total Depth	24.0 feet	
Groundwater I and Date Mea		measured		Sampler Type	2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop	
Diameter of Hole (inches)	5	Diameter of Well (inches)	2	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot	
Type of Sand Pack	Filter sand	1		Type/Depth of Seal(s)	Bentonite 6 ft to surface			
Comments	See site p	ian for locatio	n.					




Project: Detrex Corporation
Project Location: Ashtabula, Ohio

Project Number: 5E06680

## Log of Boring DETDP02

	Felling F-7	Drilling	Lahti Drilling	Total	24.0 feet
Гуре		Contractor		Depth	
Groundwater ( and Data Meas		Sampler Type	2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop
Dismeter of Hole (inches)	Diameter of Well (inches)	Type of Well Casing	Schedule 40 PVC	Screan Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type/Depth of Seal(s)	Bentonite 6 ft to surface		




Project: Detrex Corporation
Project Location: Ashtabula, Ohio

Project Number: 5E06680

## Log of Boring DETDP03

Date(s) Drilled	1/30/97	Logged By	R. Fabien	Checked By	N. Sauer
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	2-1/4-inch-ID / 5-inch-OD auger	Top of Casin Elevation	9 636.03 feet MSL
Drill Rig Type	Falling F-7	Drilling Contractor	Lahti Drilling	Total Depth	24.0 feet
Groundwater I and Date Mea		Sampler Type	2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop
Diameter of Hole (inches)	5 Diameter of Well (inches) 2	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type/Depth of Seal(s)	Bentonite 6 ft to surfece		
Comments	See site plan for location.				




Project: Detrex Corporation

Project Location: Ashtabula, Ohio

Project Number: 5E06680

### Log of Boring DETDP04

Date(s) Drilled	1/30/97	Logged	R. Fabian	Checked N. Sauer
Drilling Method	Hollow-Stern Auger	Drill Bit Size/Type	2-1/4-inch-ID / 5-inch-OD auger	Top of Casing 637.12 feet MSL Elevation
Drill Rig Type	Failing F-7	Drilling Contractor	Lahti Drilling	Total 24.0 feet Depth
Groundwater I	Depth Not measured	Sampler Type	2 x 24-inch split spoon	Hammer 140 lbs, 30-inch dro
Diameter of Hole (inches)	5 Diameter of Well (inches) 2	Type of Well Casing	Schedule 40 PVC	Screen 0.010-inch slot
Type of Sand Pack	Filter sand	Type/Depth of Seal(s)	Bentonite 6-4 ft, bentonite gro	ut 4 ft to surface
Comments	See site plan for location.			




Project: Detrex Corporation
Project Location: Ashtabula, Ohio

**Project Number:** 

5E06680 Sheet 1 of 1

Log of Boring DETDP05

Date(s) Orilled	1/31/97	Logged	R. Fabian	Checked By	M. Sauer
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	2-1/4-inch-ID / 5-inch-OD auger	Top of Casin Elevation	636.11 feet MSL
Drill Rig Type	Failing F-7	Drilling Contractor	Lahti Drilling	Total Depth	24.0 feet
Groundwater and Date Mea		Sampler Type	2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop
Diameter of Hole (inches)	5 Diameter of Well (inches)	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type/Depth of Seal(s)	Bentonite 6 ft to surface		
Comments	See site plan for location.				




Project: Detrex Corporation

Project Location: Ashtabula, Ohio

Project Number: 5E06680

#### Log of Boring DETDP06

Comments	See site plan for location.			
Type of Sand Pack	Filter sand	Type/Depth of Seal(s)	Bentonite 6 ft to surface	
Diameter of Hole (inches)	5 Diameter of Well (inches) 2	Type of Well Casing	Schedule 40 PVC	Screen 0.010-inch slot
Groundwater I and Date Mea		Sampler Type	2 x 24-inch split spoon	Hammer Data 140 lbs, 30-inch drop
Drill Rig Type	Falling F-7	Drilling Contractor	Lahti Drilling	Total Depth 24.0 feet
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	2-1/4-inch-ID / 5-inch-OD auger	Top of Casing 634.74 feet MSL Elevation
Date(s) Drilled	1/31/97	Logged By	R. Fabian	Checked N. Sauer



Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

# Log of Boring DPT-1/0209

Date(s) Drilled	11/20/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	20.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Lo and Date Meas		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location	,		

	<u> </u>			SA	MPLES				
	Elevation, feet	Depth, feet	Type	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
		0-				0.0		Medium stiff, moist, brown, silty CLAY (CL-ML) with dark brown organics and roots  Medium stiff, moist, orange brown and gray mottled, silty CLAY (CL-ML)	
		-		DP-1	60	0.0		silt content increases, moisture and organic content decreases	
		5-				0.0		becomes stiff, silt content increases	
		_				5.2			Sample from 5.0 to 6.0 feet bgs submitted for laboratory analysis.
)		-		DP-2	60	4,4		Medium dense, wet, orange brown, sandy SILT (ML)  — becomes moist, with stiff, brown, day	Sample from 9.0 to 10.0 feet
6					i	4.4		Medium stiff, moist, gray, lean CLAY (CL) with silt, trace black shale fragments and sand	Sample from 8.0 to 10.0 feet bgs submitted for laboratory analysis.
DPT-1/020		10-				0.2		shale fragments and sand content decreases	
1/13/2010 DPT-1/0209		-		DP-3	60	8.0		Medium dense, wet, gray, silty SAND (SM) with clay	
PT14.GPJ		15-				0.7		silt content increases, with stiff, varved, silty clay and fine silty sand	
FIR: DETREX DELINEATION DPT1-DPT14.GPJ;		- -				0.8		Stiff, moist, gray, silty CLAY (CL-ML) with black shale fragments [TILL]	
REX DELINEA		-		DP-4	54	2.1		· -	
FIle: DET		20		-			<u> </u>	End of Boring at 20' bgs	
ER_SB;		-						-	
E_SFT_LIN									
Report: GEOPROBE		25-							
Report: G					!		'	URS	

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

## Log of Boring DPT-2/0209

Sheet 1 of 1

Date(s) Drilled	11/20/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Orill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Land Date Meas		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

			S	AMPLES				
Elevation, feet	Depth, feet	Туре	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	. 0	<u>.</u>					Medium stiff, moist, light brown, silty CLAY (CL-ML)	
	-				59.3		Medium stiff, moist, light orange brown and gray mottled, silty CLAY (CL-ML) with slight chemical odor	-
	-		DP-1	56	647		silt content increasing with depth	<u>.</u>
	_				3771		moisture and sand content increased, silt content decreased	-
	5				7748		strong chemical odor	Sample from 5.0 to 6.0 feet bgs submitted for laboratory
	-		DP-2	60	4587		becomes stiff, brown, mottling decreases	analysis.
	-				4982		Medium stiff, gray, moist, silty CLAY (CL-ML) trace sand and gray shale fragments  with sand seams	
	10- -				6408		Dense, wet, gray, silty SAND (SM) with DNAPL	Sample from 10.0 to 12.0 feet bgs submitted for laboratory analysis.
	-		DP-3	60	3313		becomes medium dense, silt content decreases	
	1				210		Medium stiff, moist, gray, fine sandy CLAY (CL)	
	15–				318		Medium dense, wet, gray, silty SAND (SM)	
	-		DP-4	48	148		becomes moist -	
	1				23.0		alternating silty sand and varved silty clay	
	20-				188		Stiff, moist, gray, silty CLAY (CL-ML) with shale fragments, trace coarse sand	
	-		DP-5	40	39.9		- with large abole from only	d .
	25				21.1		- with large shale fragments -	No +11/ <
	23						End of Boring at 25" bgs	

Report: GEOPROBE\_5FT\_LINER\_SB; File: DETREX DELINEATION\_DPT1-DPT14.GPJ; 1/13/2010\_DPT-2/0209

URS

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

## Log of Boring DPT-3/0209

Sheet 1 of 1

Date(s) Drilled	11/19/09	Logged By	A. Heitger	Checked M.	Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole 15.	0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Land Date Meas		Sampler Types	5' Macrocore Sampler	Top of Casing Elevation	
Coordinate Location		Boring Location			

			S	AMPLES					
Elevation, feet	Depth,	Type	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	Well details	FIELD NOTES AND WELL DETAILS
	- - -				127		GRASS / TOPSOIL  Medium stiff, moist, brown and gray, silty CLAY (CL-ML) with fine gravel		
	-		DP-1	. 55	2756		- becomes gray with trace rock fragments		1-inch SCH 40 PVC riser
	5 5				2258		Loose, wet, dark brown and black, dayey SAND (SC) with white PVC fragments and DNAPL		No samples submitted due to presence of DNAPt.
	-		DP-2	58	3556		Medium dense, moist, gray, SILT (ML) with organics and white PVC fragments, trace DNAPL  Loose, wet, dark brown and black, clayey silty SAND (SM) with white PVC fragments and DNAPL		
	10-				2339 2585		Medium dense, moist, gray, SILT (ML), with organics and white PVC fragments, trace DNAPL  Loose, wet, black, coarse SAND (SP) with silt and DNAPL		<del>#5</del> Filter sand
	-				2431				1-inch SCH 40 PVC
	- - -		DP-3	60	2913		Medium stiff to soft, moist, gray, silty CLAY (CL-ML) with rock fragments, trace fine sand		0.010-slotted screen
	15-				1206				
	.,						End of Boring at 15' bgs		
							No till		
	-								
	20								
Ĺ			_				TTRS		

Report: GEOPROBE\_SFT\_LINER\_WELL; File: DETREX DELINEATION\_DPT1.0PT14.GPJ; 1/13/2010 DPT-3/0209

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

# Log of Boring DPT-6/0209

Sheet 1 of 1

Date(s) Drilled	11/23/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Le and Date Measu		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

MATERIAL DESCRIPTION  FINAL DESC	FIELD NOTES
DP-1 56  0.3  Medium stiff, moist, orange brown and gray mottled, sandy silty CLAY - (CL-ML)	
0.3 Medium dense, moist, brown, sandy clayey SILT (ML) -4* layer  1.9 Medium dense, moist, brown and gray, sandy clayey SILT (ML)	
Medium dense, moist, brown and gray, sandy clayey SILT (ML)	
I 189921 I I 1/2/11/1	
2.6 Medium stiff, moist, gray, silty CLAY (CL-ML) with fine sand, trace fine grave!	i
3.8	
DP-3 52 Medium dense, moist, gray, clayey sandy SILT (ML) trace fine gravel feet bgs si laboratory  Medium stiff, moist, gray, silty CLAY (CL-ML) with fine sand, trace fine	from 12.0 to 14.0 submitted for y analysis.
gravel  Loose, wet, gray, coarse SAND (SW) with fine gravel ~1/4" seam  Isomple for feet bgs si laboratory	from 14.0 to 15.0 submitted for
3.8  DP-3  Sample fine feet bgs si laboratory  Medium stiff, moist, gray, clayey sandy SiLT (ML) trace fine gravel  Medium stiff, moist, gray, sity CLAY (CL-ML) with fine sand, trace fine gravel  Loose, wet, gray, coarse SAND (SW) with fine gravel ~1/4" seam  DP-4  O N/A  DP-4  O N/A	y analysis.
DP-5 60 Stiff, moist, gray, silty CLAY (CL-ML) with fine gravel and shale fragments, trace sand [TiLL]	
25 End of Boring at 25' bgs	
End of boying at 25 bgs	

Report: GEOPROBE\_5FT\_LINER\_SB; File: DETREX DELINEATION\_DPT1-DPT14.GPJ; 1/13/2010 DPT-6/0209

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

# Log of Boring DPT-7/0209

Sheet 1 of 1

Date(s) Drilled	11/20/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Le and Date Meast		Sampler Types	5' Macrocore Sampler	Top of Casing Elevation	
Coordinate Location		Boring Location		_	

		SA	AMPLES			<u> </u>		1
Elevation, feet	Depth, feet	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	Well details	FIELD NOTES AND WELL DETAILS
	0-1			3994		Medium stiff, moist, light brown, orange brown and gray mottled, silty CLAY (CL-ML)	-	
İ	- - -	DP-1	60	2295		Stiff, moist, brown and gray, clayey SILT (ML)  ———————————————————————————————————		
	5-			1039		Medium stiff, moist, light brown and gray mottled, silty CLAY (CL-ML) with sand, trace DNAPL		No samples submitted due to presence of DNAPL
	-	DP-2	60	1417		-		
	10			1472		Medium dense, moist, brown, sandy SILT (ML) with staining and DNAPL, trace gravel  Medium dense, moist, gray, SILT (ML) trace fine sand and DNAPL.		-1-inch SCH 40 PVC riser
	_			1773			-	
		DP-3	60	1908		Medium stiff, moist, gray, sandy silty CLAY (CL-ML)  Alternating layers of silt and clay	-	#5 Filter sand
	15-			1329		Medium dense, moist, gray, silty SAND (SM) trace brown coloration  with sheen on surface of soil, trace DNAPL in soil		FO THE SAID
				1208				and the second s
	_	DP-4	55	771		- ∳— becomes wet, with DNAPL	7.	mentral control contro
	-			261		Stiff, moist, gray, silty CLAY (CL-ML) with chemical odor and sheen	2000	1.inch SCH 40 PM/C
	20—	DP-5	45	N/A		Medium stiff, moist, gray, varved silty sandy CLAY (CL-ML)  -		1-inch SCH 40 PVC 0.010-slotted screen
	25	51-0		14/5		Stiff, moist, gray, silty CLAY (CL-ML) with sand and chemical odor, trace brown coloration [TILL]		
	25					End of Boring at 25' bgs		
	ــــــــــــــــــــــــــــــــــــــ		<u> </u>	÷				


Report: GEOPROBE\_SFT\_LINER\_WELL; File: DETREX DELINEATION\_DPT1-DPT14,GPJ; 1/13/2010 DPT-7/0209

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

#### Log of Boring DPT-9/0209

Date(s) Drilled	11/24/09	Logged By	A. Heitger	Checked By	M. Koss
Dritling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater L and Date Meas		Sampler Types	5' Macrocore Sampler	Top of Casing Elevation	
Coordinate Location		Boring Location			




Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

#### Log of Boring DPT-10/0209

Date(s) Drilled	11/24/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	15.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Le and Date Meas		Sampler Types	5' Macrocore Sampler	Top of Casing Elevation	
Coordinate Location		Boring Location			



Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

# Log of Boring DPT-11/0209

Date(s) Drilled	11/24/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Le and Date Measu		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

		Г	SA	MPLES				
Elevation, feet	Depth, feet	Туре	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	0-	X	HA-1	12	N/A		GRASS / TOPSOIL  Medium stiff, moist, orange brown and gray, sitty CLAY (CL-ML)	
		X	HA-2	12	N/A			
		X	HA-3	12	N/A			
		X	HA-4	12	N/A		_	Samples from 0.0 to 5.0 feet bgs saturated with surface water unable to screen
	5-	X	HA-5	12	N/A		Loose, wet, brown, clayey sandy GRAVEL (GW)	headspace
		X	HA-6	12	611		Medium stiff, moist, brown and gray, sitty CLAY (CL-ML) trace sand	
	-		DP-1	48	1802		→ Medium dense, wet, brown, sandy SILT (ML) ~4" layer	
	10-				4725		becomes brown, silt content increases	Sample from 10.0 to 12.0
			i		4783		- -	feet bgs submitted for laboratory analysis.  Duplicate Sample submitted
			DP-2	60	4776		Medium stiff, moist, gray, silty CLAY (CL-ML) trace fine sand and gravel	from 10.0 to 12.0 feet bgs for laboratory analysis.
	15~		···		1252			
	-		DP-3	60	7.0		Medium dense, wet, gray, sandy SILT (ML)	
	20-				2.1		Medium dense, moist, gray, sandy clayey SILT (ML)	
	-				28.6		Medium stiff, moist, gray, sandy silty CLAY (CL-ML)	Sample from 20.0 to 22.0 feet bgs submitted for laboratory analysis.
	-		DP-4	40	13.0		Stiff, moist, gray, silty CLAY (CL-ML) with fine shale fragments and gravel, trace sand [TILL]	/ -
	25-	<b>.</b>			6.7		End of Boring at 25' bgs	

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

# Log of Boring DPT-12/0209

Sheet 1 of 1

Date(s) 12/10/09 and 12/11/09	Logged By	A. Heitger	Checked By	M. Koss
Driftling Method Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater Level and Date Measured Approximately 18.0' bgs ATD	Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location	Boring Location			

			SA	AMPLES	<b>*</b>			
Elevation, feet	Depth, feet	Type	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	0-	$\langle \rangle$	HA-1	0	N/A		ASPHALT  Loose to medium dense, wet, gray, silty GRAVEL (GW) with sand	-
		M	HA-4	12	1530		Medium stiff, moist, grayish brown, silty CLAY (CL-ML) trace gravel	
1	_	M	HA-5	12	1246		becomes brown	]
	5-	M	HA-6	12	1026			
:			·DP-1	48	1515		- silt content increases	Sample from 8.0 to 10.0 feet
	10-				>9999		- -	bgs submitted for laboratory analysis.
					3039		-	
			DP-2	46	780		Medium stiff, moist, gray, silty CLAY (CL-ML) with rock fragments, trace fine sand	_
	15-				452			1
			DP-3	50	1495		-	Sample from 16.0 to 18.0 feet bgs submitted for laboratory analysis.
	20-				>9999		Medium dense, wet, gray, sandy SILT (ML) with chemical odor and sheen	
							- ← dark brown to black DNAPL ~3" layer	-
	-		DP-4	60	N/A		Stiff, moist, gray, silty CLAY (CL-ML) with fine shale fragments and gravel, trace sand [TILL]	
	25-	888					End of Boring at 25' bgs	
	-	<u>'</u>	4	<u> </u>			TTAC	

Report GEOPROBE\_5FT\_LINER\_SB; File: DETREX DELINEATION\_DPT1-DPT14.GPJ; 1/13/2010\_DPT-12/0209

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

## Log of Boring DPT-13/0209

Sheet 1 of 1

Date(s) Drilled	11/24/09 and 12/11/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Orill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater L and Date Meas		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			

			SA	MPLES				
Elevation, feet		Type	Number	Recovery, inches	Headspace, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	0-	X	HA-1	12	1.4			
	1	X	HA-2	12	0.0		Soft, moist, dark brown and gray, silty CLAY (CL-ML) with sand and gravel	
	Ť	X	HA-3	12	0.0		without sand or gravel	]
	Ī	X	HA-4	12	0.0		heremon medium stiff trace reak (mamanta	]
	آ ۔	X	HA-5	12	0.0		becomes medium stiff, trace rock fragments	
	5		-		7.6		Medium stiff, moist, orange brown and gray mottled, silty CLAY (CL-ML)	]
			DP-1	60	15.8		silt content increases	
	40				407		Medium dense, wet, brown, sandy SILT (ML)	
	10-				497		Medium dense, wet, brownish gray, silty SAND (SM)	
			DP-2	56	4998		Medium dense, moist, brown, sandy clayey SILT (ML)	-
	15				>9999		Medium stiff, moist, brown and gray, silty CLAY (CL-ML)	Sample from 13.0 to 15.0 feet bgs submitted for laboratory analysis.
	15				3756			
	-		DP-3	60	4830		with sand and silt layering	-
	20-				278		Loose, wet, gray, silty SAND (SM)	
	-	~	DP-4	60	271		Medium stiff, moist, gray, varved siity CLAY (CL-ML)	Sample from 21.0 to 23.0 feet bgs submitted for laboratory analysis.
	1				7.9		Stiff, moist, gray, silty CLAY (CL-ML) with fine shale fragments and gravel, trace sand [TILL]	-
	25-						End of Boring at 25' bgs	

PROBE\_SFT\_LINER\_SB; File: DETREX DELINEATION\_DPT1-DPT14.GPJ; 1/13/2010 DPT-13/020

Project Location: 1100 State Road, Ashtabula, OH

Project Number: 13811443.09402

# Log of Boring DPT-14/0209

Sheet 1 of 1

Date(s) Drilled	11/24/09 and 12/10/09	Logged By	A. Heitger	Checked By	M. Koss
Drilling Method	Direct Push	Drill Bit Size/Type	2.25" OD Macrocore Sampler	Total Depth of Borehole	25.0 feet
Drill Rig Type	Geoprobe 7720 DT	Drilling Contractor	Stock Drilling	Surface Elevation	
Groundwater L and Date Meas		Sampler Types	5' Macrocore Sampler	Boring Completion	Bentonite chips and cuttings
Coordinate Location		Boring Location			


$\overline{}$			SA	MPLES			Т		
Elevation, feet	Depth, feet	Туре	Number	Recovery, inches	Headspace, ppm	Graphic Log		MATERIAL DESCRIPTION	FIELD NOTES
	0-	M	HA-1	12	78.0	•	•	GRAVEL Loose, moist, brown, fine sandy GRAVEL (GW)	
	_	M	HA-2	12	80.3			with silt becomes fine to coarse, with day	
	•	M	HA-3	12	50.3			·	]
		M	HA-4	12	24.1			Medium stiff, moist, brown and gray mottled, silty CLAY, with organics	
	5-	X	HA-5	12	187			trace are matting	
	-				459				_
	-		DP-1	60	4496			moisture content decreases	-
	10-				4966			- -	Sample from 9.0 to 11.0 feet bgs submitted for laboratory analysis.
	-		DP-2	52	4903		-	with rock fragments  Medium stiff, moist, gray, silty CLAY (CL-ML) with rock fragments	
	- 15-				4846		-	- -	-
	-		DP-3	50	25.9		-	Medium dense, wet, gray, silty SAND (SM)	-
	20-				12.2		-  -	Soft, moist, gray, silty CLAY (CL-ML) trace sand and fine rock fragments	-
	-		DD 4	F4	20.1		-	becomes medium stiff  Stiff, moist, gray, silty CLAY (CL-ML) with fine shale fragments and	Sample from 21.0 to 23.0 feet bgs submitted for laboratory analysis.
	-		DP-4	51	7.1		-	Stiff, moist, gray, silty CLAY (CL-ML) with fine shale fragments and gravel, trace sand [TILL]	
	25-							End of Boring at 25' bgs	
								TIDE	

OPROBE SFT LINER SB: File: DETREX DELINEATION DPT1-DPT14.GPJ; 1/13/2010 DPT-

Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-02

Date(s) Drilled 9/5/06 1602	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817445.2056□ 2439017.07	Total Depth of Borehole	16.0° bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	636.68
Location North of Detrex, between slurry wall and trench	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casing	g 636.68




Project Location: North of Detrex, east of trench

Project Number: 13811443

### Log of Boring DPT-03

Sheet 1 of 1

Date(s) Drilled and Installed 9/6/06 0927	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 16.00 ' bgs
Sampling Macro-Core® sampler	Orill Bit Size/Type: geoprobe	Approximete Surface Elevation 635.76
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		




4,

Project Location: Outside slury wall near well RMSMW05S

Project Number: 13811443

# Log of Boring DPT-04


Date(s) Drilled 9/5/06 1503	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 20.00 ' bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximate Surface Elevation 634.10
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring 1100 State Rd		•



Project Location: 1100 State Rd Project Number: 13811443

## **Log of Boring DPT-05**


Date(s) 9/7/06 1545	Logged By	J. Berk	Checked By	D. Gray			
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817454.2806 2439186.22	Total Depth of Borehole	16.0' bgs			
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	635.17			
Location North of Detrex	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite			
Groundwater Level and Date Measured feet bgs on Elevation 635.17							



Project Location: 1100 State Rd Project Number: 13811443

# Log of Boring DPT-06

Date(s) 9/7/06 1453	Logged By	J. Berk	Checked D. Gray	_
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817466.454 2439259.037	Total Depth of Borehole 20.0' bg	ıs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation 634.76'	
Location North of Detrex	Sampling Method(s)	Macro-Core® sampler	Borehole Completion bentoni	te
Groundwater Level and Date Measured feet bgs on			Top of Casing 634.76	




Project Location: 1100 State Rd Project Number:

13811443

### **Log of Boring DPT-07**

Date(s) Drilled 9/7/06 1510	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817465.9465 2439340.065	Total Depth of Borehole	16.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	632.80'
Location North of Detrex, west of drainage	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casir Elevation	<sup>g</sup> 632.80



Project Location: North of Detrex, east of drainage

Project Number: 13811443

# Log of Boring DPT-08

Date(s) Drilled 9/7/06 and Installed	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 16.00 ' bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation 671.00
Drill Rig Type: Geoprobe 5400 bobcat mou	Inted Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		


٠.			SAM	PLES				
Elevation feet	Depth, feet	Type Number		Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
-670	0-			48			TOPSOIL Stiff, dark brown, moist, silty CLAY, (CL) with fine to coarse gravel, trace roots, low plasticity	Begin drilling @ 9/7/06
-	5			48	1/1		Stiff, brown mottled gray, moist, CLAY, (CL) trace roots, medium plasticity	
-660	10-			48	1/1		; - ; - ; -	Backfilled with bentonite
	15			48	2/2 0/0		; -	
-	20						End of Boring at 16' bgs	End drilling on 9/7/06
-650							hs +111	
	25						-	
-640	30						-	
	35-						URS	

Project Location: West of State Rd., south of creek.

Project Number: 13811443

# Log of Boring DPT-09


Date(s) Drilled 9/8/06 1112	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 14.00 bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation 626.93
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-10

Date(s) Drilled 9/8/06 0957	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817250.2885 2438720.525	Total Depth of Borehole	16.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	627.54 <sup>-</sup>
Location West of State Rd., south of creek.	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casin Elevation	<sup>19</sup> 627.54




Project Location: West of State Rd., south of creek.

Project Number: 13811443

## Log of Boring DPT-11


Date(s) Drilled 9/8/06 0918 and Installed	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 13.00 ' bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation 628.20
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring 1100 State Rd		



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-12


Date(s) Drilled 8/29/06 1131	Logged By	J. Berk	Checked D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817211.3641 2438878.823	Total Depth of Borehole 27.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation 632.41
Location Offset south to clear fence	Sampling Method(s)	Macro-Core® sampler	Borehole bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casing 632.41



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-13

Date(s) 9/1/06 1750 Drilled	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817255.9791 2438936.709	Total Depth of Borehole	24.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	630.81′
Location NW Corner of Detrex, on earth berm	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on	Top of Casin Elevation	g 630.81		




**Project Location: NW Corner of Detrex** 

Project Number: 13811443

### Log of Boring DPT-14


Date(s) Drilled 8/30/06 1422	Geologist J. Berk	Reviewer D. Gray
Drilling Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 22.00 bgs
Sampling Macro-Core® sampler	Drili Bit Size/Type: geoprobe	Approximete Surface Elevation 632.34'
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-15


Date(s) 8/31/06 1327 Drilled 8/31/06 1327	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817272.7806 2439046.003	Total Depth of Borehole	
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	631.82
Location Along. North fence line	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casir Elevation	<sup>ng</sup> 631.82



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-16

Date(s) Drilled 9/1/06 0829	Logged By	J. Berk	Checked By	D. Gray
Orilling Method & Geoprobe Orill Bit size/type geoprobe	Coordinates	817284.2088 2439146.277	Total Depth of Borehole	24.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	632.75
Location Along. North fence line	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casin Elevation	<sup>ng</sup> 632.75



Project Location: Along. North fence line

Project Number: 13811443

# Log of Boring DPT-17


Date(s) Drilled 9/1/06 and Installed	Geologist M. Koss	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 26.00 ' bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation ~633
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		

						_	_		
	-		SAM	PLES					
Elevation feet	Depth, feet	Number		Recovery, inches	PID, OVA,	Graphic Log	500000000000000000000000000000000000000	MATERIAL DESCRIPTION	FIELD NOTES
	0				/ 6/4			Medium stiff, light grayish brown, moist, clayey SILT, (ML) little rock fragments, mottled	Begin drilling @ 9/1/06
	5				8/2			Soft, dark gray, very moist, sandy FAT CLAY, (CL) trace clayey silt, trace coarse gravel, low plasticity	
	1				16/236			Soft, light brownish gray, moist, clayey SILT, (ML) trace rock fragments, low plasticity, mottled, iron oxide staining	
	40				48/197			Medium stiff, light grayish brown, moist, clayey SILT, (ML) trace rock fragments, low plasticity, mottled	
	10- - -				266/172			Medium stiff, light brownish gray, moist, clayey SILT, (ML) low plasticity, mottled	
	]				460/110			Soft, light grayish brown, wet, clayey StLT, (ML) trace medium sand, low plasticity, mottled, Iron oxide staining	
	15-				47/8			Medium stiff, light gray, moist, silty CLAY, (CL) medium plasticity	
					20/5			Medium stiff, gray, very moist, clayey SILT, (ML) medium plasticity	
	20-			, _	10/10			Medium stiff, dark gray, moist, silty CLAY, (CL) trace rock fragments, medium plasticity	7
5					5/4			Stiff, dark gray, moist, silty CLAY, (CL) trace rock fragments, medium plasticity, (till)	•
and	25				7/4				
500	1							End of Boring at 26' bgs	End driffing on 9/1/06
Nepon: 1.0102.ccc.g.go.cc.g.xg; File: C.Ord.; 11.00/2000 DF111	30							Proble 4:	
- To	35								
<u> </u>								TRS	

Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-18


Date(s) Drilled 8/29/06 1533	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817076.7446 2438946.428	Total Depth of Borehole	22.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	634.43′
Location South end of slurry wall, 9 ft west of force main	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured feet bgs on	Top of Casin Elevation	<sup>9</sup> 634.43		



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-19


Date(s) 8/30/06 1400	Logged By	J. Berk	Checked D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817151.3448 2439045.171	Total Depth of Borehole 28.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation 632.97
Comments	Sampling Method(s)	Macro-Core® sampler	Borehole Completion bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casing 632.97



Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-20

Date(s) Drilled 8/31/06 0855	Logged By	J. Berk	Checked D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817209.1267 2439062.304	Total Depth of Borehole 28.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation 632.72
Location Northwest corner of facility. Boring relocated to	Sampling Method(s)	Macro-Core® sampler	Borehole Completion bentonite
Groundwater Level and Date Measured 5.9 feet bgs on 9/18/2006			Top of Casing 632.72




Project Number: 13811443

Project Location: Along State St. At NW property corner. Added by M.

Log of Boring DPT-21


Date(s) Dril and Installe		Geologist	J. Berk	Reviewer	D. Gray
Drilling Method	Geoprobe	Drilling Contractor	Northcoast Drilling	Total Depth of Borehole	22.00 ' bgs
Sampling Method	Macro-Core® sampler	Drill Bit Size/Type:	geoprobe	Approximete Surface Elevation	~633′
Drill Rig Type:	Geoprobe 5400 bobcat mounted	Groundwater Level(s)		Hammer Data	
Boring Location:	1100 State Rd				



Project Location: 1100 State Rd Project Number: 13811443

### **Log of Boring DPT-22**

Date(s) 9/11/06 0900	Logged By J. Berk	Checked D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates 817072.6832 2439047.536	Total Depth of Borehole 20.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor Northcoast Drilling	Elevation 633.68
Comments	Sampling Macro-Core® sampl	er Borehole Completion bentonite
Groundwater Level and Date Measured feet bgs on		Top of Casing 633.68



Project: Detrex - Detrex Project Location:

Project Number: 13811443

# **Log of Boring DPT-23**

Date(s) Dri and installe		Geologist	J. Berk	Reviewer	D. Gray
Drilling Method	Geoprobe	Drilling Contractor	Northcoast Drilling	Total Depth of Borehole	18.00 ' bgs
Sampling Method	Macro-Core® sampler	Drill Bit Size/Type:	geoprobe	Approximete Surface Elevation	~634*
Drill Rig Type:	Geoprobe 5400 bobcat mounted	Groundwate Level(s)		Hammer Data	
Boring Location:	1100 State Rd				


		T		SAM	PLES		T		T
Elevation	Depth, feet	Type	Number		Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
ž		-			46.0	1/		TOPSOIL Stiff, brown mottled gray, moist, slity CLAY, (CL) low plasticity, iron oxide staining, Medium gravel @ 4ft.	Begin drilling @ 9/11/06 1027 PID background=16, FID Failure until end of sample screening. ()
	5-				48.0	30/ 350/	Fe	Dense, brown, saturated to moist, silty SAND, (SM) fine grained, Saturated layer @ 2.0-2.8ft.	
	10-				46.0	313/		Very stiff, brown, moist, CLAY, (CL) some gravel, non plastic, laminated	Submitted to lab with DUP0911B ()
	15-				30,0	200/ 98/	2 9 6	Very stiff, gray, moist silty CLAY, (CL) low plasticity, Saturated silt seam @ 17ft.	usole.
					17.0	0/-		<u> </u>	Water encountered at 17 feet ()
Neport	20- 25- 30-					•		End of Boring at 18' bgs  LIY'  Distribute Till >  In complete w/-  in complete w/-	End drilling on 9/11/06 1050
o company	35-	1						TTDC	

Project Location: Along State Rd.

Project Number: 13811443

### Log of Boring DPT-24


Date(s) Drilled 9/8/06 1400	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 15.80 bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation 631.91'
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		



Project Location: 1100 State Rd Project Number: 13811443

# **Log of Boring DPT-25**

Date(s) 9/11/06 1215	Logged By	J. Berk	Checked D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817133.9061 2438784.584	Total Depth of Borehole 16.0' bgs
Drill Rig Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation 634.49'
Location West side of State Rd.	Sampling Method(s)	Macro-Core® sampler	Borehole Completion bentonite
Groundwater Level and Date Measured feet bgs on			Top of Casing 634.49




**Project Location:** 

Project Number: 13811443

# Log of Boring DPT-26

Date(s) Drilled and installed 9/11/06 1255	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 16.00 'bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation 633.78
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		




Project Location: 59-ft W of DPT-19, 83 ft NE of DPT-18

Project Number: 13811443

# Log of Boring DPT-28


Date(s) Drilled 9/11/06 1493	Geologist J. Berk	Reviewer D. Gray
Drilling Method Geoprobe	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 20.00 bgs
Sampling Macro-Core® sampler	Drill Bit Size/Type: geoprobe	Approximete Surface Elevation 632.72
Drill Rig Type: Geoprobe 5400 bobcat mounted	Groundwater Level(s)	Hammer Data
Boring Location: 1100 State Rd		



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

# Log of Boring GP-1


Date(s) Drilled	2/9/99  Geoprobe / Direct Push  Geoprobe 6600  Elevation 633.12 feet on 2/10/99		Logged By	S. Davis	Checked By	S. Davis	
Drilling Method			Drilling Contractor	Summit Drilling Co.	Total Depth of Borehole	20.0 feet	
Drill Rig Type			Geoprobe 6600 Drill Bit Size/Type 2-1/8-inch geoprobe of	2-1/8-inch geoprobe drive point	Surface Elevation	635 feet MSL (approx.) 638.07 feet MSL	
Groundwater Level and Date			evation 633.12 feet on 2/10/99 Sampler Type Geoprobe dual-tube sampler	Geoprobe dual-tube sampler	Top of PVC Elevation		
Diameter of Hole (inches)	2-1/8	Diameter of Well (inches)	2	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter san	d		Type and Dep of Seal(s)	Bentonite 4.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface
Comments	Refer to s	ite plan for bor	ing/well lo	cation.			



Project Location: Ashtabula, Ohio Project Number: 38-08F06011.00

### Log of Boring GP-2


Date(s) Drilled	2/8/99	Logged By	S. Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push	Drilling Contractor	Summit Drilling Co.	Total Depth of Borehole	20.0 feet
Drill Rig Type	Geoprobe 6600 Drill Bit Size/Type 2-1/8-Inch geoprobe drive point	2-1/8-inch geoprobe drive point	Surface Elevation	635 feet MSL (approx.)	
Groundwater Level and Date	Elevation 633.65 feet on 2/10/99	evation 633.65 feet on 2/10/99 Sampler Type Geoprobe dual-tube sampler	Geoprobe dual-tube sampler	Top of PVC Elevation	638.05 feet MSL
Diameter of Hole (inches)	2-1/8 Diameter of Well (Inches) 2	Type of Well Casing	2-Inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type and De of Seal(s)	Bentonite 4.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface
Comments	Refer to site plan for boring/well to	cation,			



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-3


Date(s) Drilled	2/8/99	Logged By	S. Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push	Drilling Contractor	Summit Drilling Co.	Total Depth of Borehole	20.0 feet
Drill Rig Type	Geoprobe 6600	Drill Bit Size/Type	2-1/8-inch geoprobe drive point	Surface Elevation	637 feet MSL (approx.)
Groundwater Level and Date	Elevation 634.95 feet on 2/10/99	Sampler Type	Geoprobe dual-tube sampler	Top of PVC Elevation	636.59 feet MSL
Diameter of Hole (inches)	2-1/8 Diameter of Well (inches) 2	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type and De of Seal(s)	Bentonite 4.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface
Comments	Refer to site plan for boring/well lo	cation.			



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-4


Date(s) Orilled	2/8/99	Logged By	S. Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push	Drilling Contractor	Summit Drilling Co.	Total Depth of Borehole	16.0 feet
Orill Rig Type	Geoprobe 6600	Sampler	2-1/8-inch geoprobe drive point	Surface Elevation	636 feet MSL (approx.)
Groundwater Level and Date	Elevation 633.57 feet on 2/10/99		Geoprobe dual-tube sampler	Top of PVC Elevation	
Diameter of Hole (inches)	2-1/8 Diameter of Well (Inches) 2	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type and De of Seal(s)	Bentonite 4.0 - 1.0 ft, cement g	rout 1.0 ft to su	rface
Comments	Refer to site plan for boring/well location.				



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-5


Date(s) Drilled	2/8/99	Logged By	S. Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push	Drilling Contractor	Summit Drilling Co.	Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drill Bit Size/Type	2-1/8-inch geoprobe drive point	Surface Elevation	635 feet MSL (approx.)
Groundwater Level and Date	Elevation 633.73 feet on 2/10/99	Sampler Type	Geoprobe dual-tube sampler	Top of PVC Elevation	634.74 feet MSL
Diameter of Hole (inches)	2-1/8 Diarneter of Well (inches) 2	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type and Deport of Seal(s)	Poth Bentonite 4.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface
Comments	Refer to site plan for boring/well lo	cation.			



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-6


Date(s) Drilled	2/8/99		Log <b>ged</b> By	S. Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push Geoprobe 6600 Elevation 631.29 feet on 2/10/99		Orilling Summit Drilling Co.		Total Depth of Borehole	20.0 feet
Drill Rig Type			Geoprobe 6600 Drill Bit Size/Type	2-1/8-inch geoprobe drive point	Surface Elevation	634 feet MSL (approx.)
Groundwater Level and Date			Sampler Geoprobe dual-tube sampler	Top of PVC Elevation	633.95 feet MSL	
Diameter of Hole (inches)	2-1/8	Diameter of 2 Well (inches)	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand		Type and De of Seal(s)	rface		
Comments	Refer to	site plan for boring/well to	ocation.			



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-7


Date(s) Drilled	2/8/99	Logged S.	Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push	Pirect Push Drilling Summit Drilling Co.		Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600 Drill Bit Size/Type 2-1/8-inch	1/8-inch geoprobe drive point	Surface Elevation	633 feet MSL (approx.)	
Groundwater Level and Date	Elevation 628.92 feet on 2/10/99	evation 628.92 feet on 2/10/99 Sampler Type Geoprobe dual-tube s	eoprobe dual-tube sampler	Top of PVC Elevation	632.44 feet MSL
Diameter of Hole (inches)	2-1/8 Diameter of Well (Inches) 2	Type of Well Casing	2-inch-dla, Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type and Depth of Seal(s)	Bentonite 4.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface
Comments	Refer to site plan for boring/well	ocation.		-	



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-8


Date(s) Drilled	2/9/99  Geoprobe / Direct Push  Geoprobe 6600  Elevation 631.35 feet on 2/10/99		Logged By	S. Davis	Checked By	S. Davis		
Drilling Method			eoprobe / Direct Push Orilling Contractor Summit Drilling Co.		Total Depth of Borehole	24.0 feet		
Drill Rig Type			probe 6600 Drill Bit Size/Type 2-1/8-inch geoprobe dr	2-1/8-inch geoprobe drive point	Surface Elevation	637 feet MSL (approx.)		
Groundwater Level and Date					Geoprobe dual-tube sampler	Top of PVC Elevation	639.17 feet MSL	
Diameter of Hole (inches)	2-1/8	2-1/8 Diameter of Well (Inches) 2		Diameter of 2 Type of Well (inches) 2 Well Ca	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand		ter sand  Type and Depth of Seal(s)  Bentonite 11.0 - 2.0 ft, cement grout 2.0 ft to		grout 2.0 ft to s	urface		
Comments	Refer to	site plan for bor	ing/well lo	cation.				



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

## Log of Boring GP-9


Date(s) Drilled	2/9/99	Logged By	S. Davis	Checked By	S. Davis
Drilling Method	Geoprobe / Direct Push	Drilling Contractor Summit Drilling Co.		Total Depth of Borehole	20.0 feet
Drill Rig Type	Geoprobe 6600	Drill Bit Size/Type	2-1/8-inch geoprobe drive point	Surface Elevation	638 feet MSL (approx.)
Groundwater Level and Date	Elevation 633.33 feet on 2/10/99	Sampler Type			640.59 feet MSL
Diameter of Hole (inches)	2-1/8 Diameter of Well (inches) 2	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sand	Type and De	pth Bentonite 8.0 - 2.0 ft, cement g	rout 2.0 ft to su	rtace
Comments	Refer to site plan for boring/well lo	cation.			,



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-10


Date(s) Drilled	2/9/99	Logged By	S. Davis	Checked By	S. Davís	
Drilling Method	Geoprobe / Direct Push	Drilling Contractor	Summit Drilling Co.	Total Depth of Borehole	20.0 feet	
Drill Rig Type	Geoprobe 6600	Drill Bit Size/Type 2-1/8-inch geoprobe drive point		Surface Elevation	636 feet MSL (approx.)	
Groundwater Level and Date	Elevation 629.20 feet on 2/10/99	Sampler Geoprobe dual-tube sampler	Geoprobe dual-tube sampler	Top of PVC Elevation	638.53 feet MSL	
Diameter of Hole (inches)	2-1/8 Diameter of Well (inches) 2	Type of Well Casing	2-inch-dia, Schedule 40 PVC	Screen Perforation	0.010-inch slot	
Type of Sand Pack	Filter sand	Type and Dept of Seal(s)	th Bentonite 8.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface	
Comments	Refer to site plan for boring/well location.					



Project Location: Ashtabula, Ohio Project Number: 38-08E06011.00

### Log of Boring GP-11

Date(s) Drilled	2/9/99 Geoprobe / Direct Push Geoprobe 6600 Elevation 636.62 feet on 2/10/99		Log <b>ged</b> By	S. Davis	Checked By	S. Davis	
Drilling Method					Total Depth of Borehole	16.0 feet	
Drill Rig Type			Sample	2-1/8-inch geoprobe drive point	Surface Elevation	638 feet MSL (approx.)	
Groundwater Level and Date					Geoprobe dual-tube sampler	Top of PVC Elevation	641.10 feet MSL
Diameter of Hole (inches)	2-1/8	Diameter of Well (inches)	2	Type of Well Casing	2-inch-dia. Schedule 40 PVC	Screen Perforation	0.010-inch slot
Type of Sand Pack	Filter sa	nd		Type and Dep of Seal(s)	th Bentonite 4.0 - 2.0 ft, cement g	rout 2.0 ft to su	rface
Comments	Refer to	site plan for bor	ing/well lo	cation.			




Project: Detrex

Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

### Log of Boring GP-500

Date(s) Drilled	9/7/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.45 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 816410.9 E 2471835.8	Boring Location	Refer to Site Plan		



Project: Detrex

Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

# Log of Boring GP-501

Date(s) Drilled	9/7/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borshole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.00 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 816377.4 E 2471793.7	Boring Location	Refer to Site Plan		

		SA	MPLES				1	
Elevation, feet	Depth, feet	J86	Recovery, inches	Headspace, ppm.	Graphic Log	MATERIAL DESCRIPTION	. FIELD NOTES	
<b>.</b>	0-		48	0.0		Hard, dry, dark brown, clayey SILT  Hard, dry, brown, SILT, trace clay		
- -630	-1 -1 -1			0.0		Hard, moist, brown, silty CLAY, laminated		
-	5		48	0.0				
- -625	10-			0.0		Firm, wet, brown, silty SAND  becomes hard, moist, increasing clay content  Soft, wet, brown, silty SAND, with clay becomes loose, dry		
		12	12	0.0		- - - -		
- 620-			24	0.0		Soft, wet, gray, sandy SILT  Hard, dry, gray, CLAY, and silt layers		
-	15-			0.0		Hard, dry, gray, CLAY, and silt layers		
-62 <del>0</del> - - -615	4-4-4					Danible Fill		
<b>−615</b>	20-		-			-		
·	URS							


Project: Detrex

Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

### Log of Boring GP-502

Date(s) Drilled	9/7/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.00 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Top of Casing Elevation	
Coordinate Location	N 816383.2 E 2471751.0	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-503

Date(s) Drilled	9/7/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.00 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chlps
Coordinate Location	N 816349.9 E 2471722.0	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number:

13810732

#### Log of Boring GP-504

Date(s) Drilled	9/7/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.54 above MSL
Groundwater L and Date Meas		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location N	816543.2 E 2471508.6	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-505

Date(s) Drifled	9/7/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	633.29 above MSL
Groundwater I and Date Mea		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	816394.7 E 2471465.2	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

**Project Number:** 

13810732

#### Log of Boring GP-506

Date(s) Drilled	9/7/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Dîrect Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	630.55 above MSL
Groundwater L and Date Meas		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location N	816363.6 E 2471564.2	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-507

Date(s) Drilled	9/7/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	633.54 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 816408.5 E 2470926.5	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-508

Date(s) Drilled	9/7/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.00 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Top of Casing Elevation	
Coordinate Location	N 816439.8 E 2471027.8	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohlo

Project Number: 13810732

#### Log of Boring GP-509

Date(s) Drilled	9/8/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	633.24 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 816295.6 E 2471233.8	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number:

13810732

#### Log of Boring GP-510

Date(s) Drilled	9/8/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Oril) Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	632.66 above MSL
Groundwater Le		Sampler Types	Acetate Liner	Top of Casing Elevation	
Coordinate N	816287.6 E 2471345.5	Boring Location	Refer to Site Plan		



Project Location: 1100 State Road, Ashtabula, Ohio

Project Number:

13810732

### Log of Boring GP-511

Date(s) Drilled	9/8/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	632.00 above MSL
Groundwater Level and Date Measured		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	816260.0 E 2471454.3	Boring Location	Refer to Site Plan		


Locatio	_		10200.0	E 24/ 145			Location	
			S/	MPLES				
Elevation, feet	Depth, feet	Туре	Number	Recovery, inches	Headspace, ppm.	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
-630	-0			32	0.0		Firm, dry, light brown, silty CLAY, with gray mottles, brittle	
-					0.0	-	Firm, dry, light brown, SILT, trace fine sand and gray mottles	
-	5-			44	0.0			
-625 -	•		-		0.0		Hard, dry, brown, clayey SILT, trace fine sand layers	
-	10-			36	0.0		Firm, moist, gray, silty CLAY	
620						2411	End of boring at 12 feet bgs	
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	15-						- M +,,,	
-615							-	
Application of the control of the co	20-						URS	

Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-512

Date(s) Drilled	9/8/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	632.37 above MSL
Groundwater L and Date Meas		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location N	816235.4 E 2471556.5	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohlo

Project Number: 13810732

#### Log of Boring GP-513

Date(s) Drilled	9/8/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	633.72 above MSL
Groundwater and Date Mea		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 816214.4 E 2471671.8	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number:

13810732

#### Log of Boring GP-514

Date(s) Drilled	9/8/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	634.21 above MSL
Groundwater L and Date Meas		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location N	816203.1 E 2471773.7	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-515

Date(s) Drilled	9/8/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	635.81 above MSL
Groundwater I and Date Mea		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location N	I 816202.1 E 2471911.6	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

**Project Number:** 

13810732

#### Log of Boring GP-516

Date(s) Drilled	9/8/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drift Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	623.98 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Top of Casing Elevation	,
Coordinate Location	N 815860.1 E 2471494.0	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohlo

Project Number: 13810732

#### Log of Boring GP-517

Date(s) Drilled	9/8/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	621.52 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 815833.7 E 2471484.6	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-518

Date(s) Drilled	9/8/05	Logged By	J. Kaminski	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	16.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	624.00 above MSL
Groundwater i		Sampler Types	Acetate Liner	Top of Casing Elevation	
Coordinate Location	N 815876.2 E 2471470.8	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

Project Number: 13810732

#### Log of Boring GP-519

Date(s) Drilled	9/9/05	Logged By	J. Berk	Checked By	K. Mast
Drilting Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	636.69 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	N 817085.2 E 2471807.2	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohio

**Project Number:** 

13810732

#### Log of Boring GP-520

Date(s) Drilled	9/9/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	635.76 above MSL
Groundwater I and Date Mea		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate Location	816901.1 E 2471881.7	Boring Location	Refer to Site Plan		




Project Location: 1100 State Road, Ashtabula, Ohlo

Project Number: 13810732

#### Log of Boring GP-521

Date(s) Drilled	9/9/05	Logged By	J. Berk	Checked By	K. Mast
Drilling Method	Direct Push	Drill Bit Size/Type	4-foot long geoprobe sampler	Total Depth of Borehole	12.0 feet
Drill Rig Type	Geoprobe 6600	Drilling Contractor	Summit Drilling, Inc.	Surface Elevation	635.42 above MSL
Groundwater and Date Me		Sampler Types	Acetate Liner	Boring Completion	Bentonite Chips
Coordinate	N 817223.0 E 2471894.2	Boring	Refer to Site Plan		




**Project: Detrex - Detrex** 

Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring DPT-01

Date(s) Drilled 9/5/06	Logged By	J. Berk	Checked By	D. Gray
Drilling Method & Geoprobe Drill Bit size/type geoprobe	Coordinates	817511.3146 2439055.034	Total Depth of Borehole	12.0' bgs
Drill Rig Type Geoprobe 5400 bobcat mounted	Drilling Contractor	Northcoast Drilling	Elevation	636.68′
Location North of Detrex	Sampling Method(s)	Macro-Core® sampler	Borehole Completion	bentonite
Groundwater Level and Date Measured 6.35 feet bgs on 9/18/2006			Top of Casin Elevation	<sup>9</sup> 640.96



Project: Detrex - Detrex

Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring IT0601

Sheet 1 of 2

Date(s) Drilled 8/24/06 1300 and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth 32.00 bgs
Sampling Method	Drill Bit Size/Type: 4-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location: Center of line		

				SAME	LES				
Elevation feet	Depth, feet	Type	Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	0			3 4 7 11	22.0	0		Soft, light gray, moist, clayey SILT, (CL-ML) trace fine sand, low plasticity  Medium stiff, light tan, moist, CLAY, (CL) low plasticity	Begin drilling @ 8/24/06 130
	2			4 4 8 9	1.5	0		Medium stiff, light brown tight gray, molst, CLAY, (CL) low plasticity	
	4-			5 8 7 5	23.0	0		Soft, light gray, CLAY, (CL) medium plasticity, (Fill)	·
	6-		Ì	2 2 4 5	17.0	0		Light gray, moist, silty CLAY, (CL-ML) some fine sand	
	8-			2 2 4 5	21.0	0		Medium stiff, light brown light gray, molst, silty CLAY, (CL-ML) low plasticity	
	10			5 5 5 6		0		Light gray, (CL-ML) low plasticity	Towns to the state of the state
	14			5 7 9		0		Medium stiff, gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plasticity, (till)	
	14		The Continue of the Continue o	4 6 7 9	24.0	0		Medium stiff, gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plasticity, (till)	Sample submitted for laboratory anelysis ()
	16		Contraction Contraction (Section Contraction Contracti	4 9 10 11	24.0	0		Light gray, moist, sandy CLAY, (CL-ML) trace silty sand, low plasticity, (tix)	Sample time 1415 ()
	18			6 7 8				Soft, gray, silty CLAY, (CL-ML) medium plasticity. (till)	Coarse sand fine gravel ()

a Rasobe 84

Project: Detrex - Detrex

Project Location: 1100 State Rd Project Number: 13811443

### Log of Boring IT0601

Sheet 2 of 2

		_	_	SAME	LES				1
feet	Depth, feet	Type	Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	20	T		3			TV	Soft, gray, moist, silty CLAY, (CL-ML) trace fine gravel, trace silt, modium plasticity, (tilt)	
	22	1		4 7 8	22.0	0			
	22-			4 8 12 13	24.0	0		Medium stiff, gray, moist, silty CLAY, (CL-ML) trace cobbles, trace silt, medium plasticity, (till)	
	24-			5 10 12	24.0	0		Medium stiff, gray, moist, slity CLAY, (CL-ML) trace cobbles, trace slit, medium plasticity, (till)	
	26-			16 5 7 10	24.0	0		Stiff, gray, moist, silty CLAY, (CL-ML) trace cobbles, trace silt, medium plasticity, (till)	
	28-			12 6 10	24.0	0		Stiff, gray, moist, silty CLAY, (CL-ML) trace cobbtes, trace silt, medium plasticity, (till)	
	30			12 16		·		Light gray, (CL-ML) low plasticity, (till)	
	32-							-	End drilling @
	34							End of Boring at 32' bgs	
	36	-						·	
	36								
	38-								
	40								
	42-							- -	
	-								

Project Number: Detrex

### Log of Boring IT0602

Sheet 1 of 1


Date(s) Drilled and Installed 8/25/06 0917	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 20.00 bgs
Sampling Method	Drill Bit Size/Type: 4-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer Data
Boring Location:		

		<u> </u>	SAM	PLES		T		
Elevation feet	Depth, feet	Type Number	Sampling Resistance Blows/6	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	U- -	-			3		Gravish brown, moist, silty CLAY Medium stiff, light tan light gray, silty CLAY	Begin drilling @ 8/25/06 091
	2		2 3 5 7	24.0	5		Medium stiff, light tan light gray, silty CLAY	Moist silt seam ()
	4		3 4 4	24.0	6		Light brownish tan, clayey SILT	Silt seam. Wet ()
	6-		2 4 3	22.0	0		Medium stiff, light tan light gray, silty CLAY  Gray, moist, silty CLAY, medium plasticity	- -
	8-		6 2 2 3	24.0	0		Gray, moist, silty CLAY, trace fine to coarse gravel, low plasticity	-
	10		3 4 3	20.0	0		Gray, moist, silty CLAY, trace fine to coarse gravel, low plasticity	
	12-		5 2 3 3	21.0	0		Gray, moist, silty CLAY, trace fine to coarse gravel, trace rock fragments, low plasticity, (till)	
	-++		2 4 5 6	24.0	0		Gray, moist, gravelly CLAY, with rock fragments, (till)	-
	16-		4 7 8 7	23.0	10		Gray, moist, gravelly CLAY, with rock fragments, (till)	
	18		4 6 4 9	24.0	10		Gray, moist, gravelly CLAY, with rock fragments, low plasticity, (till)	Sample submitted for laboratory analysis ()
	20-		1			ASIA	End of Boring at 20' bgs	End drilling @ 8/25/06 1012
	22						Liu >	
	26							-
	28-						es.	
	30							

Project: - Detrex
Project Location:
Project Number: Detrex

#### Log of Boring IT0603


Date(s) Drilled 8/25/06 1206 and installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 16.00 'bgs
Sampling Method	Drill Bit Size/Type: 4-1/4" ID HSA	Approximete Surface Elevation 632.00
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer Data
Boring Location:		



**Project Number: Detrex** 

#### Log of Boring IT0604

Date(s) Drilled 8/28/06 1205 and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 14.00 bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation 634.00
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boxing Location: Itercepter trench		



Log of Boring IT0605

Project Number: Detrex

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer		
Orilling Method Hollow Stern Auger	Drilling Contractor Northcoast Drilling	Total Depth 16.00 bgs		
Sampling Melhod	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation 636.8ft'		
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer		
Boring Location: East end of IT line				

			SAMI	LES				
Elevation feet	Depth, feet	Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	0		1 2 3 6	14.0	2		Soft, dark brown, moist, slity CLAY, (CL-ML) with organics  Medium stiff, light brown light gray, moist, slity CLAY, (CL-ML) with manganese, low plasticity, mottled, Iron oxide staining	Begin drilling @ Lignt rain during drilling and well instalation ()
	2		2 5 6 7	23.0	2		Soft, dark brown, moist, silty CLAY, (CL-ML) with roots  Medium stiff to soft, light brown light gray, molst, silty CLAY, (CL-ML)  trace roots, low plasticity, mottled	
	4-		2356	20.0	0		Medium stiff, light brown light gray, wet, clayey SILT, (CL-ML) low plasticity, mottled, no staining	_
	6-		2 4 4 6	20.0	1		Medium stiff, light brown light gray, wet, clayey SILT, (CL-ML) low plasticity, mottled, no staining	. "
	8-		3 4 5 7	22.0	1		Medium stiff, light brown light gray, wet, clayey SILT, (CL-ML) low blasticity, mottled, no staining Medium stiff, gray, most, silty CLAY, (CL-ML) trace line to medium	Sample submitted for laboratory analysis ()
i i	10-		1 2 4		1		gravel, medium plasticity Medium stiff, gray, moist, silty CLAY, (CL-ML) trace fine to medium gravel, trace rock fragments, medium plasticity, (till)	
	12		1 2 4 4	24.0			Medium stiff, gray, moist, silty CLAY, (CL-ML) trace fine to medium gravel, trace rock fragments, medium plasticity, (till)	
	14		2 3 4 4				Medium stiff, gray, moist, silty CLAY, (CL-ML) trace fine to medium gravel, trace rock fragments, medium plasticity, (till)	
A 170805	16 - 18					<b>34</b> (A	End of Boring at 16' bgs	End drilling @ 8/28/06 1400
FIN: DETREX IT BORINGS.GPJ; 9/20/2006 IT0805	20						$\sim$ .	
T BORINGS.C	22-		-				DUMBE XI	
B. OETREX	24						<b>*</b> , <b>*</b>	
ió.	26						6. 5-	
Report: URS, CLEV_3CCL_	28-						1	
Report: Ul	30 <u>.T</u>						· ·	

Ргојесt Number: Detrex

# Log of Boring IT0606

Sheet 1 of 1

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer
Orilling Hollow Stern Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 14.00 bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		

1			SAMPLES						
	Elevation feet	Depth, feet	Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
		-		2 4 5 6	18.0	1		Dark brown, dry, silty CLAY, (CL-ML) little roots Medium stiff, light gray light brown, silty CLAY, (CL-ML) trace roots, medium plasticity, mottled	Begin drilling @
		2-		3 3 4 5	21.0	0		Medium stiff, light gray light brown, silty CLAY, (CL-ML) trace roots, medium plasticity, mottled Soft, light brown, very moist, silty CLAY, (CL-ML) trace fine sand,	
		4-1		2 3 3 5		1		medium plasticity  Medium stiff, light brown light gray, moist, silty CLAY, (CL-ML) frace fine sand, trace, low plasticity, motited  Soft, light brown, very moist, silty CLAY, (CL-ML) little fine send, trace	
		6-		4 4 6 7	24.0	1		coarse gravel, low plasticity Medium stiff, light tan light brown, moist, silty CLAY, (CL-ML) trace manganese, medium plasticity, laminated	
		8-		3 3 7 7	21.0	0 *		Medium stiff, gray, moist, silty CLAY, (CL-ML) Softsbrown, very moist, CLAY, (CL) Medium stiff, gray, moist, silty CLAY, (CL-ML) some rock fragments, little fine to medium gravel, medium plasticity, (till)	' Completed boring on second day. Weather light rain. ()
		10-		2 4 6 7	22.0	0		Medium stiff, gray, moist, sitty CLAY, (CL-ML) some rock fragments, little fine to medium gravel, medium plasticity, (till)	·
		12-		5 3 9	24.0	0		Medium stiff to stiff, gray, moist, silty CLAY, (CL-ML) some rock fragments, with fine to medium gravel, medium plasticity, (till)	
		14-							End drilling @
		, ‡	_ ′ ]					End of Boring at 14' bgs	
ıρ		16		ľ				1	
Report: UKS_CLEV_3COL_S; File: DETREX IT BORINGS.GPJ; 9/20/2006 170606		18-		-				P. B. S. S. S. A.	
INGS.GPJ;		20-						8 ° ° € .	
EX IT BOR		7						8.5.70	
File: DETR		24						· · · · ·	
3COL_S.		26-							
UKS_CLEV		28-			į				
Report: (		30-1-							

S. C. FV 3COL S. File DETREY IT BORINGS GB . BOOLDING GB

Project: - Detrex
Project Location:
Project Number: Detrex

# Log of Boring IT0607

Date(s) Drilled and installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 14.00 ' bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		

SAMPLES								
Elevation feet	Depth, feet	Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	0		1 2 4 5	19.0			Soft, brown, very moist, silty CLAY, (CL-ML) trace organics, medium plasticity Medium stiff, light orangeish brown, moist, silty CLAY, (CL-ML) trace organics, low plasticity, mottled	Begin drilling @
	2		3 3 4 5	19.0	2		Medium stiff, light grayish brown, moist, silty CLAY, (CL-ML) trace coarse sand, medium plasticity, mottled	
	4		3 4 6 7		1		Soft, pale orangeish brown, very moist, sandy SILT, (MH) mottled, iron oxide staining	
	6-		3598	19.0	2	200000	Medium dense, pale gravish brown, moist, sandy SiLT, (MH) trace manganese, low plasticity, aminated, fron oxide staining, (Lacustrine)	Sample submitted for laboratory analysis ()
	8		2245	23.0	0		Stiff, light gray, moist, silty CLAY, (CL-ML) medium plasticity, (Till)	endersteiner
	10		2356	23.0	0		Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rook fragments, medium plasticity, (Till)	ACTION TO A CONTROL OF THE PARTY OF THE PART
	12		3 4 4 5	22.0	0		Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rock fragments, medium plasticity, (Till)	. *
	14					<b>44.</b>	End of Boring at 14' bgs	End drilling @
	16-						Pion be	
	20						Pionsk XIV	
	22-		:					
	26-						· -	
	28						- -	
	30							

Log of Boring IT0608 Sheet 1 of 1

Project	Location:	
Project	Number:	Detrex

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 14.00 ' bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		

	-	<u>s</u>	AMP	LES		-		
Elevation feet	Depth, feet Type	Number	Resistance Blows/6"	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	• <b>I</b>	$\neg \vdash$	1				Light brown, very moist, silty SAND, (SM) trace organics	Begin drilling @
	+	808	3 6 8	24.0	1		Medium stiff, light grayish brown, moist, sitty CLAY, (GP-GM) trace organics, low plasticity	1
	2		5 3 4 4	16.0	2		Light grayish brown, moist, silty CLAY, (GM) low plasticity, iron oxide staining	1
	+	808	2 2 5 6	23.0	2		Medium stiff, light orangeish brown, moist, silty CLAY, (GP-GM) medium plasticity	]  -
	6		2 3 4 5	22.0	2		Medium stiff, light brownish gray, moist, clayey SILT, (CL-ML) medium plesticity	- - - -
	8		1 2 2 4	22.0	1		Medium stiff, light gray, moist, slity CLAY, (CL-ME) medium plasticity	and the second
-	10		2	23.0	1		Medium stiff, light gray, moist, clayey SILT, (CL-ML) trace rock fragments, medium plasticity, (till)	Sample submitted for laboratory analysis ()
	12		2 2 4 5	22.0	1		Medium stiff, light gray, moist, clayey SILT, (CL-ML) trace rock fragments, medium plasticity, (till)	
	14-						End of Boring at 14' bgs	End drilling @
	18-						Dons, har xia =	
	20						c/0-xia=	
	22-						~ ·	
	24+							
	28-							
	30							

Project: - Detrex
Project Location:
Project Number: Detrex

### Log of Boring IT0609

Date(s) Drilled	Geologist J. Berk	Reviewer
and Installed  Drilling Method  Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 14.00 bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		

		SAM	PLE\$				
Elevation feet Depth,	EZ	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
		1 6 8	22.0	1		Soft, pale orangeish brown, moist, silty CLAY, (CL-ML) trace organics, with, low plasticity, mottled	Begin drilling @
2		4 4 4 8	22.0	1		Medium stiff, light grayish brown, moist, silty CLAY, (CL-ML) low plasticity, mottled	
4		3 2 2 4	18.0	1		Soft, light brown, wet, sandy SILT, (ML) non plastic	
6		2 4 3 4	18.0	1	1///	Medium stiff, light grayish brown, very moist, silty SAND, (SC)  Medium stiff, light gray, moist, silty CLAY, (GC) low plasticity	
8		2 2 3	19.0	1		Medium stiff, light gray, moist, clayey SILT, (CL-ML) medium plasticity	- -
10		5 2 2 3 4	20.0	1		Medium stiff, light gray, moist, clayey SILT. (CL-ML) trace rock fragments, medium plasticity, (till)	-
12		1 2 /	18.0	1		Medium stiff, light gray, moist, clayey SILT, (CL-ML) little rock fragments, medium plasticity, (till)	-
14	-					End of Boring at 14' bgs	End drilling @
16	- - - -			3 w	,	Dog	
20	<del> </del>					Dombe Ky	•
22	‡						
24 26						· _	
28	‡					-	
30	†					-	

Project: - Detrex
Project Location:
Project Number: Detrex

# Log of Boring IT0610

Sheet 1 of 1

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 24.00 bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		

			SAM	PLES				
Elevation feet	Depth, feet	Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
	- -		1 4 6 7	22.0	3		Medium stiff, light grayish brown, moist, slity SAND, (SM) trace organics	Begin drilling @
	<b>2</b> -		3344	20.0	1		Medium stiff, light grayish brown, moist, silty CLAY, (GM) trace organics, low plasticity	
	4-		2 1 3 5/	17.0	1		Soft, light grayish brown, wet, slity SAND, (SM) manganese, iron oxide staining	
_	6		3 5 7 8	20.0	1		Medium stiff, light grayish brown, moist, silty CLAY, (CL-ML) trace manganese, low plasticity, Iron oxide staining	
,	35-		3 3 6	20.0	2		Medium stiff, light gray, moist silty CLAY, (CL-ML) little rock fragments, low plasticity	
	10		2 3 4 5	22.0	1		Medium stiff, light gray, moist, clayey SILT, (CL-ML) trace rock fragments, medium plasticity	× ,
	12-		3 5 5 8	22.0	4		Silff, light gray, moist, clayey SILT, (CL-ML) with rock fragments, medium plasticity, (Till)	7
	14		4 4 6 7	24.0	3		Stiff, light gray, moist, clayey SILT, (CL-ML) with rock fragments, medium plasticity, (till)	
	16-		4 5 6 8	24.0	2		Stiff, light gray, moist, clayey SILT, (CL-ML) with rock fragments, low plasticity, (Till)	
	18		1 5 7	24.0	2		Stiff, light gray, moist, silty CLAY, (CL-ML) some rock fragments, low plasticity, (Titl)	
	20-		6 8 10 16	20.0	2		Stiff, light gray, moist, silty CLAY, (CL-ML) little silty sand, trace rock fragments, low plasticity, (Till)	
	22	A margaret server	8 10 13 18	22.0	1		Very stiff, light gray, moist, clayey FAT CLAY, (CL) trace rock fragments, low plasticity, (till)	
	24						End of Boring at 24' bgs	End drilling @
	26		è	(A)	/_		All of soming at 24 bigs	
	28				9		K1 /11 )	
	30⊥				!			

Report URS\_CLEV\_3COL\_S; File: DETREX IT BORINGS.GPJ; 9/20/2006 IT0610

Project: - Detrex	
Project Location:	
Project Number:	Detrex

### Log of Boring IT0611

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 18.00 ' bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		


			SAIM	PLES		-		
Elevation feet	Depth, feet	lype Number	Sampling Resistance Blows/6	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
			1 1 4 5	16.0	1		Soft, light grayish brown, moist, slity SAND, (ML) trace organics, low plasticity, mottled	Begin drilling @
	2		3 4 4 6	20.0	4		Soft, light grayish brown, moist, silty SAND, (SM) trace manganese, mottled, iron exide staining	
	6		3 2 2 4	19.0	5		Medium stiff, light grayish brown, very moist, silty SAND, (SM) iron oxide staining	
	8		3 3 6 8	22.0	2		Medium stiff, light grayish brown, moist, silty SAND, (SM) trace clayey silt	
	10		245,9	23.0	3		Medium stiff, light gray, moist, silty CLAY, (CL-ML) low plasticity	
	10-		4 4 6	22.0	3		Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rock-fragments, low plasticity	CONCRETE SERVICE
-			2 4 4 5	22.0	2		Medium stiff, light gray, moist, silty CLAY, (CL-ML) medium plasticity	
	16		3536	18.0	5		Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plasticity, (till)	
	18		2 4 6 7	22.0	5		Stiff) light gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plasticity, (till)	
	20-						End of Boring at 18' bgs	End drilling @
	22-		1 ps	$ \wedge $			Poor	
	24						Donathe Kin	
	26							
	28							
	30 <u>+</u>							

**Project Number: Detrex** 

#### Log of Boring IT0612

Sheet 1 of 1

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 18.00 ' bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		



Report URS\_CLEV\_3COL\_S; File: DETREX IT BORINGS.GPJ; 9/20/2006

Project Number: Detrex

# Log of Boring IT0613

Date(s) Dniled and installed	Geologist J. Berk	Reviewer
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 18.00 ' bgs
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer
Boring Location:		

		SAIM	PLES				
Elevation feet Depth,	Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA,	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
		1 4 5 8	20.0	7		Dry, silty CLAY, (GC) trace organics, non plastic, mottled Medium stiff, light grayish brown, very moist, sandy SILT, (ML) trace clayey silt, non plastic	Begin drilling @
2.		5 8 9 11	18.0	20		Medium stiff, light grayish brown, moist, clayey SILT, (MH) trace clayey sand, non plastic, mottled	
4.		2 3 3 5	21.0	20		Soft, light grayish brown, very moist, silty SAND, (SM) trace clayey silt, fine to medium grained, iron oxide staining Soft, light grayish brown, very moist, silty SAND, (SP-SC) fine to medium grained	
6-		2 4 5 7	21.0	12		incoluit granted	1
- - -		2 1 4 5	22.0	23		Light grayish brown, moist, clayey SILT, (ML) trace clayey sand, low plasticity	
10-		3 4 5	20.0	12		Medium stiff, light grayish brown, moist, clayey SILT, (MH) trace silty sand, non plastic Medium stiff, light gray, moist, clayey SILT, (MH) trace, low plasticity,	
12		6 1 2 3 4	24.0	30		eiron oxide staining.  Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plaeticity, (till)	·
14-		2 3 4 5	23.0	12		Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plasticity, (till)	ľ
16-		2 2 3 4	24.0	7		Medium stiff, light gray, moist, silty CLAY, (CL-ML) with rock fragments, low plasticity, (till)	
18-		- 4			444	End of Boring at 18' bgs	End drilling @
20-						Popola	
22-						Porsisa My	
24-						/2 / -	
26-							
28-						-	

Project Number: Detrex

# Log of Boring IT0614

Sheet 1 of 1

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer	
Drilling Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 22.00 bgs	
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation	
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer	
Boring Location:			

			SAM	PLES				
Elevation feet	Depth, feet	Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA, ppm		MATERIAL DESCRIPTION	FIELD NOTES
			1 3 2	18.0	0		Loose, light orangeish brown, molst, silty SAND, (SP-SM) little wood, trace organics, trace rock fragments, medium grained	Begin drilling @
	2		1 1 2 2	19.0	0		Soft, light grayish brown, very moist, sandy SILT, (ML) trace, non plastic, mottled, iron oxide staining	
	4		1 1 2 4	20.0	0		Soft, light grayish brown, moist, silty SAND, (GC) trace clay, non plastic	
	6-		3 5 7	22.0	0		Medium stiff, light grayish brown, moist, clayey SILT, (ML) trace clayey sand, low plasticity	
	8-		4 6 5 6	20.0	0		Medium stiff, light brownish gray, moist, silty CLAY, (CL-ML) trace coarse sand, low plasticity	·.
9	10		4 3 4 5	21.0	1		Medium stiff, fight gray, moist, silly CLAY, (CL-ML) trace rock fragments, medium plasticity	
	12-		1 3 4 5		1		Medium stiff, light gray, moist, silty CLAY, (CL-ML) trace rock fragments, low plasticity	
	14-		2 4 9 11	24.0	3		Stiff, light gray, moist, slity CLAY, (CL-ML) trace clayey sand, with rock fragments, low plasticity	€COme do se
	16-		5 8 11	20.0	5		Medium stiff, light gray, silty CLAY, (CL-ML) with rock fragments, low plasticity, (till)	
	18-		7 8 10 17	24.0	3		Stiff, light gray, molst, silty CLAY, (CL-ML) with rock fragments, low plasticity, (till)	
	20-		10 12 17 30	20.0	3		Very stiff, light gray, moist, silty CLAY, (CL-ML) some rock fragments, non plastic, (till)	
	24					,	End of Boring at 22" bgs	End drilling @
	26-					M	Oca Se XII	
	30							
_			,				10-	J

Report URS\_CLEV\_3COL\_S; File: DETREX IT BORINGS.GPJ; 9/20/2006 IT0614

Project: - Detrex
Project Location:
Project Number: Detrex

### Log of Boring IT0615

Date(s) Drilled and Installed	Geologist J. Berk	Reviewer	
Drilling Method Hollow Stem Auger	Drilling Contractor Northcoast Drilling	Total Depth of Borehole 18.00 ' bgs	
Sampling Method	Drill Bit Size/Type: 3-1/4" ID HSA	Approximete Surface Elevation	
Drill Rig Type: Truck-mounted CME	Groundwater Level(s)	Hammer 140# auto hammer	
Boring Location:			


		SAMI	LES		1		1
Elevation feet Depth, feet	.Type Number	Sampling Resistance Blows/6"	Recovery, inches	PID, OVA, ppm	Graphic Log	MATERIAL DESCRIPTION	FIELD NOTES
4		1 3 3 3	18.0	1		Soft, light brownish gray, moist, sandy SiLT, trace organics, low plasticity, mottled	Begin drilling @
2-		2 2 2 3	16.0	3		Soft, light brownish gray, moist, sandy SILT, (ML) non plastic, iron oxide staining	
6		2 4 7 10	20.0	3		Medium stiff, light grayIsh brown, moist, sandy SILT, (ML) trace clayey silt, non plastic, iron oxide staining	
8-		2 4 7 9	22.0	1		Medium stiff, light brownish gray, moist, clayey SiLT, (CL-ML) low plasticity, mottled	
10-		2 2 2 3	22.0	1		Medium stiff, light gray, moist, slity CLAY, (CL-ML) medium plasticity	<b>≪</b> Mbd s
10-		2 2 3 4		1		Medium stiff, light gray, moist, clayey SiLT, (CL-ML) trace rock fragments, low plasticity	
14		2344	22.0	1		Medium stiff, light gray, moist, clayey SILT, (CL-ML) trace silty sand, low plasticity	
16		2 3 5 7	24.0	1		Medium stiff, light gray, moist, silty CLAY, (CL-ML) some rock fragments, low plasticity, (till)	
18	the procession of	3 4 7 8	18.0	1		Stiff, light gray, moist, silty CLAY, (CL-ML) some rock fragments, low plasticity, (tili)	
20-		1	5~			End of Boring at 18' bgs	End drilling @
22						Prook X, 4.	
26						· / · · · · · · · · · · · · · · · · · ·	
28					- A A A A A A A A A A A A A A A A A A A	-	

Project: **Detrex Corporation** Project Location: Ashtabula, Ohio **Project Number:** 

5E06680

# Log of Boring MP-1

Date(s) Drilled	1/27/97		Logged By	R. Fabian	Checked By	N. Sauer	
Drilling Method	Hollow-St	em Auger	Drill Bit Size/Type	4-1/4-inch-ID / 8-inch-OD auger	Top of Casing 636.38 feet MSI		
Drill Rig Type	Failing F-7		Drilling Contractor	Lehti Drilling	Total Depth	22.0 feet	
Groundwater and Date Mee	Depth sured Not	measured	Samplar Type	2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop	
Diameter of Hole (inches)	8	Diameter of 2 Well (inches)	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot	
Type of Sand Pack	Filter sand		Type/Depth of Seal(s)	Bentonite 6-4.5 ft, bentonite g	rout 4.5 ft to s	urfece	
Comments	Drilled 10	feet east of Recovery	Well RW-1; see	site plan for location.			




Project: Detrex Corporation

Project Location: Ashtabula, Ohio

Project Number: 5E06680

# Log of Boring MP-2

Date(s) Drilled	1/28/97	Logaed By	R. Fabian	Checked By	N. Sauer			
Drilling Method	Hollow-Stem Auger	Drift Bit Size/Type	4-1/4-inch-ID / 8-inch-OD auger	Top of Casing 636.09 feet !				
Drill Rig Type	Failing F-7	Drilling Contractor	Lehti Drilling	Total Depth	22.0 feet			
	roundwater Depth d Date Measured ameter of g Diameter of 2		2 x 24-inch split spoon	Hammer Data	140 lbs, 30-inch drop			
Diameter of Hole (inches)	8 Diameter of Well (inches) 2	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot			
Type of Sand Pack	Filter sand	Type/Depth of Seal(s)	Bentonite 6-4.5 ft, bentonite g	Data 140 lbs, 30-link				
Comments	Drilled 20 feet south of Recovery	Well RW-1; se	e site pisn for location.					




Project: Detrex Corporation
Project Location: Ashtabula, Ohio

Project Number: 5E06680

### Log of Boring MP-3

Date(s) Drilled	1/28/97		Logged By	R. Fabian	Checked By	N. Sauer	
Drilling Method	Hollow-Stem Auger	Hollow-Stem Auger		4-1/4-inch-ID / 8-inch-OD auger	Top of Casing 636.30 feet N		
Drill Rig Type			Drilling Contractor	Lahti Drilling	Total Depth	24.0 feet	
Groundwater I and Date Meas			Sampler Type	2 x 24-inch split spoon, Shelby	Hammer Data	140 lbs, 30-inch drop	
Diameter of Hole (inches)	8 Diameter of Well (inches)	2	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot	
Type of Sand Pack	Filter sand		Type/Depth of Seal(s)	Bentonite 6-4.5 ft, bentonite g	rout 4.5 ft to s	urface	
Comments	Drilled 10 feet west of i	Recovery W	ell RW-1; sec	site plan for location.			




Project: Detrex Corporation
Project Location: Ashtabula, Ohio

Project Number: 5E06680

# Log of Boring MP-4

Date(s) Drilled	1/28/97 - 1/29/97	Logged By	R. Fabian	Checked By	N. Sauer	
Drilling Method	Hollow-Stem Auger	Drill Bit Size/Type	4-1/4-inch-ID / 8-inch-OD auger	Top of Casing 636.18 feet MS		
Drill Rig Type	Failing F-7	Drilling Contractor	Lahti Drilling	Total Depth	24.0 feet	
Groundwater I and Date Meas		Sampler Type	2 x 24-inch split spoon, Shelby	Hammer Data	140 lbs, 30-inch drop	
Diameter of Hole (inches)	8 Diameter of Well (inches) 2	Type of Well Casing	Schedule 40 PVC	Screen Perforation	0.010-inch slot	
Type of Sand Pack	Filter send	Type/Depth of Seal(s)	Bentonite 6-4.5 ft, bentonite g	rout 4.5 ft to s	surface	
Comments	Drilled 40 feet north of Recovery	Well RW-1; se	e site plan for location.			



1	IARE	TES	T BORING	LOG	NO. RMI	- 25	
	PORATED		-,-,-		SHEET NO. 1 0	<del></del>	
PROJECT: KCK	A FACILITY	INVESTIGA	7101		PROJECT NO. 6	120	
	I SODIUM PL	4 K	1	SAMPLING	METHODS		
CONTRACTOR: P	ILLING DATA	20111110 00		SAMPLER	TUBE	COR	E
			TYPE	JAMILLI	5 cont. SPLIT TUBE		
DRILLER: BU	SRNIE GOLL	THUE	DIAMETER		411		
EQUIPMENT: RO	07ARY 80	D AVKER					
METHOD:			OTHER WELL DEV	FLORMENT	GROUND	WELL F	ROT CSG.
WE	ELL CONSTRUCT			ELOPMENT	ELEV 636,3	638.64	
	RISER	INTAKE	METHOD:		DATE STARTED:		9 - 88
MATERIAL	Teflon	Teflon	DURATION:		DATE COMPLETE		
DIAMETER	2"	2"	YIELD:		INSPECTOR: Re	B GUID	EY
COUPLING	THREADED	THREADED	OTHER:		Marcolon Re		
WĒLL CONSTRUCTION	NO. TYPE	PLE	CLASSIFICA	TION	REMARKS	,	
OOMO THE OTTOIL	W W TYPE	BLOWS PER	(AFTER BURMIST		// // // // // // // // // // // // //		HNU
	100 1111	6 INCHES					
/	}	GRAY	SILTY CLAY, ER	Acc(+) SanD	0,4,00		
/ š / / /	<b> </b>		•		CLAY CAP		6000
*//	+   /			3,5'			6pm
em ENT/Bentonite grout		Mo	Etled BROWN AND C	FRAY SILTY CLAY			
	-5 -			.,			
/8							
	2		. 1				llaph
73   /			grades to		WEATHERED TI	L C	llppm
$\left\langle \vec{\xi} \right\rangle$	.						
/0 /		E A A III	CLAY + SILT,	Learn fine Gener			
	T10   -						
MAN Herrin	1			LE PLANES THROWHOUT		•	
	3	THIN.	fine Sound lense @12.	8-12.9' 12.9'			
William Will	-						
	-		SILTY CLAY				1.50.4
·   /    ! · ·	-15	0×101	ZED FRACTURES	present 15.9	UNWEATHERE	DTILL	150ppm
	-				-1		
·   ·   =   · ·	- 4	GRAN	Clayey SILI, &	Erace(t) fine Sand, el			
		ta	ace () time likav	el			
	-	SILT	and fine Sound 16	aminations increase			
.PACK.	20 -	4 pm	4 70,50 5116.				
2		5mal.	L PINK CLAY INCLU	21.61			
	- 5			fine Sand-filled	1		
		FRAC	tures				13000
			· SILTY CLAY	23.7	†		
[	25	UIREY		25′			
			END OF BO	>RING			
	<b> </b>						
	<b> </b>						
	-30	-					
	<b> </b>						
	<u> </u>	<b></b>					
	-						
	<b>L</b>						
	_35						1
<b>.</b>							
1							
		·		•			
	-40						
	T						


Project: Fields Brook Superfund Site - Ashtabula, Ohio

## Log of Boring RMSMW058

Project Number: 86C3609K

Boring Location: RMI Titanium Company (Sodium Plant)

Date(s) Drilled	2/3/93	Logged E. Page	Checked J.A. Ozimek
Drilling Method	Hollow stem suger	Auger Bit Size/Type (in. I.D.) 4.25	Approx. Surface Elevation (feet, MSL) 635.6
Drill Rig Type	Feiling F-7	Drilled Lehti Drilling By	Total Depth 20.2
Groundwater Elevation (feet,	, MSLJ	Number of Samples Collected: 8 Analyzed: 3	Sampler Continuous sample
Diameter of Hole (inches)	8.25 Diameter of 2 Well finches)	Type of PVC Well Casing	Screen 0.010 in.
Type of Sand Pack	20 mesh	Type/Thickness 2.5 ft. Bentonite pellete of Sealts)	
Comments			Top of Well Casing Elevation (feet, MSL) 638.22



(WL-01) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND ¥

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO1-01 DATE COMPLETED: JANUARY 9, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

EPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	<del></del> _	ANAL	YS
BGS	GROUND SURFACE	ft. AMSL	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	010
	GROUND SURFACE	1		ž		(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	60,	
	TOPSOIL	609.3						
5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist to very moist  - black stain, faint odor @ 2.3ft BGS	000.0			2.0 2.3	0		
5	CL-SILTY CLAY, soft, low plasticity, light gray,	606.8			3.0	0		
	very moist						] .	
.0	- firm @ 5.0ft BGS				5.0	0		
						•		
.5	BOTTOM OF TEST PIT @ 7.0ft BGS	602.5			7.0	0	<u> </u>	
	NOTE:							
.0	<ol> <li>Elevation of NE end of TT01-01 is 610.1ft AMSL, and the SW end is 609.5ft AMSL.</li> </ol>						ĺĺ	
İ								
:.5								
.0								
}		}	j	]				
_							. [	
.5							1	
0.0				İ				
J				J				
2.5								
					ļ		}	
					}			
5.0								
7.5			}		{			
					ļ			
0.0				[				
2.5				- 1				
				l				
						-		

(WL-02) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO2-01 DATE COMPLETED: JANUARY 9, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	.YSI
ft. BGS	GROUND SURFACE	ft. AMSL 610.1	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	TOPSOIL  MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist to very moist	609.8						
-2.5	- gray, wet, dilatant @ 3.0ft BGS	606.4	Indududa.		3.0	0		
-5.0	CL-SILTY CLAY, trace sand, firm, low plasticity, gray, moist	604.6		,	4.5 5.5	0		
7.5	BOTTOM OF TEST PIT @ 5.5ft BGS  NOTE:  1. Elevation of SW end of TT02-01 is 610.6ft AMSL, and the NE end is 610.1ft AMSL.							
10.0								
12.5								
15.0								:
17.5								
20.0					ļ			
22.5								
25.0								
27.5								
30.0								
32.5								
			1	1	ŀ	}	1	

(WL-03) Page 1 of 1

PROJECT NAME: FIELDS BROOKS SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO3-01 DATE COMPLETED: JANUARY 9, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC	<u> </u>	SAMPLE	т	ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 611.3	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	TOPSOIL (dark brown, silt, trace sand)  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist	611.0			2.0	0		
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	607.3			4.0	0		
-	BOTTOM OF TEST PIT @ 6.0ft BGS	605.3		007	5.5	0		•
-7.5	NOTE: 1. Elevation of SE end of TT03-01 is 612.3ft AMSL, and the NW end is 611.3ft AMSL.							
10.0								
-12.5								
-15.0	•							
-17.5								
-20.0								
-22.5								
25.0								
27.5								
30.0								
32.5								
02.0						}		

(WL-04) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO4-01 DATE COMPLETED: JANUARY 9, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	T	ANAL	.YS
t. BGS	GROUND SURFACE	ft. AMSL 612.8	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	I A OT MOUNT
<del></del>	TOPSOIL (dark brown, silt, trace sand)	612.5				<del> </del>	<del> </del>	├
2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist				2.0	0		
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	608.8			4.0	2.0		
7.5	– strong odor @ 6.0ft BGS				7.0	180+		
_	BOTTOM OF TEST PIT @ 9.0ft BGS	603.8			9.0	2000+		
-10.0	NOTE: 1. Elevation of SW end of TT04-01 is 612.8ft AMSL, and the NE end is 614.9ft AMSL.			:				
12.5								
15.0						į		
17.5								
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								
	ES: MEASURING POINT ELEVATIONS MAY CHANGE							

(WL-05) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO5-01
DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 620.2	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
_	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist to very moist				2.0	0		
-2.5		616.2			4.0	0	 	
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	614.2			6.0	0		
7.5	BOTTOM OF TEST PIT @ 6.0ft BGS  NOTE:  1. Elevation of W end of TT05-01 is 620.2ft  AMSL, and the E end is 620.2ft AMSL.				<b>3.0</b>			
10.0								
12.5								
15.0								
17.5								l
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								
					}			

(WL-06) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO6-01 DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	CAMBLE DECOMPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	YSIS
ft. BGS	SAMPLE DESCRIPTION	ft. AMSL	LOG	3ER	SAMPLE	PID	Zщ	CAL
:	GROUND SURFACE	620.2		NUMBER	INTERVAL	(ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace to with sand, compact, fine grained, poorly graded, brown, moist to very moist				2.0	0		
-5.0	- silt, some sand, gray, very moist to wet, odor @ 4.3ft BGS	615.2			4.5	7.0		
-7.5	CL-CLAY, some silt, stiff, low plasticity, gray, moist, strong odor BOTTOM OF TEST PIT @ 6.0ft BGS NOTES:	614.2						
-10.0	<ol> <li>DNAPL in pockets and cracks, dark brown.</li> <li>Sheen in water.</li> <li>The elevation of the S end of TT06-01 is 620.6ft AMSL, and the N end is 620.2ft AMSL.</li> </ol>							
-12.5								
-15.0								
-17.5								
-20.0		y.						
-22.5								
25.0								
-27.5								
30.0								
32.5								

(WL-07) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO7-01 DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	619.1	106	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, light brown, moist				2.0	0		
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	615.1			5.0	9.8		
7.5	BOTTOM OF TEST PIT @ 8.0ft BGS	611.1		!				
10.0	NOTE:  1. Elevation of S end of TT07-01 is 619.7ft AMSL, and the N end is 619.1ft AMSL.					!		i
12.5						·		
5.0						ļ		
17.5								
20.0								
22.5								
25.0								
27.5								
0.0								
2.5								

(WL-08) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TTO8-01 DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	,	ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 618.0	L0G	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist				2.0	0		
	CL-CLAY, some silt, stiff, low plasticity, gray,	614.5						
5.0	moist	612.0			5.0	15.0+		
7.5	BOTTOM OF TEST PIT @ 6.0ft BGS  NOTE:  1. Elevation of S end of TT08-01 is 620.3ft  AMSL, and the N end is 618.0ft AMSL.							
10.0								
12.5								
15.0					ļ			
17.5								
20.0								
22.5								
25.0							}	
27.5								
30.0								
32.5								
1			1		1		- 1	

(WL-09) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT09-01 DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	,	ANAL	_
ft. BGS	GROUND SURFACE	ft. AMSL 616.4	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	TA OTA CITO
2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist				2.0	0		
2.5	CL-CLAY, with to some silt, stiff, low plasticity, gray, moist	613.4		,	4.0	0		i
5.0	BOTTOM OF TEST PIT @ 5.5ft BGS	610.9			5.0	0		
7.5	NOTE: 1. Elevation of S end of TT09-01 is 617.8ft AMSL, and the N end is 616.4ft AMSL.							
0.0								
12.5								
5.0								
7.5								
0.0								
2.5								
5.0								
7.5								
0.0								
2.5								
	TES: MEASURING POINT ELEVATIONS MAY CHANGE:							

(WL-10) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT10-01
DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	<del></del>	ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 616.5	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  CL-CLAY, some silt, stiff, low plasticity, gray,	614.0			2.0	0		
5.0	moist				4.0	0		
-5.0	BOTTOM OF TEST PIT @ 6.0ft BGS	610.5			6.0	0		
7.5	NOTE: 1. Elevation of S end of TT10-01 is 620.5ft AMSL, and the N end is 616.5ft AMSL.							
10.0								
12.5								
15.0								
17.5								
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								

(WL-11) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT11-01
DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH [	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	YSIS
ft. BGS	GROUND SURFACE	ft. AMSL 616.6	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT (FILL), trace sand, some chunks of gray clay, compact, fine grained, poorly graded, brown, moist				2.0	0		3
-5.0	CL-CLAY, with silt, very stiff, low plasticity, gray, moist	612.1			6.0	0		
-7.5	BOTTOM OF TEST PIT @ 6.5ft BGS  NOTE:  1. Elevation of S end of TT11-01 is 622.6ft	610.1						
-10.0	AMSL, and the N end is 616.6ft AMSL.							
-12.5								
-15.0								
-17.5								
-20.0								
-22.5								
-25.0								
-27.5								
-30.0								
-32.5								

(WL-12) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT12-01
DATE COMPLETED: JANUARY 10, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

EPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	r	ANAL	
t. BGS	GROUND SURFACE	ft. AMSL 616.6	L06	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
2.5	MH-SILT (FILL), trace sand, some clay chunks, compact, fine grained, poorly graded, gray and brown, moist				2.0	0		
5.0	CL-CLAY, some silt, trace sand, firm to stiff,	612.1			4.0	300+		
.0	low plasticity, gray, moist, clay is stratified/fissured with sand and silt				6.0	300+		
.5					8.0	300+		
0.0	BOTTOM OF TEST PIT @ 9.0ft BGS  NOTE:  1. Elevation of S end of TT12-01 is 622.5ft	607.6						
2.5	AMSL, and the N end is 616.6ft AMSL.							
5.0					:			
7.5								
0.0								
2.5								
5.0								
7.5								
0.0								
2.5								
			1				}	

(WL-13) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT13-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
t. BGS	GROUND SURFACE	ft. AMSL 617.2	LOG	NUMBER	SAMPLE INTERVAL	(ppm)	GRAIN SIZE	CHEMICAL
2.5	MH-SILT, trace to with sand, compact, fine grained, poorly graded, brown, moist				2.0	0		
	- wet, sheen on water @ 4.2ft BGS	612.7			4.0	50+		
5.0	CL-CLAY, some silt, clay stratified with silt and sand, firm, gray, wet	610.7			6.0	150+		
7.5	BOTTOM OF TEST PIT @ 6.5ft BGS  NOTES:  1. DNAPL on clay, dark brown.  2. Elevation of S end of TT13-01 is 618.8ft							
10.0	AMSL, and the N end is 617.2ft AMSL.							
12.5							j	
15.0								
17.5								•
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								
					ĺ			

(WL-14) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP14-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

11. Biss	DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
poorly graded, brown, moist  2.5.0  -5.0  -7.5  -10.0  -7.5  -10.0  -12.5  -12.5  -13.0  -14.5  -15.0  -15.0  -15.0  -17.5  -20.0  -22.5  -25.0  -27.5	ft. BGS		_	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
-7.5 -10.0 -12.5 -15.0 -17.5 -17.5 -20.0 -27.5	-2.5	MH~SAND, with silt, compact, fine grained, poorly graded, brown, moist							
CL-CLAY, some silt, stiff, low plasticity, gray, moist BOTTOM OF TEST PIT @ 13.0ft BGS  15.0  -17.5  -20.0  27.5	-5.0								
-12.5 CL-CLAY, some silt, stiff, low plasticity, gray, moist BOTTOM OF TEST PIT @ 13.0ft BGS -15.0 -17.5 -20.0 -22.5 -25.0 -27.5	-7.5					8.0	0		
-12.5 CL-CLAY, some silt, stirt, low plasticity, gray, moist BOTTOM OF TEST PIT @ 13.0ft BGS  -15.0 -20.0 -22.5 -25.0 -27.5	-10.0		2005						
-15.0 -17.5 -20.0 -22.5 -25.0 -27.5	-12.5	moist				12.0	0		
-20.0 -22.5 -25.0 -27.5	-15.0								
-22.5 -25.0 -27.5	-17.5								
-25.0	-20.0								
-27.5	-22.5								
	-25.0								
-30.0	-27.5								
	-30.0								
-32.5	-32.5								

(WL-15) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT15-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	·	ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 618.3	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				2.0	0		
5.0					4.0	o		
7.5	CL-CLAY, some silt, stiff, low plasticity, gray,	610.8			6.0 8.0	0 500+		
10.0	moist, strong odor  BOTTOM OF TEST PIT @ 9.5ft BGS	608.8						
12.5	NOTE: 1. Elevation of SE end of TT15-01 is 619.6ft AMSL, and the NW end is 618.3ft AMSL.							
15.0								
17.5								
20.0								
22.5								
25.0								
27.5								
0.0								
2.5								
	TES: MEASURING POINT ELEVATIONS MAY CHANGE;	200	DUDDENT STEWA	77011	ADIE			_

(WL-16) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT16-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

					······································		·	
DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE	<del></del>	ANAL	
ft. BGS	GROUND SURFACE	618.8	LUG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist to very moist				3.0	0		
-5.0					6.0	0		
<b>−</b> 7.5 <b>−</b>	CL-CLAY, some silt, stiff, low plasticity, gray, moist	611.3			7.5	19.5		
-10.0	BOTTOM OF TEST PIT @ 9.5ft BGS	609.3		013	9.5	15+		•
-12.5	NOTE: 1. Elevation of SE end of TT16-01 is 619.5ft AMSL, and the NW end is 618.8ft AMSL.							
-15.0								
-17.5						í		
-20.0								
-22.5		:						
-25.0								
-27.5								
-30.0								
-32.5								
NO	TES: MEASURING POINT ELEVATIONS MAY CHANGE; F	REFER TO (	CURRENT ELEVA	TION T	ABLE			_

(WL-17) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT17-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DESCRIPTION		GRAPHIC		SAMPLE		ANAL	
URFACE	ft. AMSL 621.8	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
compact, fine grained, n, moist, no odor/stain				2.0 4.0	0		<u> </u>
iff, low plasticity, gray,	616.8			6.0	0		
T @ 7.0ft BGS	614.8				-		
l of TT17-01 is 622.0ft is 621.8ft AMSL.							
			TELEVATIONS MAY CHANCE DEED TO CURRENT ELEVA	T ELEVATIONS MAY QUANCE. DEFER TO CURRENT ELEVATION T	TELEVATIONS MAY CHANCE PEEED TO CHERENT ELEVATION TARLE	T EL EVATIONS MAY CHANGE: REFER TO CURRENT EL EVATION TARLE	

(WL-18) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT18-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
t. BGS	GROUND SURFACE	ft. AMSL 620.9	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist to very moist			Ž	1			2
2.5		646.0			2.0	0		
5.0	CL-CLAY, with silt, stiff, low plasticity, gray, moist	614.9			4.0 5.0	50-100 100+		
7.5	BOTTOM OF TEST PIT @ 6.0ft BGS  NOTES:  1. DNAPL on clay, dark brown.  2. Elevation of S end of TT18-01 is 621.5ft  AMSL, and the N end is 620.9ft AMSL.					i		
10.0	ANGE, and the West is decised an out							
12.5								
5.0								ı
7.5								
20.0								
2.5								
5.0								
7.5								
0.0								
2.5								
02.0						}	}	

(WL-19) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT19-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 620.9	L06	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist to very moist				2.0	0		
-5.0	- sheen on water @ 4.0ft BGS  CL-CLAY, with silt, sand and silt fissures in clay, firm to stiff, low plasticity, gray, moist, sheen on water	618.9 615.4			4.5 5.0	50-100 50-100		
-7.5	BOTTOM OF TEST PIT @ 5.5ft BGS  NOTES: 1. DNAPL pockets on clay.							
-10.0	2. Elevation of S end of TT19-01 is 621.3ft AMSL, and the N end is 620.9ft AMSL.							
-12.5								
-15.0								
-17.5								
-20.0							;	
-22.5								
-25.0								
-27.5								
-30.0								
-32.3								

(WL-20) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT20-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	YSIS
ft. BGS	GROUND SURFACE	ft. AMSL 618.5	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				2.0	0		
-5.0	CL-CLAY, some silt, firm, low plasticity, gray, moist, clay has fractures/fissures of sand	614.5			4.0	25-50		
_7 <i>.</i> 5	BOTTOM OF TEST PIT @ 6.5ft BGS	612.0			6.5	25-50		
-10.0	<ol> <li>Elevation of SW end of TT20-01 is 618.5ft AMSL, and the NE end is 620.7ft AMSL.</li> </ol>							
—12.5								
-15.0								
-17.5								
-20.0								
-22.5								
-25.0								
-27.5								
-30.0								
-32.5								
NI	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO (	CURRENT FLEVA	TION T	ABIF			4

(WL-21) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT21-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH t. BGS	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE	r	ANAL	
t. BG5	GROUND SURFACE	619.4	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				2.0	0		-
2.5								
5.0	<ul> <li>wet @ 3.9ft BGS</li> <li>CL-CLAY, with silt, stiff, low plasticity, gray, moist</li> </ul>	615.4			4.0 4.0	40 5.0		
-	BOTTOM OF TEST PIT @ 6.5ft BGS	612.9						
7.5	NOTES:  1. Slight sheen on water along creek.  2. Elevation of S end of TT21-01 is 619.4ft							
0.0	<ol><li>Elevation of S end of TT21-01 is 819.4ft AMSL, and the N end is 619.8ft AMSL.</li></ol>				;			
12.5								
5.0								
7.5								
20.0								
2.5					ļ			
25.0								
7.5								
0.0								
2.5								
						}	}	

(WL-22) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT22-01 DATE COMPLETED: JANUARY 11, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH ft. BGS	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE	т —	ANAL	
11, 803	GROUND SURFACE	619.2	200	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist							
-2.5					3.0	0		
5.0	- very moist @ 4.8ft BGS CL-CLAY, with silt, stiff, low plasticity, gray,	614.2			4.5	25-40		
7.5	BOTTOM OF TEST PIT @ 7.0ft BGS	612.2			7.0	18.4		
10.0	NOTES: 1. DNAPL present on clay. 2. Sheen present in wet sand pockets. 3. Elevation of S end of TT22-01 is 619.2ft AMSL, and the N end is 619.9ft AMSL.							
12.5								
15.0								
17.5								
20.0								
22.5								
25.0								
27.5								,
30.0								
32.5								

(WL-23) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT23-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL		NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	OL-ORGANIC SILT, trace sand, loose, fine grained, poorly graded, gray, white, very moist				3.0	12.8		
-5.0					6.0	16.2		
-7.5	CL-CLAY, with silt, firm, low plasticity, gray, moist	610.7			8.0	75+		
-10.0 -12.5								
-15.0	BOTTOM OF TEST PIT @ 15.0ft BGS	- 602.7			15.0	10-15		
-17.5	NOTES: 1. DNAPL present on clay. 2. Elevation of S end of TT23-01 is 617.7ft AMSL, and the N end is 623.0ft AMSL.							
-20.0								
-22.5								
-25.0								
27.5								
30.0								
ı		1	1	- 1	{	-	1	

(WL-24) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT24-01
DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	CAMPLE DECODEDITION	ELEV.	GRAPHIC		SAMPLE		ANAL	YSIS
ft. BGS	SAMPLE DESCRIPTION	ft. AMSL	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	OL-ORGANIC SILT, trace sand, loose, fine	615.9		N N		(ppiii)	95 S	_뚬
	grained, poorly graded, gray and white, very moist			ı				
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, very moist	613.4						
-5.0	CL-CLAY, with silt, stiff, low plasticity, gray, moist	611.4						
-7.5	BOTTOM OF TEST PIT @ 6.5ft BGS	609.4		001	6.0	50+		•
-7.5	NOTES: 1. DNAPL present on clay. 1. Elevation of SE end of TT24-01 is 615.9ft							
-10.0	AMSL, and the NW end is 617.2ft AMSL.							
-12.5								i
-15.0		<u> </u>						
-13.0								
-17.5					j			
-20.0								
-22.5								
-25.0			ı e					
-27.5								
-30.0								
-32.5								
N01	TES: MEASURING POINT ELEVATIONS MAY CHANGE; R	EFER TO (	CURRENT ELEVAT	TION T	ABLE			-

(WL-25) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT25-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

SAMPLE DESCRIPTION	ELEV.	GRAPHIC	<u> </u>	SAMPLE		ANAL	
GROUND SURFACE	ft. AMSL 615.0	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist							
				3.0	o		
<ul> <li>very moist @ 4.9ft BGS</li> <li>CL-CLAY, with silt, very stiff, low plasticity, gray, moist</li> </ul>	610.0		002	5.5	150		•
			003	10.0	150-200+		•
BOTTOM OF TEST PIT @ 14.5ft BGS	600.5						
NOTE: 1. Elevation of SE end of TT25-01 is 615.0ft AMSL, and the NW end is 616.1ft AMSL.							
	BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE:  1. Elevation of SE end of TT25-01 is 615.0ft	GROUND SURFACE  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  - very moist @ 4.9ft BGS  CL-CLAY, with silt, very stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE:  1. Elevation of SE end of TT25-01 is 615.0ft	GROUND SURFACE  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  - very moist @ 4.9ft BGS  CL-CLAY, with silt, very stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE:  1. Elevation of SE end of TT25-01 is 615.0ft	GROUND SURFACE  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  - very moist @ 4.9ft BGS  CL-CLAY, with silt, very stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE:  1. Elevation of SE end of TT25-01 is 615.0ft	GROUND SURFACE  BIS.0  SAMPLE INTERVAL  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  3.0  - very moist @ 4.9ft BGS  CL-CLAY, with silt, very stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE:  1. Elevation of SE end of TT25-01 is 615.0ft	GROUND SURFACE  BIS.0  SAMPLE INTERVAL (ppm)  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  3.0  - very moist @ 4.9ft BGS  CL-CLAY, with silt, very stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE: 1. Elevation of SE end of TT25-01 is 615.0ft	GROUND SURFACE  615.0  MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  3.0  - very moist @ 4.9ft BGS  CL-CLAY, with silt, very stiff, low plasticity, gray, moist   610.0  002  5.5  150  BOTTOM OF TEST PIT @ 14.5ft BGS  NOTE:  1. Elevation of SE end of TT25-01 is 615.0ft

(WL-26) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP26-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 615.9	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
0.5	MH-SAND, with silt, compact, fine grained, poorly graded, brown, moist							
-2.5					4.0	0		
-5.0	CL-CLAY, some silt, trace sand, stiff, low plasticity, gray, moist	610.9			7.0	4.5		
-7.5	BOTTOM OF TEST PIT @ 8.0ft BGS	607.9						
-10.0 -12.5								
-12.5 -15.0								
-17.5								
-20.0								
-22.5								
-25.0								
27.5								
-30.0								
32.5								
72.0								

(WL-27) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP27-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE	γ	ANAL	
ft. BGS	GROUND SURFACE	616.5	100	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist							
-2.5					3.5	0		
-5.0	CL-CLAY, some silt, vertical sand fissures, firm to stiff, low plasticity, gray, moist, clay is stained red, brown and black	611.5			6.0	3.2		
-7.5					8.5	150+		
-10.0								
-12.5	BOTTOM OF TEST PIT @ 12.0ft BGS	604.5		004	12.0	200+		•
-15.0				;				
-17.5		;						
-20.0								
-22.5		3						
-25.0								
-27.5								
-30.0								
32.5								
								,

(WL-28) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP28-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	YS!
t. BGS	GROUND SURFACE	ft. AMSL 616.0	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist	+		_	<u></u>			
2.5				.]		_		
5.0	CL-CLAY, some silt, trace sand, sand fissures, firm, medium plasticity, gray, moist	611.5			4.0	0		
7.5					6.0 8.0	150+ 150+		
10.0	BOTTOM OF TEST PIT @ 9.5ft BGS	606.5			8.0	150+		
	20.10.10.120.71.20.00.000							
12.5								
15.0				}				
17.5						· 		
20.0						ļ		
22.5								
25.0								
27.5								
30.0								
32.5							ļ	

(WL-29) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP29-01

DATE COMPLETED: JANUARY 16, 2001
TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH ft. BGS	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 616.1	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist, no odor or staining				2.0	0		
5.0	CL-CLAY, some silt, trace sand, firm, low plasticity, gray, moist	612.6			4.0	0		
	BOTTOM OF TEST PIT @ 5.5ft BGS	610.6	<i>/////////////////////////////////////</i>	·	5.5	0		
-7.5								
-10.0								
12.5						!		
15.0								
-17.5								
-20.0								
-22.5								
25.0								
27.5								
30.0								
32.5								

(WL-30) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT30-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV. ft. AMSL	GRAPHIC	<u> </u>	SAMPLE	<del>1</del>	ANAL	
ft. BGS	GROUND SURFACE	615.9	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist							
-5.0					3.5	0		
5.0	- very moist @ 5.3ft BGS  CL-CLAY, some silt, trace silt and sand fissures, stiff, low plasticity, gray, moist	610.4		005	5.5	14.0		•
-7.5								
-10.0		603.0		006	11.0	150+		•
-12.5	BOTTOM OF TEST PIT @ 12.0ft BGS NOTE:	603.9						
-15.0	1. Elevation of S end of TT30-01 is 615.9ft AMSL, and the N end is 616.1ft AMSL.				]			
-17.5								
-20.0								
-22.5								
-25.0								
-27.5								
-30.0								
-32.5								
						1		

(WL-31) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP31-01 DATE COMPLETED: JANUARY 16, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 613.8	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				2.5	0		
	DNAPL @ 4.0ft BGS	609.8 609.3			2.0	ŭ		
-5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 4.5ft BGS	000.5						
-7.5								
-10.0								
12.5								
15.0								
17.5								
20.0								
22.5								
25.0								
27.5			,					
30.0								
32.5								
}				1			}	

WATER FOUND ¥

(WL-32) *Page 1 of 1* 

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP32-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 612.7	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				3.5	0		
-5.0	- very moist to wet, sheen present @ 4.3ft BGS  CL-CLAY, some silt, stif, low plasticity, gray, moist	608.2 606.7			5.5	105		
-7.5	BOTTOM OF TEST PIT @ 6.0ft BGS							l
-10.0								
-12.5								
-15.0								
-17.5								
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								
	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; R							

(WL-33) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP33-01
DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	<del></del>	ANAL	_
ft. BGS	GROUND SURFACE	ft. AMSL 612.6	L06	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	I VOINLING
	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist, occasional wet sand pocket							
2.5					2.5 4.0	0		
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	608.1			6.0	0		
7.5	BOTTOM OF TEST PIT @ 6.5ft BGS	608.1						
10.0								
-12.5								
15.0								
17.5								1
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								

(WL-34) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP34-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 612.9	LUG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				3.5	0		
-5.0	CL-CLAY, some silt, trace sand, stiff, low plasticity, gray, moist	608.4			6.0	180+		
-7.5	BOTTOM OF TEST PIT @ 6.0ft BGS							
-10.0								
-12.5								
-15.0					;			
-17.5								
-20.0								
-22.5								
-25.0								
-27.5								
-30.0								
-32.5								
N.C.	<u>OTES:</u> MEASURING POINT ELEVATIONS MAY CHANGE; F	REFER TO	CURRENT ELEVA	TION T	ARLE			

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND ▼

(WL-35) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP35-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC	ļ	SAMPLE		ANAL	7—
ft. BGS	GROUND SURFACE	ft. AMSL	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist				<del></del>			
-2.5		2004			2.5	0		
-5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	609.1		008	4.5 5.0	250+ 50		•
-7.5	BOTTOM OF TEST PIT @ 6.0ft BGS	607.1						
-10.0								
-12.5								
-15.0								
-17.5								
-20.0				I				
22.5								
25.0								
27.5								
30.0								
32.5						,		
		1			}	}		

(WL-36) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP36-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	YSIS
ft. BGS		ft. AMSL	LOG	NUMBER	SAMPLE	PID	GRAIN SIZE	CHEMICAL
	GROUND SURFACE	0.0		DN.	INTERVAL	(ppm)	R S	뿡
	MH-SILT, trace to with sand, compact, fine grained, poorly graded, brown, wet, dilatant							
-2.5	CL-SILTY CLAY, firm to stiff, low plasticity,	-3.0			2.5	0		
-5.0	gray, moist - clay, some silt @ 5.0ft BGS				4.5	14.5		
					5.5	50+		
-7.5	BOTTOM OF TEST PIT @ 8.0ft BGS	-8.0				i		
-10.0	NOTE: 1. Sand and Silt lenses/fissures throughout clay strata.							
-12.5								
-15.0								
-17.5								
-20.0								
-22.5						:		
-25.0								
-27.5								
30.0								
32.5								

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND \$\rm\$

(WL-37) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP37-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEDT		ELCV	CDADUTO		SAMPLE		ANAL	YSIS
DEPTH ft. BGS	SAMPLE DESCRIPTION	ELEV. ft. AMSL	GRAPHIC LOG	æ		<u> </u>		
	GROUND SURFACE	613.7		NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  - very moist to wet @ 3.8ft BGS DNAPL, dark brown @ 4.0ft BGS	609.7			3.0	0		
-5.0 -7.5	CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 5.0ft BGS	608.7						
-10.0								
<b>–</b> 12.5								
—15.O								
—17.5								
20.0								
-22.5	·							
-25.0								
-27.5								
-30.0								
<b>–32.5</b>								
Ŋ	NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REWATER FOUND ♀	FER TO	CURRENT ELEVAT	TION T	ABLE			

(WL-38) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP38-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE	,	ANAL	
t. BGS	GROUND SURFACE	ft. AMSL 612.7	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	
2.5	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist  - very moist to wet @ 4.8ft BGS	607.7			4.0	o		
7.5	ONAPL @ 5.0ft BGS  CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 5.5ft BGS	607.7 607.2						
0.0								
2.5								
5.0								
7.5								
0.0					ļ			
2.5								
5.0								
7.5				ļ				
0.0								
2.5								

(WL~39) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP39-01

DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 614.8	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace sand, loose, fine grained, poorly graded, brown, moist to very moist – compact, moist @ 1.5ft BGS				3.5	0		
-5.0	CL-CLAY, some silt, trace sand, stiff, low plasticity, gray, moist	609.8			6.0	0		
-7.5	BOTTOM OF TEST PIT @ 7.0ft BGS	607.8	,					
-10.0								
-12.5				:				
-15.0								
-17.5								
-20.0								
-22.5							į	
-25.0								
-27.5								
-30.0								ļ
-32.5								i
NO.	IES: MEASURING POINT ELEVATIONS MAY CHANGE; F	REFER TO (	CURRENT ELEVAT	TION T	ABLE			

(WL-40) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP40-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

SAMPLE DESCRIPTION   CLEEK   STAPPLE   CLOG   CLO	E ANALYS
MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist  -2.5  - with sand @ 4.5ft BGS  CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 7.0ft BGS  -10.0  -12.5  -15.0	(mdd) GRAIN SIZE
2.5   poorly graded, brown, moist	(60)
- with sand @ 4.5ft BGS  CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 7.0ft BGS  10.0  12.5  15.0	
- with sand @ 4.5ft BGS  CL-CLAY, some silt, stiff, low plasticity, gray, moist  7.5  BOTTOM OF TEST PIT @ 7.0ft BGS  10.0  112.5  117.5	
CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 7.0ft BGS  5.5  7.0  12.5  15.0	0
7.5 BOTTOM OF TEST PIT @ 7.0ft BGS  10.0  12.5  15.0  17.5	
10.0 BOTTOM OF TEST PIT & 7.0ft BGS	
-12.5 -15.0 -17.5	0
15.0	
15.0	
17.5	
20.0	
22.5	
25.0	
27.5	
30.0	
32.5	

(WL-41) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT41-01

DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 614.5	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist				25			
-5.0	~ very moist to wet, sand pockets @ 5.5ft BGS	608.5			3.5 5.5	0		
-7.5	DNAPL @ 6.0ft BGS  CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 7.0ft BGS	607.5						
-10.0	NOTE: 1. Elevation of S end of TT41~01 is 614.9ft AMSL, and the N end is 614.5ft AMSL.			ļ		ĺ		
-12.5								
-15.0			2					
-17.5								
-22.5		į						
-25.0								
-27.5								
-30.0								
-32.5								
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO C	CURRENT FLEVA	TON T	ARIF			

(WL-42) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND ₹

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT42-01

DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

EPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG	<b></b>	SAMPLE		ANAL	T
I. BGS	GROUND SURFACE	615.3	LUG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CURVICAL
	MH-SILT, with sand, compact, fine grained, poorly graded, brown, moist							
2.5	~ wet				3.5	0		
5.0	CL-CLAY, some silt, firm, low plasticity, gray, moist, clay stratified with fine sand lenses	610.8			5.5	4-150		
.5	DNAPL pockets @ 7.0ft BGS BOTTOM OF TEST PIT @ 7.5ft BGS	607.8		009 010	7.5 7.5	15.0 15.0		
0.0	NOTE: 1. Elevation of SE end of TT42-01 is 616.0ft AMSL, and the NW end is 615.3ft AMSL.							
2.5								
5.0								
7.5								
0.0								
2.5								
5.0							:	
7.5						ļ		
0.0	•							
2.5								
ĺ						1		

(WL-43) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT43-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
ft. BGS	GROUND SURFACE	ft. AMSL 616.1	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
-2.5	MH-SILT, trace sand, occasional sand pockets, compact, fine grained, poorly graded, brown, moist							3
2.0	DNAPL, patchy @ 4.0ft BGS	612.1			3.0	0		
-5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist  BOTTOM OF TEST PIT @ 5.0ft BGS	611.1						
<b>-</b> 7.5	NOTE: 1. Elevation of SE end of TT43-01 is 616.5ft AMSL, and the NW end is 616.1ft AMSL.							
-10.0								
-12.5						,		
—15.O								
-17.5								
-20.0								
-22.5								
-25.0								
-27.5								
-30.0								
-32.5								
Ŋ	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO (	CURRENT ELEVAT	TION T	ABLE			

(WL-44) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP44-01 DATE COMPLETED: JANUARY 17, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

EPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	_
t. BGS	GROUND SURFACE	ft. AMSL 616.1	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	
2.5	MH-SILT, trace to with sand, compact, fine grained, poorly graded, brown, moist							
.0	- very moist to wet @ 4.5ft BGS  DNAPL @ 5.0ft BGS  CL-CLAY, some silt, stiff, low plasticity, gray,	611.1			3.5	0		
.5	BOTTOM OF TEST PIT @ 6.0ft BGS							
0.0						ı		
2.5								
5.0								
7.5								
0.0								
2.5								
5.0								
7.5								
0.0								
2.5								
		}	l		1	1	- 1	

(WL-45) *Page 1 of 1* 

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT45-01 DATE COMPLETED: JANUARY 18, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

EPTH	SAMPLE DESCRIPTION	ELEV. ft. AMSL	GRAPHIC LOG	 	SAMPLE	T	ANAL	
t. BGS	GROUND SURFACE	617.7	LUG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
2.5	MH-SILT, trace sand, compact, fine grained, poorly graded brown, moist	613.7			3.0	0		
5.0	CL-CLAY, some silt, trace vertical sand lenses, stiff, low plasticity, gray, moist			011	6.0	0		•
7.5					8.0	100+		
0.0	BOTTOM OF TEST PIT @ 10.0ft BGS	607.7		012	10.0	200+		•
2.5	NOTES:  1. Photograph taken of vertical sand lenses.  2. Elevation of S end of TT45-01 is 617.7ft  AMSL, and the N end is 619.1ft AMSL.							
5.0						:		
7.5								
0.0						:		
2.5								
5.0								
27.5								
0.0								
2.5						ļ		
				1				

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND ▼

(WL-46) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT46-01 DATE COMPLETED: JANUARY 18, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

CRA SUPERVISOR: D. DEITNER

EPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
. BGS	GROUND SURFACE	ft. AMSL 617.6	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	01770170
2.5	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist				2.5	0		
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	613.6			4.5	0		
.5		609.6			6.5 8.0	0		
0.0	BOTTOM OF TEST PIT @ 8.0ft BGS  NOTE:  1. Elevation of S end of TT46-01 is 617.9ft AMSL, and the N end is 617.6ft AMSL.							
2.5								
5.0					1		;	
7.5								
0.0						{		
2.5								
5.0								
7.5								
0.0								
2.5								

WATER FOUND \$\Bar{\Bar{\Bar}}\$

(WL-47) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$\Bar{\Pi}\$

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP47-01 DATE COMPLETED: JANUARY 18, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
t. BGS	GROUND SURFACE	ft. AMSL 617.5	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
2.5	MH-SILT, trace to with sand, compact, fine grained, poorly graded, brown, moist				3.0	0		
5.0	CL-CLAY, some silt, stiff, low plasticity, gray, moist	613.5			6.0	0		
7.5	BOTTOM OF TEST PIT @ 8.0ft BGS	609.5			8.0	0		
0.01								
2.5					ļ			
5.0								
7.5								
20.0								· 
22.5								
25.0								
27.5								
0.0								
2.5								
	TES: MEASURING POINT ELEVATIONS MAY CHANGE							

(WL-48) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TP48-01 DATE COMPLETED: JANUARY 18, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

DEPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC LOG		SAMPLE	<del></del>	ANAL	
ft. BGS	GROUND SURFACE	618.0	206	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN	CHEMICAL
	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist					_		
-2.5					2.0	0		
5.0	CL-CLAY, some silt, trace sand, fissures, stiff, low plasticity, gray, moist	614.0			4.5	7.0		
7.5	- slight sheen @ 6.0ft BGS			ĺ	6.5 7.5	50+ 80+		
	BOTTOM OF TEST PIT @ 8.0ft BGS	610.0		ļ				
10.0								
12.5			j					
15.0								
17.5								
20.0								
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								
					1			

(WL-49) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676-10

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

LOCATION: ASHTABULA, OHIO

TEST PIT DESIGNATION: TT49-01
DATE COMPLETED: JANUARY 18, 2001

TEST PIT METHOD: TRACK MOUNTED EXCAVATOR

EPTH	SAMPLE DESCRIPTION	ELEV.	GRAPHIC		SAMPLE		ANAL	
t. BGS	GROUND SURFACE	ft. AMSL 616.9	LOG	NUMBER	SAMPLE INTERVAL	PID (ppm)	GRAIN SIZE	CHEMICAL
	MH-SILT, trace sand, compact, fine grained, poorly graded, brown, moist							
2.5					3.0	0		
5.0	CL-CLAY, some silt, stratified with sand and silt lenses, firm, low plasticity, gray, moist, syrup like DNAPL in clay/sand lenses	612.9			<b>4.5</b> 5.5	6.0 2.8		
	BOTTOM OF TEST PIT @ 6.0ft BGS	610.9						
0.0	NOTES: 1. Photograph taken of trench. 2. Clay/Sand lenses contain frozen DNAPL. 3. Elevation of S end of TT49-01 is 616.9ft AMSL, and the N end is 617.7ft AMSL.							
.5								
.0								
.5								
0.0								
2.5								
5.0								
7.5								
0.0						į		
2.5								
						1		

# SECTION 5 GEOPROBE STRATIGRAPHIC LOGS

FIELDS BROOK SUPERFUND SITE ASHTABULA, OHIO

(WL-66) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP1-01

DATE COMPLETED: JANUARY 30, 2001

DRILLING METHOD: 2" Ø GEOPORBE

				_		AMPLE	_
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ft. AMSL	MONITOR INSTALLATION	ας			
	GROUND SURFACE	615.2		NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5	ML-SILT (TOPSOIL), with clay, trace to little fine sand, low plasticity, dark gray, moist, rootlets  ML-SILT, with clay, trace to little fine sand, trace gravel, medium to low plasticity, light gray, moist, mottled, fractured horzontally and	614.7		íGP			1448 (0- 51t)
-5.0	vertically, fractured surfaces oxidized, rootlets  - very moist to wet, slightly dilatant, slight chemical odor	611.2	2" Ø		$\langle - \rangle$		
-7.5	ML-CLAYEY SILT (LACUSTRINE), trace to little fine sand, trace gravel, hard, gray, moist, varving visable (bedding planes), slight to faint chemical odor  - very faint chemical odor		BOREHOLE	2GP	X		45.6 5- 10ft)
-10.0	- more competent						
-12.5			GROUT GROUT	3GP	X		29.1 (10– 15ft)
-15.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	600.2					
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ♀ STATIC WATER LEVEL ▼	FER TO C	CURRENT ELEVATION TABLE				

(WL-65) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP2-01

DATE COMPLETED: JANUARY 30, 2001

DRILLING METHOD: 2" Ø GEOPORBE

		· ·	<del>, , , , , , , , , , , , , , , , , , , </del>				
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<u> </u>	S	AMPLE	
11. 665	GROUND SURFACE	615.5	INSTALLATION	NUMBER	STATE	'N' VALUE	(ppm)
-2.5	ML-SILT (TOPSOIL), with trace clay, with fine sand, low plasticity, dark gray, moist, rootlets  ML-SILT, with clay, with to trace fine sand, trace gravel, medium plasticity, light gray, moist, mottled, oxidized, rootlets, fractured horzontally and vertically, fractured surfaces oxidized	615.0	₹ 2" Ø	1GP			6688 (0- 5ft)
5.0	<ul> <li>with fine sand, wet, dilatant, slight chemical odor @ 1.5ft BGS</li> <li>fractured horizontally and vertically,</li> </ul>		BOREHOLE	2AGP)			9366
-7.5	fractures oxidized with some evidence of impact @ 2.0ft BGS  - horizontal fracture, strong chemical odor @ 4.8ft BGS	608.0	BENTONITE GROUT	2GP 2BGP	X		(5- 7ft) 710
-10.0	- strong to slight chemical odor @ 5.0ft BGS  ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist, varved appearance	605.5			/ \		(7– 10ft)
-12.5	BOTTOM OF BOREHOLE @ 10.0ft. BGS						
<b>~</b> 15.0							
-17.5							
-20.0		. }					
-22.5	·						
-25.0							
-27.5							
-30.0		,					
-32.5							
Ŋ	IOTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ♀ STATIC WATER LEVEL ♀ CHEMICAL ANALYSIS ○	FER TO	CURRENT ELEVATION TABLE		<u> </u>		

(WL-64) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP3-01

DATE COMPLETED: JANUARY 30, 2001

DRILLING METHOD: 2" Ø GEOPORBE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION		S	AMPLE	
11. 803	GROUND SURFACE	615.6	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
-2.5	ML-SILT (TOPSOIL), trace fine sand, low plasticity, black, moist, rootlets  ML-SILT, with clay, trace to little fine sand, trace gravel, gray, very moist, slightly dilatant, fractured horizontally and vertically, oxidized, mottled, slight odor  - moist, fractured, slight odor, oxidized,	615.4	2" Ø	IGP			130 (0- 51t)
-5.0 -7.5	mottled, fractured horizontally and vertically @ 4.0ft BGS SM-SAND seam, with silt, brown, wet, dilatant @ 3.5ft BGS - fractured, mottled, slight chemical odor @	608.6	BOREHOLE  BENTONITE	2GP			8400 (5-
-10.0	5.0ft BGS  CL-SILTY CLAY (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist, varved appearance, strong chemical odor slight chemical odor 9.0ft BGS	605.6	GROUT	2AGP 2BGP	$\triangle$		10ft) 5650 7- 10ft) 367 (10ft)
—12.5	BOTTOM OF BOREHOLE @ 10.0ft. BGS						
<b>–15.0</b>							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ♀ STATIC WATER LEVEL ▼ CHEMICAL ANALYSIS ◯	FER TO (	CURRENT ELEVATION TABLE		I		

(WL-58) *Page 1 of 1* 

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP4-01

DATE COMPLETED: JANUARY 31, 2001

DRILLING METHOD: 2" Ø GEOPORBE

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR		S	AMPLE	
ft. BGS	GROUND SURFACE	ft. AMSL 615.1	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
<u> </u>				ž	Ś	ż	(PPIII)
2.5 5.0	ML-SILT (TOPSOIL), with fine sand, trace clay, low plasticity, brown, moist, rootlets  ML-SILT, with fine sand, with to trace clay, trace gravel, medium plasticity, brown, moist, rootlets, fractured  - very moist, slightly dialtant, oxidized @ 2.0ft BGS  - moist, light gray, fractured horizontally and	614.6	2" Ø BOREHOLE	1GP			43 (0- 5ft)
<b>-</b> 7.5	vertically, surfaces oxidized, slight chemical odor @ 4.0ft BGS  — fractures more visable, oxidized, mottled, strong chemical odor @ 5.0ft BGS	608.6	BENTONITE	2GP 2BGP	$\bigvee$		2300 (5- 61t) 1336
-10.0	ML-CLAYEY SILT (LACUSTRINE), with fine sand, trace gravel, hard, low plasticity, gray, moist, mottled, strong odor, varved appearance - slight chemical odor @ 7.5ft BGS  BOTTOM OF BOREHOLE @ 10.0ft. BGS	605.1	GROUT	2CGP			(6.5- 10ft) 46 (10ft)
<b>–12.5</b>							
-15.0							
<b></b> 17.5							
-20.0							
-22.5							
25.0							
-27.5							
-30.0							
-32.5							
Ŋ	NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ♀ STATIC WATER LEVEL ▼ CHEMICAL ANALYSIS ○	FER TO C	CURRENT ELEVATION TABLE				

(WL-59) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP5-01

DATE COMPLETED: JANUARY 31, 2001

DRILLING METHOD: 2" Ø GEOPORBE

	,	<del>,</del> -	<u></u>	_			
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	-		AMPLE	
	GROUND SURFACE	615.5		NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5	ML-SILT (TOPSOIL), with fine sand, with to trace clay  ML-SILT, with clay, trace fine sand, trace gravel, low to medium plasticity, gray, moist,	615.0		1GP	$\bigvee$		417
	rootlets – very moist, brown, fractured, oxidized @ 1.5ft BGS		2" Ø BOREHOLE		$/\!\!/$		(0- 51t)
-5.0	- mottled, fractured horizontally and vertically, oxidized @ 3.5 to 5.0ft BGS  ML-CLAYEY SILT (LACUSTRINE), with to trace	810.5		2AGP			931 (5- 71t)
-7.5	fine sand, trace gravel, hard, low plasticity, gray, moist, varved appearance, slight odor		BENTONITE GROUT	2GP	$\left  \right\rangle$		710
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	605.5		2BGP			5.5 (9.5– 10ft)
12.5							
-15.0							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND \$\Pi\$ STATIC WATER LEVEL \$\Pi\$ CHEMICAL ANALYSIS \$\igchtarrow\$	FER TO C	CURRENT ELEVATION TABLE				

(WL-61) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP6-01

DATE COMPLETED: JANUARY 31, 2001

DRILLING METHOD: 2" Ø GEOPORBE

<u> </u>		T	<del></del>				
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	_	Ι	AMPLE	
11. 500	GROUND SURFACE	615.4	INOTALEATION	NUMBER	STATE	N' VALUE	PID (mqq)
	ML-SILT (TOPSOIL), with to trace fine sand, with clay, low plasticity, black, moist, rootlets	614.4				•	
-2.5	ML-SILT, with clay, with fine sand, trace gravel, low plasticity, brown, moist, rootlets, fractured horizontally and vertically, oxidized, mottled		2" Ø	1GP	$\bigwedge$		21 (0- 51t)
-5.0	<ul> <li>very moist @ 2.0ft BGS</li> <li>very moist to wet, and fine sand, strong odor, fractured horizontally and vertically, oxidized @ 5.0 to 8.0ft BGS</li> </ul>	609.4	BOREHOLE	2AGP			980 (5– 6ft)
-7.5	ML-CLAYEY SILT (LACUSTRINE), with fine sand, trace gravel, hard, low plasticity, gray, moist, varved appearance, definite chemical odor		BENTONITE GROUT	2BGP 2GP 2CGP	X		808 (6- 81t) 800 (5-
-10.0	- faint odor @ 8.0 to 10.0ft BGS BOTTOM OF BOREHOLE @ 10.0ft. BGS	605.4					10ft) 38 (8- 10ft)
-12.5							1010
-15.0							
-17.5							
-20.0							
-22.5			į				
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RI WATER FOUND ♀ STATIC WATER LEVEL ♀ CHEMICAL ANALYSIS ◯	EFER TO C	CURRENT ELEVATION TABLE				

(WL-60) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP7-01

DATE COMPLETED: JANUARY 31, 2001

DRILLING METHOD: 2" Ø GEOPORBE

GROUND SURFACE  T (TOPSOIL), with fine sand, trace clay, sticity, black, moist, rootlets  T, with clay, trace to with fine sand, gravel, low to medium plasticity, brown, nottled, fractured horizontally and ally, oxidized ing more evident @ 3.0ft BGS  AYEY SILT (LACUSTRINE), with fine trace gravel, hard, low plasticity, gray, warved appearance stiff, fractured @ 5.0ft BGS  ag chemical odor, red hematite staining @ 10.0ft BGS	ft. AMSL 615.4 614.4	INSTALLATION	IGP IAGP	STATE	N VALUE
sticity, black, moist, rootlets  T, with clay, trace to with fine sand, gravel, low to medium plasticity, brown, nottled, fractured horizontally and ally, oxidized ing more evident @ 3.0ft BGS  AYEY SILT (LACUSTRINE), with fine trace gravel, hard, low plasticity, gray, warved appearance stiff, fractured @ 5.0ft BGS  ag chemical odor, red hematite staining @			1AGP		
gravel, low to medium plasticity, brown, nottled, fractured horizontally and ally, oxidized ing more evident @ 3.0ft BGS  AYEY SILT (LACUSTRINE), with fine race gravel, hard, low plasticity, gray, varved appearance stiff, fractured @ 5.0ft BGS  ag chemical odor, red hematite staining @	611.4		1AGP		
AYEY SILT (LACUSTRINE), with fine race gravel, hard, low plasticity, gray, varved appearance stiff, fractured @ 5.0ft BGS ag chemical odor, red hematite staining @			IBGP /	V	
g chemical odor, red hematite staining @			}     }'		5
		2" Ø BOREHOLE	2GP	X	3 ( 10
low plasticity, no odor detected @ 10.0 it BGS					10
		BENTONITE GROUT	3GP	X	4 (1 15
4 OF BOREHOLE @ 15.0ft. BGS	600.4		<u> </u>		
	4 OF BOREHOLE @ 15.0ft. BGS	# OF BOREHOLE @ 15.0ft. BGS	600.4 GROUT	BENTONITE GROUT	BENTONITE GROUT

(WL-62) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP8-01

DATE COMPLETED: JANUARY 31, 2001
DRILLING METHOD: 2" Ø GEOPORBE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION		Γ	AMPLE	: 
003	GROUND SURFACE	615.4	INOTALLATION	NUMBER	STATE	'N' VALUE	PID (ppn
	ML-SILT (TOPSOIL), with fine sand, trace clay, low plasticity, black, moist, rootlets	614.4			7		
.5	ML-SILT, with clay, trace to with fine sand, trace gravel, low to medium plasticity, brown, moist, mottled, fractured horizontally and vertically, oxidized  - mottling more evident @ 3.0ft BGS		2" Ø	1GP	X		
.0	ML-CLAYEY SILT, trace fine sand, trace	610.4	BOREHOLE		$\langle - \rangle$		
.5	gravel, low to medium plasticity, gray, competent, higher moisture content then at GP7-01		BENTONITE GROUT	2GP			
0.0	<ul> <li>low plasticity, varving more visible, decrease in moisture content @ 10.0 to 15.0ft BGS</li> </ul>			2AGP	<u> </u>		1.3 (8- 10ft
2.5				3GP 3AGP 3BGP	X		0.5 (10- 12.5f
.0	- increase in moisture content, varying not as evident @ 14.5 to 15.0ft BGS  BOTTOM OF BOREHOLE @ 15.0ft. BGS	600.4			_		0.1 (12.5 15ft
7.5							
0.0							
2.5							
5.0							
7.5							
0.0							

(WL-63) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP9-01

DATE COMPLETED: JANUARY 31, 2001

DRILLING METHOD: 2" Ø GEOPORBE

ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	III ΔM™II					
ł	GROUND SURFACE	ft. AMSL 616.3	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
	ML-SILT (TOPSOIL), with fine sand, trace to with clay, low plasticity, black, moist, rootlets	615.3		Z	\	Ž	
-2.5	ML-SILT, with to and clay, with fine sand, trace gravel, low plasticity, brown, moist, rootlets, fractured horizontally and vertically, oxidized	612.3	2" Ø	IGP			252
5.0	<ul> <li>mottled @ 3.0 to 4.0ft BGS</li> <li>ML-CLAYEY SILT (LACUSTRINE), with to trace fine sand, trace gravel, low plasticity, gray, moist, varved appearance, slight chemical odor</li> </ul>	012.5	BOREHOLE	(IAGP)			353 (3- 5ft)
7.5	- varving visable @ 5.0 to 6.0ft BGS - varving less evident @ 6.0 to 7.0ft BGS - varving evident @ 6.0 to 10.0ft BGS		BENTONITE GROUT	2GP 2AGP 2BGP	$\left  \right\rangle$		229 (5- 7.5ft) 1.7
10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	606.3					(7.5- 10ft)
12.5							
15.0		}	ĺ				
17.5							
20.0							
22.5							
25.0						}	
27.5							
30.0							
32.5							
NC.	DTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO CL	IRRENT ELEVATION TABLE				

(WL-57) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP10-01

DATE COMPLETED: FEBRUARY 1, 2001

DRILLING METHOD: 2" Ø GEOPORBE

<u> </u>	<u>,</u>			ī			
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<u></u>		MPLE m	
	GROUND SURFACE	623.0		NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5 -5.0	ML-SILT (TOPSOIL), with clay, little fine sand, low plasticity, black, moist, rootlets  SM-SILTY SAND, trace gravel, fine grained, poorly graded, dark brown/black, moist  ML-SILT, with to little clay, trace fine sand, low plasticity, dark brown, moist  SM-SILTY SAND, trace fine gravel, fine grained, poorly graded, wet, dilatant, layering visable  - PT-PEAT seam 1/2" thick-not fibrous, no odor @ 4.5ft BGS	622.8 622.5 622.0		1GP			0.0
7.5 10.0	- very wet, silty to and silt, fine grained, very dilatant @ 5.0ft BGS	613.0	2" Ø BOREHOLE	2GP	$\bigwedge$		0.0
—10.0 —12.5	ML-SILT, with clay, trace fine sand, low plasticity, brown, moist, mottled, fractured horizontally and vertically, oxidized, gradual contact  ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist,	611.5		3GP 3AGP 3BGP	M	ļ	144 755 (II.5-
-15.0	varving beds slightly visable - lower plasticity @ 15.0 to 20.0ft BGS		BENTONITE (	4AGP	$\langle \cdot \rangle$		13ft) 1531
-17.5				4GP 4BGP	X		(15- 17ft) 770 (17- 19ft)
-20.0	BOTTOM OF BOREHOLE @ 20.0ft. BGS	603.0		4CGP/			2.7 (19– 20ft)
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
<u> </u>	IOTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ♀ STATIC WATER LEVEL ▼	FER TO C	CURRENT ELEVATION TABLE				
	CHEMICAL ANALYSIS						

(WL-56) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP11-01

DATE COMPLETED: FEBRUARY 1, 2001

DRILLING METHOD: 2" Ø GEOPORBE

		T	<del>_</del>	<del></del>	
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<del>                                     </del>	MPLE
	GROUND SURFACE	616.9		NUMBER	N' VALUE (mdd) OId
-2.5	ML-SILT (TOPSOIL), with to little clay, trace to little fine sand, low plasticity, black, moist, rootlets  ML-SILT, with to little clay, little fine sand, trace gravel, moderate plasticity, brown, moist, rootlets, slightly dilatant	616.4		1GP	
-5.0	SM-SAND seam with silt, fine grained, poorly graded, light gray, oxidized, moist	612.7 612.4	₹ 2" Ø BOREHOLE	IAGP	35.4 (4- 51t)
<b>-</b> 7.5	ML-SILT, with clay, trace fine sand, trace gravel, low plasticity, brown, moist, mottled, fractured horizontally and vertically, oxidized  - very moist, medium to low plasticity, brown @ 5.0ft BGS	609.4	BENTONITE	2AGP 2GP	3500 (6.5– 7.5ft)
-10.0	- vertical fracture, evidence of impact, strong odor @ 7.0 to 7.5ft BGS  ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist		GROUT	2BGP 3GP	150.1 (7- 101t)
—12.5	- vertical fracture, evidence of impact, strong odor @ 7.5 to 7.8ft BGS - slight increase in clay content, more	604.9		3AGP	25 (11.5– 12ft)
<b>—</b> 15.0	competent @ 10.0ft BGS  BOTTOM OF BOREHOLE @ 12.0ft. BGS				
-17.5					
-20.0					
-22.5					
-25.0					
-27.5					
-30.0					
-32.5					
Ŋ	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND \$\Pi\$ STATIC WATER LEVEL \$\P\$ CHEMICAL ANALYSIS \$\infty\$	FER TO C	URRENT ELEVATION TABLE		

(WL-72) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP12-01

DATE COMPLETED: FEBRUARY 3, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH t. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS   ELI	ELEV.	MONITOR INSTALLATION	SAMPLE				
1. 803	GROUND SURFACE	616.7	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppn	
	SP/GP-COARSE SAND and GRAVEL (FILL), brown, dry				/	-		
2.5	ML-SANDY SILT (FILL), trace clay and gravel, brown, moist	613.7	2" Ø BOREHOLE	IGP	X			
5.0	ML-SILT, sandy silt, trace clay and gravel, dark gray, presence of black organic lenses (topsoil)	611.7	BONETIGEE	IAGP			25 (3.5 4.5f	
_	ML-SILTY SAND, trace gravel, low plasticity, brown, moist  ML-CLAYEY and SANDY SILT (LACUSTRINE),	610.2	BENTONITE	2AGP	$\setminus /$		2700 (5.5 7ft)	
7.5	trace gravel, gray, moist, varving visible		GROUT	2GP 2BGP	$\bigwedge$		18	
0.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	606.7		2CGP			(7- 8ft) 1 (9-	
2.5							10ft	
5.0								
7.5							ı	
0.0								
2.5								
5.0								
3.0								
7.5								
0.0								
2.5								

(WL-74) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP13-01

DATE COMPLETED: FEBRUARY 3, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<b></b>	S	AMPLE	
1. 865	GROUND SURFACE	615.7	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm
	ML-SANDY SILT (FILL), some clay and gravel, few rootlets, low plasticity, light brown, moist			-			
2.5		612.2		IGP IAGP	X		9 (2- 3ft)
5.0	TOPSOIL, sandy silt, dark black, wet  ML-SAND and CLAYEY SILT, trace gravel, gray, moist, light chemical odor	611.2	2" Ø BOREHOLE		$\langle - \rangle$		
7.5	- becoming with visible varving, dry @ 6.5ft BGS		BENTONITE	2AGP 2GP			136 (5- 6.5fi
0.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	605.7	GROUT	2BGP	$\triangle$		6 (8– 9ft)
2.5							
5.0							
7.5							
0.0							
2.5							
5.0							
7.5							
0.0							
2.5							
NOI	ES: MEASURING POINT ELEVATIONS MAY CHANGE; WATER FOUND \$\Pi\$ STATIC WATER LEVEL \$\Pi\$		IRRENT ELEVATION TABLE				

(WL-54) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP15-01

DATE COMPLETED: FEBRUARY 1, 2001

DRILLING METHOD: 2" Ø GEOPORBE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR	<del></del>	AMPLE	
11. 865	GROUND SURFACE	617.4	INSTALLATION	NUMBER	'N' VALUE	PID (ppm)
0.5	ML-SILT (TOPSOIL), with to little clay, trace fine sand, low plasticity, dark brown, moist, rootlets	616.4				
-2.5 -5.0	ML-SILT, with clay, trace fine sand, trace gravel, low plasticity, brown, moist, fractured horizonally and vertically, oxidized, mottled - very moist to wet, dilatant @ 2.5 to 3.5ft BGS		<b></b> 2" Ø	1GP		240 (3-
-3.0 -7.5	- slight to strong chemical odor @ 5.0 to 7.5ft BGS	609.9	BOREHOLE	2AGP 2GP		5(t) 2500 (5- 9(t)
-10.0	ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist, varving bedding planes visable, slight chemical odor	000.0	BENTONITE GROUT	28GP		148 (9-
-12.5		604.9		збР		10ft) 61
15.0	BOTTOM OF BOREHOLE @ 12.5ft. BGS					
17.5						
20.0						
22.5						
25.0						
27.5						
30.0						
32.5						
52.5						
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; F WATER FOUND \$\foatstart \text{STATIC WATER LEVEL \$\pi\$} CHEMICAL ANALYSIS \$\infty\$	REFER TO C	URRENT ELEVATION TABLE	<u>.                                      </u>		

(WL-55) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP16-01

DATE COMPLETED: FEBRUARY 1, 2001 DRILLING METHOD: 2" Ø GEOPORBE

ļ							
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION		S	AMPLE	
14. 503	GROUND SURFACE	616.1	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
	ML-SILT (TOPSOIL), with to little clay, little fine sand, low plasticity, dark brown, moist, rootlets	615.8 615.7				, <u>z</u>	
-2.5	SP-SAND, with silt, trace gravel, fine grained, poorly graded, brown, moist			IGP	X		
-5.0	ML-SILT, with to and clay, trace fine sand, trace gravel, low plasticity, brown, moist, rootlets, fractured		2" Ø BOREHOLE	IAGP			813 (3~ 5ft)
-7.5	- very moist, slightly dilatant, faint odor @ 2.0ft BGS - moist, fractured horizontally and vertically,	609.6	BUILINGE	2AGP 2GP	$\bigvee  $		4000 (5- 71t)
	slight chemical odor @ 3.0ft BGS  - SM-SAND (LOAM), little silt, fine grained, poorly graded, brown, moist, strong chemical		BENTONITE	2BGP	$\bigwedge$		4041
-10.0	odor @ 5.3 to 5.5ft BGS  ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist, varved, strong chemical odor,	00.11		3GP 3AGP	$\forall$		494.1 (9~ 10ft) 161
—12.5	- slight odor @ 7.5ft BGS - extremely hard, slight increase in clay content, more competent, varying less visable	604.1	<i>Quantum</i>	ĺ			(II~ I2ft)
<b>—</b> 15.0	BOTTOM OF BOREHOLE @ 12.0ft. BGS						
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
							}
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO C	CURRENT ELEVATION TABLE				—
	WATER FOUND \$\forall STATIC WATER LEVEL \$\forall\$						1

(WL-96) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP17-01

DATE COMPLETED: FEBRUARY 2, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAGUETTE

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	RAPHIC DESCRIPTION & REMARKS ELEV.	MONITOR	SAMPLE				
ft. BGS		ft. AMSL	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm	
	GROUND SURFACE	618.8	Valuation S.	₹	ß	ż	(ppi	
ļ	ML-SANDY SILT (TOPSOIL), trace gravel, dark brown, wet	617.8			$\setminus$			
-2.5 -5.0	ML-CLAYEY and SANDY SILT, trace gravel, low plasticity, brown, moist, varving visible		2" Ø BOREHOLE	IGP	$\bigwedge$		1.3 (3- 5ft)	
-7.5		010.0		2AGP	$\bigvee$		1.0	
-10.0	ML-CLAYEY SILT (LACUSTRINE), trace fine grained sand and gravel, low plasticity, gray, moist to dry, varving visible BOTTOM OF BOREHOLE @ 10.0ft. BGS	610.8	BENTONITE GROUT	286P	$\triangle$		(7- 8.0ft 1.5 (8- 10ft)	
-12.5								
15.0								
17.5								
20.0								
22.5								
25.0								
27.5								
30.0								
32.5								

(WL-97) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP18-01

DATE COMPLETED: FEBRUARY 2, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR	1	C.		
		ft. AMSL	INSTALLATION	-	Γ	AMPLE	
	GROUND SURFACE	615.8		NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5 -5.0	ML-SILT (TOPSOIL), trace sand and gravel, dark brown, wet  ML-CLAYEY and SANDY SILT, trace gravel, low plasticity, varved from 3.5ft BGS	614.8	2" Ø BOREHOLE	IGP IAGP			3.0 (3-
-7.5	ML-CLAYEY SILT (LACUSTRINE), some sand, trace gravel, gray, moist, varved to 10.0ft BGS	608.8	BENTONITE GROUT	2AGP 2GP 2BGP	$\bigvee$		5ft) 224 (5- 7.0ft) 438 (7.5- 9.5ft)
-10.0 -12.5	- wet @ 10.0ft BGS  BOTTOM OF BOREHOLE @ 12.5ft. BGS	603.3		3AGP 3GP	X		54 (10- 12ft)
-15.0	DOTTON OF BOILEHOLD & IZIOTA BOO						
-17.5							
-20.0							
-22.5						!	
-25.0							
-27.5							
-30.0							
NOTE	ES: MEASURING POINT ELEVATIONS MAY CHANGE; RE						

STATIC WATER LEVEL T WATER FOUND \$

(WL-98) *Page 1 of 1* 

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

WATER FOUND ¥

CHEMICAL ANALYSIS

STATIC WATER LEVEL Y

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP19-01

DATE COMPLETED: FEBRUARY 2, 2001

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<u> </u>	S	AMPLE	: <del> </del> -
	GROUND SURFACE	616.3	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm
2.5	ML-SILT (TOPSOIL), trace sand and gravel, dark brown, moist  ML-CLAYEY and SANDY SILT, trace gravel, varving visible from 3.0ft BGS, strong odor	615.6	2" Ø BOREHOLE	1GP	$\bigvee$		3568 (3-
5.0	- becoming gray/brown from 6.0ft BGS			2AGP			51t) 6189
-7.5		607.3	BENTONITE GROUT	2GP	$\bigwedge$		(5.5~ 7.5ft)
·10.0	ML-CLAYEY SILT (LACUSTRINE), some sand, trace gravel, gray, moist, varving visible			2BGP	$\langle \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \$		891 (9– 10ft)
12.5				3AGP 3GP	X		30 (11– 13ft)
15.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	601.3		3BGP	_		0.3 (14~ 15ft)
17.5							
20.0							
22.5							
25.0							
27.5							
30.0							
32.5							

(WL-99) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP20-01

DATE COMPLETED: FEBRUARY 2, 2001

GROUND SURFACE  ML-SANDY and CLAYEY SILT (FILL), trace gravel  ML-SILT (TOPSOIL), trace sand and gravel, dark brown, moist  ML-CLAYEY and SANDY SILT, trace gravel, low plasticity, brown  ML-CLAYEY SILT (LACUSTRINE), some sand, trace gravel, gray, moist, varving visible	ft. AMSL 616.5 - 616.2 - 615.2 - 610.5		JEGP IAGP PREHOLE 2AGP	'N' VALUE	9ID (ppm (3- 51t) 20 (5- 6ft) 43 (7- 9ft)
gravel ML-SILT (TOPSOIL), trace sand and gravel, dark brown, moist ML-CLAYEY and SANDY SILT, trace gravel, low plasticity, brown ML-CLAYEY SILT (LACUSTRINE), some sand, trace gravel, gray, moist, varving visible	615.2	BOF	Ø IAGP REHOLE 2AGP		51t) 2.0 (5- 61t) 43 (7-
trace gravel, gray, moist, varving visible		BEN GRO	2 <del>G</del> R NTONITE 2BGP		2.0 (5- 6ft) 43 (7-
BOTTOM OF BOREHOLE @ 10.0ft. BGS	606.5				
				MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE	MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND   STATIC WATER LEVEL   #### TO CURRENT ELEVATION TABLE

(WL-77) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND ¥

CHEMICAL ANALYSIS

STATIC WATER LEVEL \$

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP21-01

DATE COMPLETED: FEBRUARY 3, 2001

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR	<u> </u>	S.	AMPLE	
11. 865	GROUND SURFACE	614.0	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5	ML-CLAYEY and SANDY SILT, trace gravel, trace rootlets, low plasticity, brown		2" Ø BOREHOLE	1GP			2.0
-5.0	<ul> <li>becoming very soft and saturated @ 5.0ft</li> <li>BGS</li> <li>ML-SANDY and CLAYEY SILT (LACUSTRINE),</li> </ul>	608.0	BONEHULE	2AGP			3.0 (4- 5ft) 1286 (5-
7.5	trace gravel, varving visible horizontally		BENTONITE GROUT	2GP 2BGP	$\bigwedge$		6ft) 81 (6.5– 8ft)
10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	604.0		2CGP			1 (9- 10ft)
12.5					ĺ		
15.0							
17.5							
20.0							
22.5							
25.0							
27.5					į		
30.0							
32.5							

(WL-78) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

CHEMICAL ANALYSIS

STATIC WATER LEVEL \$

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP22-01

DATE COMPLETED: FEBRUARY 3, 2001

EPTH . BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<u> </u>	S	AMPLE	: <del></del> -
. 865	GROUND SURFACE	613.5	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm
				Z	<del>"</del>	Ż	
	ML-SANDY SILT (TOPSOIL), trace rootlets  ML-CLAYEY SILT, some sand, trace gravel,	613.0			$\setminus$		
.5	slightly plastic, moist			IGP	V		
	ML-SANDY and CLAYEY SILT (LACUSTRINE),	610.5		IAGP	$  \wedge  $		4 (2- 3ft
1	trace gravel, varving visible, dry to moist		2" Ø BOREHOLE	(IBGP)	$/\setminus$		77
0					$\langle - \rangle$		(4- 5ft
{				} ,	$\setminus$ /	}	
.5			DENTONITE	2GP	X		4
			BENTONITE GROUT	2AGP	$/ \setminus$		(5.5 7ft)
0.0		603.5		2BGP			0.8 (9~
	BOTTOM OF BOREHOLE @ 10.0ft. BGS						1016
.5							
.0							
.5							
0.0						İ	
						ł	
, [							
2.5							
5.0						}	
.5							
0.0							
,.0							
2.5					1		
				-			
	TES: MEASURING POINT ELEVATIONS MAY CHANGE;						

(WL-50) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP23-01

DATE COMPLETED: FEBRUARY 1, 2001

DRILLING METHOD: 2" Ø GEOPORBE

CRA SUPERVISOR: D.GRAY

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	
11. 003	GROUND SURFACE	614.2	MOTALEATION	NUMBER	STATE	N' VALUE	PID (ppm)
	ML-SILT (TOPSOIL), with clay, trace fine sand, low plasticity, black, moist, rootlets	613.5			/	2	
-2.5	ML-SILT, with clay, little fine sand, trace gravel, low plasticity, brown, moist, fractured horizontally and vertically, oxidized, mottled		2" Ø	IGP			69.3
-5.0		608.7	BOREHOLE		$\langle - \rangle$		(3- 5ft)
-7.5	ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist, varving present		BENTONITE GROUT				15.3 (5.5-
-10.0	- increase in clay content, more massive in appearance @ 9.5 to 10.0ft BGS  BOTTOM OF BOREHOLE @ 10.0ft. BGS	604.2	BROOT	2BGP	/_\		7.5ft) 14.3 (7.5– 10ft)
-12.5							
-15.0							
-17.5		:					
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
ZI.	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND \$\square\$ STATIC WATER LEVEL \$\square\$ CHEMICAL ANALYSIS \$\square\$	FER TO (	CURRENT ELEVATION TABLE				

(WL-100) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND \$

CHEMICAL ANALYSIS

STATIC WATER LEVEL ¥

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP24-01

DATE COMPLETED: FEBRUARY 2, 2001

TIFFIR		ELEV.	MONITOR		S	AMPLE	
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ft. AMSL	INSTALLATION	Ä.			PID
	GROUND SURFACE	613.8		NUMBER	STATE	'N' VALUE	(ppm)
-2.5 -5.0	ML-SILT (TOPSOIL), trace sand and clay, dark brown, moist  ML-CLAYEY SILT, trace gravel and sand, low plasticity, brown, moist  - slight chemical odor @ 5.0ft BGS	- 612.8	2" Ø BOREHOLE	IGP IAGP			0.3 (3~ 51t)
-7.5	ML-CLAYEY SILT (LACUSTRINE), trace fine grained sand and gravel, low plasticity, gray, moist, varving visible	605.8	BENTONITE GROUT	2AGP 2GP 2BGP	$\setminus$		305 (5.5- 7ft) 59 (8-
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	603.8					10ft)
-12.5							
-15.0 -17.5			!				
-20.0							
-22.5							
-25.0							
27.5							
-30.0							
32.5						}	

(WL-101) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP25-01

DATE COMPLETED: FEBRUARY 2, 2001

EPTH .	STRATIGRAPHIC DESCRIPTION & REMARKS	ft. AMSL	MONITOR INSTALLATION	<u> </u>	- S.	AMPLE	
1. 863	GROUND SURFACE	613.3	INSTACLATION	NUMBER	STATE	N' VALUE	PID (ppm
	ML-SILT (TOPSOIL), trace sand and gravel, dark brown, dry	612.3			/		
2.5	ML-CLAYEY SILT, trace sand and gravel, low plasticity, brown,m oist		2" Ø	1GP	X		2.0
5.0		607.3	BOREHOLE	2AGP)	$\langle - \rangle$		(3~ 5ft) 127
.5	ML-CLAYEY SILT (LACUSTRINE), trace fine grained sand and gravel, low plasticity, gray, moist to dry, varving visible		BENTONITE GROUT	2GP			(5.5 6.5f 11 (7~
0.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	603.3					9ft)
2.5							
5.0						· ·	
7.5							
0.0							
2.5							
5.0						j	
7.5							
0.0							
2.5							
-							

(WL-75) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP26-01

DATE COMPLETED:

EPTH t. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<b> </b>	S	AMPLE	: <del></del>
1. 865	GROUND SURFACE	612.8	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
2.5	ML-SANDY SILT (TOPSOIL), trace gravel, dark brown, moist  ML-SANDY SILT, some clay, trace gravel, medium to low plasticity, brown, moist	611.8		1GP		•	
5.0	<ul> <li>becoming soft, wet @ 4.0ft BGS</li> <li>becoming varved from 5.0ft BGs, strong chemical odor</li> </ul>	- 606.8	2" Ø BOREHOLE	1AGP	$\langle \ \rangle$		1 (3- 5ft) 10718 (5-
7.5	ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, low plasticity		BENTONITE GROUT	2GP 2BGP			6ft) 5 (7- 8ft)
0.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	602.8		2CGP	\		1 (9- 10ft)
2.5					ļ		
5.0					!		
7.5							
0.0							
2.5							
5.0							
7.5							
0.0							
2.5							
		j		- 1	- 1	1	

(WL-76) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP27-01

DATE COMPLETED: FEBRUARY 3, 2001

DEPTH   t. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	<u> </u>
503	GROUND SURFACE	612.7	INSTALLATION	NUMBER	STATE	N' VALUE	PIC (ppr
	ML-SANDY SILT (TOPSOIL), trace clay, few rootlets, dark brown, dry	612.0			/		
.5	ML-SANDY SILT, some clay, trace gravel, low plasticity, brown, moist - becoming with visible varving from 3.0ft BGS, chemical odor	608.7	2" Ø	1GP	$\bigg  \bigg $		30 (3-
0	ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, visible varving (horizontal)		BOREHOLE	(IBGP)	$\frac{(}{}$		41t 865 (4- 51t
5			BENTONITE GROUT		$\setminus$		4 (5.5 7.5f
0.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	602.7		2BGP	<u>/\</u>		0 (9- 101t
.5							
.0							
.5							
0.0						}	
2.5							
5.0							
7.5							
0.0							
2.5							

(WL-53) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP28-01

DATE COMPLETED: FEBRUARY 1, 2001 DRILLING METHOD: 2" Ø GEOPORBE

CRA SUPERVISOR: D.GRAY

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR	ļ	S	AMPLE	· 
	GROUND SURFACE	612.1	INSTALLATION	NUMBER	STATE	N' VALUE	(ppm)
-2.5	ML-SILT (TOPSOIL), with clay, with to little fine sand, low plasticity, black, moist, rootlets  ML-SILT, with to and clay, trace fine sand, trace gravel, low plasticity, brown, moist, fractured horizonally and vertically, oxidized,	611.6	2" Ø	IGP		Z.	
-5.0	mottled, rootlets  - no rootlets @ 2.0ft BGS  - hard @ 3.0ft BGS  ML-CLAYEY SILT (LACUSTRINE), trace to little	608.1	BOREHOLE BENTONITE	IAGP IBGP	$\left\langle \cdot \right\rangle$		2.t (3- 4ft) 0.0 (4- 5ft)
-7.5	fine sand, trace gravel, low plasticity, gray, moist, varving present  - extremely hard, varving very visable from 5.0 to 7.5ft BGS	604.6	GROUT	2GP			1.B (5~ 7.5ft)
-10.0	BOTTOM OF BOREHOLE @ 7.5ft. BGS						
·12.5							
-15.0							
-17.5							
20.0							
22.5							
25.0							
27.5				!			
30.0							
32.5							

(WL-52) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP29-01 DATE COMPLETED: FEBRUARY 1, 2001

DRILLING METHOD: 2" Ø GEOPORBE

CRA SUPERVISOR: D.GRAY

STRATIGRAPHIC DESCRIPTION & REMARKS   SELEV   MONITOR INSTALLATION   SAMPLE   SAMPLE   STRATIGRAPHIC DESCRIPTION & REMARKS   SELEV   MONITOR INSTALLATION   SAMPLE								
GROUND SURFACE    Size	DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS				$\overline{}$		: T
Low plasticity, black, moist, rootlets		GROUND SURFACE	<del></del>		NUMBER	STATE	N. VALU	PID (ppm)
- and fine sand, wet, dilatant, no rootiets from 2.0 to 2.51 to 186S 2.0 to 2.51 to 186S - very hard, fracturing very visable from 2.5 to 4.87t BgS ML-CLAYEY SILT (LACUSTRINE), trace to little fine sand, trace gravel, herd, low plasticity, varving present very hard, low plasticity, varving very visable 8.50 to 185S - slight clay content increase-more competent 9.5 to 10.01 till BS BOTTOM OF BOREHOLE @ 10.0ft. BGS  -15.0 -17.5 -20.0 -22.5 -25.0 -27.5 -30.0 -32.5  MOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	-2.5	low plasticity, black, moist, rootlets  ML-SILT, with clay, with to little fine sand, trace gravel, low plasticity, brown, moist, fractured horizontally and vertically, oxidized,	612.3					
MI_CLAYEY SILT (LACUSTRINE), trace to little fine sand, trace gravel, hard low plasticity, gray, moist, varving present - very hard, low plasticity, varving very visable e. 5.01 tigS?  -10.0 -12.5 -15.0 -16.0 -17.5 -20.0 -22.5 -25.0 -27.5 -30.0 -32.5  MOITES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	-5.0	- and fine sand, wet, dilatant, no rootlets from 2.0 to 2.5ft BGS - very hard, fracturing very visable from 2.5 to	608.0	2" Ø BOREHOLE		$\langle \cdot \rangle$		(3.5- 5ft)
-10.0	<b>-</b> 7.5	ML-CLAYEY SILT (LACUSTRINE), trace to little fine sand, trace gravel, hard, low plasticity, gray, moist, varving present		V/////// PROUT	2GP	X		(5- 7.5ft) 14.6
-12.5 -15.0 -17.5 -20.0 -22.5 -25.0 -27.5 -30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	-10.0	@ 5.0ft BGS - slight clay content increase-more competent @ 9.5 to 10.0ft BGS	602.8		 	<u> </u>		
-17.5 -20.0 -22.5 -25.0 -27.5 -30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE	-12.5	BOLLOW OF BOKEHOLE & 10.011. BG2						
-20.0 -22.5 -25.0 -27.5 -30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE	-15.0							
-22.5 -25.0 -27.5 -30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	17.5							
-25.0 -27.5 -30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	-20.0							
-27.5 -30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE	22.5							
-30.0 -32.5  NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	25.0							
NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	-27.5							
NOTES: MEASURING POINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	-30.0							
	-32.5							
			FER TO C	CURRENT ELEVATION TABLE				

(WL-51) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP30-01
DATE COMPLETED: FEBRUARY 1, 2001

DRILLING METHOD: 2" Ø GEOPORBE

CRA SUPERVISOR: D.GRAY

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	: 
11. 865	GROUND SURFACE	612.5	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
<b> </b>	ML-SILT (TOPSOIL), with clay, with to little fine	ļ		Ž	, o,	جزا	ļ
	sand, low plasticity, black, moist, rootlets	611.8			$\setminus$		
-2.5	ML-SILT, with to and clay, little fine sand, trace gravel, low plasticity, brown, moist, rootlets			1GP	X		
-5.0	<ul> <li>very moist to wet, dilatant, oxidized @ 2.0ft BGS</li> </ul>		2" Ø BOREHOLE	1AGP		ļ	51.6 (3- 51t)
<b>−7.5</b>	ML-CLAYEY SILT (LACUSTRINE), trace fine sand, trace gravel, low plasticity, gray, moist, varving present	607.0	BENTONITE GROUT	2AGP 2GP			349 (5.5- 7.5ft)
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	602.5					(7.5– 10ft)
-12.5							
-15.0							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
И	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO (	CURRENT ELEVATION TABLE				

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND 

STATIC WATER LEVEL 

CHEMICAL ANALYSIS 

CHEMICAL ANALYSIS 

■

(WL-67) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND ¥

CHEMICAL ANALYSIS

STATIC WATER LEVEL T

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP31-01

DATE COMPLETED: FEBRUARY 4, 2001

DEPTH	OTRATION AND DESCRIPTION OF DELIABILE	ELEV.	MONITOR		S	AMPLE	
ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ft. AMSL	INSTALLATION	EB.	TE	I UE	PID
	GROUND SURFACE	624.2		NUMBER	STATE	'N' VALUE	(maga)
-2.5 -5.0	TOPSOIL, silt and sand, low to medium plasticity, dark brown, moist, rootlets  ML-SILT (FILL), some fine sand, trace clay, trace gravel, medium plasticity, medium brown to dark brown, some gray, moist, piece of porcelain (foreign material)  ML-SILT, some fine sand, trace clay, low plasticity, medium brown, moist, varving visible (horizontal), rootlets	624.0		1GP 1AGP			56 (4- 4.5ft)
-7.5 -10.0	CL-CLAYEY SILT, trace fine sand, trace gravel, medium to high plasticity, gray to dark gray, rootlets, moist to very moist, same as above, more clean, less fine sand	617.9	BOREHOLE	2AGP 2GP	$\bigvee$		77 (6.5- 7ft)
-12.5			BENTONITE GROUT	3GP 3AGP			3476
-15.0	<ul> <li>thin layer of sand, some clay, low plasticity, dark gray, moist @ 14.8ft BGS</li> </ul>				<u></u>		(14– 14.5ft)
-17.5	CL-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, medium plasticity, gray, moist, free product, chemical odor	607.5					
-20.0	BOTTOM OF BOREHOLE @ 20.0ft. BGS	604.2					
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE						

(WL-79) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP31A-01

DATE COMPLETED: FEBRUARY 4, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

EPTH t. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<b> </b>	S	AMPLE	T
	GROUND SURFACE	624.2	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm
	TOPSOIL, silt and sand, rootlets, low to medium plasticity, dark brown, moist	623.9				<u> </u>	
2.5	ML-SILT (FILL), some fine sand, trace clay, trace gravel, medium plasticity, brown, some gray, moist	622.0		1GP	X		
.0	ML-SILT and FINE SAND, trace clay, trace gravel, rootlets, low to medium plasticity, light brown, varving visible (horizontal)		2" Ø BOREHOLE	IAGP	$\langle - \rangle$		2.4 (4.5 51t
.5	- more clay, little gravel, medium plasticity @ 6.8ft BGS		BENTONITE	2GP	$\bigvee$		511
0.0	CL-CLAY, silt, little sand, trace gravel, rootlets, high plasticity, gray to dark gray, moist	615.4	GROUT	2AGP			24 (9- 10ft
2.5	ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low to medium plasticity, gray, moist	613.1		3GP			
5.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	609.2		3AGP/			18 (14.5 15ft
7.5							
0.0							
2.5			j				
5.0							
7.5							
0.0							
2.5							

(WL-68) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP32-01

DATE COMPLETED: FEBRUARY 4, 2001

GROUND SURFACE  ML/SM-SILT and SAND (FILL), trace clay, medium plasticity, gray brown, moist, trace ootlets  FOPSOIL, silt, some sand, medium plasticity, trace clay, trace gravel, brown, rootlets  ML-SILT, little clay, trace fine sand, medium to high plasticity, gray to light brown, moist  CL-CLAYEY SILT, trace fine sand, high plasticity, gray to light brown, moist  GM-SAND, some silt, trace clay, low plasticity, gray, moist  ML-CLAYEY SILT (LACUSTRINE), little fine and, trace gravel, low plasticity, gray, varving isible (horizontal)  Free product @ 11.0 to 15.0ft BGS	617.0 617.0 615.1 614.8 614.1 610.3 609.8	INSTALLATION  2" Ø BOREHOL  BENTONI GROUT	2GP 2AGP 2BGP	[/ \ <u>]</u>	IN, VALUE	PID (ppm lico (g- loft)
medium plasticity, gray brown, moist, trace rootlets  FOPSOIL, silt, some sand, medium plasticity, trace clay, trace gravel, brown, rootlets  AL-SILT, little clay, trace fine sand, medium to high plasticity, gray to light brown, moist  CL-CLAYEY SILT, trace fine sand, high plasticity, gray to light brown, moist  SM-SAND, some silt, trace clay, low plasticity, gray, moist  HL-CLAYEY SILT (LACUSTRINE), little fine land, trace gravel, low plasticity, gray, varving isible (horizontal)  - free product @ 11.0 to 15.0ft BGS	614.8 614.1 610.3 609.8	BOREHOL BENTONI	_E 2GP 2AGP 2BGP	[/ \ <u>]</u>		(8-
GM-SAND, some silt, trace clay, low plasticity, gray, moist  IL-CLAYEY SILT (LACUSTRINE), little fine land, trace gravel, low plasticity, gray, varving isible (horizontal)  Free product @ 11.0 to 15.0ft BGS	609.8	BOREHOL BENTONI	2GP 2AGP 2BGP	[/ \ <u>]</u>		(8-
	602.0		TE			
OTTOM OF BOREHOLE @ 15.0ft. BGS	602.0					
				1	- 1	
	MEASURING POINT ELEVATIONS MAY CHANGE; RE	MEACURING POINT SURVATIONS MAY CHANGE REFER TO C	MEACURING SOINT ELEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TARLE	MEASURING POINT SLEVATIONS MAY CHANGE: REFER TO CURRENT ELEVATION TABLE	MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE	MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

(WL-69) *Page 1 of 1* 

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP32A-01

DATE COMPLETED:

DRILLING METHOD:

CRA SUPERVISOR:

DEPTH   ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<u> </u>	S.	AMPLE	
	GROUND SURFACE	617.0	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm
2.5	Drove down to 10.0ft BGS						
5.0			2" Ø BOREHOLE				
7.5							
10.0	ML-CLAYEY SILT (LACUSTRINE), little fine sand, low plasticity, gray, moist, chemical odor, free product	607.0	BENTONITE GROUT	1GP	$\bigvee$		
15.0 -	BOTTOM OF BOREHOLE @ 15.0ft. BGS	602.0		IAGP	$\triangle$		7450 (14.5-
7.5	-						15ft)
20.0							
2.5							
25.0							
27.5							
0.0							
32.5							

(WL-102) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

CHEMICAL ANALYSIS

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP33-01

DATE COMPLETED: FEBRUARY 2, 2001

EPTH !	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<u> </u>	S.	AMPLE	: 
. 863	GROUND SURFACE	617.B	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppn
	ML-SILT, with to and clay, little sand, rootlets, low to medium plasticity, dark to red brown, oxidized, moist	617.3					
2.5	ML-SILT, some clay, rootlets, medium plasticity, gray to gray brown, moist, fractured vertical and horizontal	613.3	2" Ø BOREHOLE	1GP 1AGP	$\bigwedge$		80 (3 <del>-</del>
5.0	CL-CLAY, some silt, little sand, medium plasticity, gray brown, moist  ML-CLAYEY SILT (LACUSTRINE), little fine	612.3	BONEHULE	2AGP			5ft 234 (5- 5.5f
7.5	sand, trace gravel, low plasticity, gray, moist, varving visible		BENTONITE GROUT	2GP 2BGP	$\bigwedge$		129
0.0					$\langle \cdot \rangle$		(8- 10ft
2.5				3GP	$\left  \right $		2
5.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	602.8		3AGP			24.5 (14- 15ft
7.5							
0.0							
2.5							
5.0							
7.5							
0.0							
2.5							
			ļ				

(WL-103) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP34-01

DATE COMPLETED: FEBRUARY 2, 2001

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR	<u></u>	S.	AMPLE	· 
ft. BGS	GROUND SURFACE	ft. AMSL 623.3	INSTALLATION	NUMBER	STATE	N' VALUE	PIO (ppr
-2.5 -5.0	ML-SILT, with to and clay, little sand, rootlets, low to medium plasticity, dark brown, moist  ML-SILT, little clay, little fine sand, trace gravel, rootlets, low plasticity, brown, moist, oxidized, fractured vertical and horizontal  dark brown @ 3.5ft BGS  little sand, rootlets, low to medium plasticity,	622.7	2" Ø BOREHOLE	1GP			0 (3- 4ft)
·7.5	dark brown to red brown, fractured vertical and horizontal @ 4.0ft BGS  CL-CLAY, trace silt, little sand, gray	616.8		2AGP	X		0
-10.0	CL-CLAY, trace silt, medium to high plasticity, gray to brown	615.3	BENTONITE GROUT	2GP			(6.5- 8ft)
-12.5	ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, gray, moist,	610.8		3AGP 3GP	$\langle \ \rangle$		35 (10- 12ft) 0
-15.0	varving visible			4GP	$\bigwedge$		(13- 13.5ft
-17.5	BOTTOM OF BOREHOLE @ 17.0ft. BGS	606.3			·Y		
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							

(WL-80) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP35-01

DATE COMPLETED: FEBRUARY 4, 2001

			<del></del>	<del>,</del>			
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	ļ	S	AMPLE	
11. 003	GROUND SURFACE	618.5	MOTALEATION	NUMBER	STATE	N' VALUE	PID (ppm)
-2.5 -5.0	ML-SILT (FILL), some fine sand, little gravel, trace clay, medium plasticity, light brown, moist CRUSHED STONE (1.4" Ø), low plasticity, black, chemical odor  ML-CLAYEY SILT, some fine sand, little rootlets, medium plasticity, gray with light brown, oxidation	- 617.9 - 617.3	2" Ø BOREHOLE	1GP			30 (4.5-
<b>-</b> 7.5	ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, gray, moist, varving visible (horizontal)	611.7	BENTONITE GROUT	2AGP 2GP 2BGP			5ft) 32 (6.8- 7.2ft) 2.4
-10.0	BOTTOM OF BOREHOLE @ 9.0ft. BGS	009.5			<u>/_\</u>		(8.5- 9ft)
<b>–12.5</b>							
-15.0							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO C	URRENT ELEVATION TABLE				
	WATER FOUND ¥ STATIC WATER LEVEL ₹						- 1

(WL-81) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP36-01

DATE COMPLETED: FEBRUARY 4, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION		S	AMPLE	
11. 865	GROUND SURFACE	618.1	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
-2.5	ML-SILT (TOPSOIL), some sand, trace gravel, trace clay, rootlets, medium plasticity, brown to light brown, moist  ML-SILT, little fine sand, trace clay, trace gravel, rootlets, low plasticity, moist  - slightly more clay, oxidation @ 2.0ft BGS	617.8	2" Ø BOREHOLE	IGP IAGP			7.6 (2.7- 3ft)
5.0 7.5	ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, gray, moist, visible varving (horizontal)	612.1	<i>Y////////</i>	2AGP 2GP			33 (5- 6ft)
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	608.1		28GP /			29 (9.5– 10ft)
-12.5							
-15.0							
-17.5							
-20.0							
-22.5							
<b>-</b> 25.0							
-27.5							
-30.0							
-32.5							
NI NI	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FFR TO C	URRENT ELEVATION TARLE				
	WATER FOUND ♥ STATIC WATER LEVEL ♥	100	THE PERIOD INDE				l

(WL-104) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP37-01

DATE COMPLETED: FEBRUARY 2, 2001

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	
ft. BGS	GROUND SURFACE	616.9	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
	ML-SILT (FILL), trace clay, trace fine grained sand, trace gravel, rootlets, medium plasticity, brown to dark brown, moist	615.9		IAGP	\	Z	0
-2.5	ML-SILT, trace clay, trace fine grained sand, trace gravel, low plasticity, light to medium brown, moist	613.4	2" Ø	IGR (BGP	X		(1- 1.5ft) 7.01 (2.5- 3.5ft)
-5.0	- very moist @ 2.5 to 3.5ft BGS  ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, gray, moist		BOREHOLE	2AGP			0
-7.5	– slightly less clay, varving visible @ 9.0ft BGS		BENTONITE GROUT	2GP			(5- 7ft)
10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	606.9		2BGP	/		1.0 (9- 101t)
·12.5							
15.0							
17.5							
20.0							
22.5							
25.0			į				
27.5							
30.0						]	
32.5					}		
					ļ		

(WL-105) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP38-01

DATE COMPLETED: FEBRUARY 2, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: D. MAPP

<u> </u>		_	T				
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	
11. 803	GROUND SURFACE	617.9	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
-2.5	ML-SILT (FILL), with to and clay, trace fine grained sand, medium plasticity, brown to light brown with gray, moist		2" Ø BOREHOLE	IGP 1AGP		-	0 (1– 1.5ft)
-5.0	- slightly more clay, gray @ 5.0ft BGS	612.4	BUREHULE	2AGP			0
<b>-7.5</b>	ML-CLAYEY SILT (LACUSTRINE), little fine grained sand, trace gravel, low to medium plasticity, gray, very moist - slightly less clay, varving visible @ 6.5ft BGS		BENTONITE GROUT	2GP 2BGP			(5- 5.5ft) 0
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	607.9					(9.5- 10ft)
-12.5							
-15.0							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE: R	EFER TO C	CURRENT ELEVATION TABLE				

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND ♀ STATIC WATER LEVEL ▼

(WL-106) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP39-01

DATE COMPLETED: FEBRUARY 2, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: D. MAPP

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR		S	AMPLE	
ft. BGS	GROUND SURFACE	ft. AMSL 621.2	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
-2.5	ML-SILT (FILL), some sand, trace clay, trace gravel, low to medium plasticity, brown to light brown, moist  ML-SILT, trace clay, trace sand, some gravel, low plasticity, brown to light brown and some	619.2		IGP	V V	.z	
-5.0	gray, dry to moist  ML-SILT, with clay, trace fine sand, some	615.2	2" Ø BOREHOLE	1AGP 2AGP			0 (3- 51t)
-7.5 -10.0	gravel, low to medium plasticity, gray, varving visible, fractured horizontal and vertical  - brown to light brown @ 7.0ft BGS  ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low to medium plasticity, gray, moist	613.2	BENTONITE GROUT	2GP 2BGP			(6- 71t) 12.8 (7- 81t)
-12.5	- slight decrease in clay, varving visible @ 10.0ft BGS  BOTTOM OF BOREHOLE @ 13.0ft. BGS	608.2		3GP 3AGP	X		0 (12- 13ft)
-15.0							
-17.5							
22.5							
25.0							
27.5							
30.0							ı
32.5	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE						

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE
WATER FOUND ▼ STATIC WATER LEVEL ▼

(WL-107) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS \_

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP42-01

DATE COMPLETED: FEBRUARY 2, 2001

	<del></del>	<u> </u>	T :			AMD! C	
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ft. AMSL	MONITOR INSTALLATION	-		AMPLE	
	GROUND SURFACE	618.6		NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5 -5.0	SM-SANDY SILT (FILL), trace clay, trace gravel, low to medium plasticity, brown with some gray, moist  SM/ML-SAND and SILT, trace clay, trace gravel, fine grained sand, low plasticity, moist  ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, light brown, varving visible (horizontal)  - slightly more clay, gray @ 6.3ft BGS	617.8 617.3	2" Ø BOREHOLE	IGP IAGP			5.9 (0.9- 1.3ft) 283 (6- 6.5ft)
-7.5 -10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	608.6	BENTONITE GROUT	2GP 2BGP	$\triangle$		32 (9.5~ 10ft)
-12.5							
-15.0							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N.	LOTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE	FER TO (	CURRENT FLEVATION TABLE				
L.	WATER FOUND ♥ STATIC WATER LEVEL ♥						ł

(WL-108) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP43-01

DATE COMPLETED: FEBRUARY 2, 2001

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION			AMPLE W	
	GROUND SURFACE	618.8		NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5 -5.0 -7.5	SM-SILTY SAND (FILL), little clay, trace gravel, trace rootlets, low to medium plasticity, brown with some gray, moist  ML-SILT, trace fine sand, trace gravel, trace rootlets, low plasticity, light brown, moist  SM/ML-SAND and SILT, trace clay, trace gravel, moist  ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, gray, moist, slight varving (horizontal)  BOTTOM OF BOREHOLE @ 5.0ft. BGS	617.9 618.0 615.7 613.8	BOREHOLE  BENTONITE GROUT	1AGP 1GP 1BGP			5.1 (2.3- 2.7ft) 26 (2.8- 3.0ft) 36 (4.5- 5ft)
-10.0							
-12.5							
, -15.0							
-17.5			s				
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
Ŋ	IOTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ♀ STATIC WATER LEVEL ▼ CHEMICAL ANALYSIS ○	FER TO C	CURRENT ELEVATION TABLE				

(WL-70) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP44-01

DATE COMPLETED: FEBRUARY 3, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: D. MAPP

		<del></del>	<del></del>				
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<u> </u>		AMPLE	<u> </u>
	GROUND SURFACE	618.0		NUMBER	STATE	N' VALUE	PID (ppm)
	ML-SILT (FILL), little fine sand, little gravel, medium plasticity, light brown, moist, rootlets	616.5				<u> </u>	
-2.5	ML-SILT, trace clay, trace gravel, medium to high plasticity, gray to light gray, moist to very moist - chemical odor @ 3.0ft BGS			IGP IAGP 2AGP	$\bigwedge$		250 (3.5-
-5.0	<ul> <li>very moist, crystalline chunks, amber in color, chemical odor @ 4.0 to 5.5ft BGS</li> <li>ML-CLAYEY SILT (LACUSTRINE), little fine</li> </ul>	612.5	2" Ø	2GP	$\bigvee$		4ft) 900 (4-
-7.5	sand, trace gravel, gray to light gray, moist, chemical odor  - varving visible @ 6.5ft BGS		BOREHOLE	28F	$\left\langle \cdot \right\rangle$		4.5ft) 120 (7.5- 8tt)
-10.0				3GP			
-12.5	BOTTOM OF BOREHOLE @ 13.0ft. BGS	605.0	GROUT GROUT	3AGP			24 (12.5– 13ft)
-15.0							
<b>⊢17.5</b>							l
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
NQ	TES: MEASURING POINT ELEVATIONS MAY CHANGE; R	EFER TO C	CURRENT ELEVATION TABLE				

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE
WATER FOUND 

▼ STATIC WATER LEVEL 

CHEMICAL ANALYSIS 

□

(WL~82) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP44A-01

DATE COMPLETED: FEBRUARY 3, 2001

	<del>,</del>	<del>,</del>					
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION		T	AMPLE	
	GROUND SURFACE	618.0		NUMBER	STATE	'N' VALUE	(mqq)
	ML-SILT (FILL), some fine sand, some gravel (3/4"Ø), trace clay, medium plasticity, light brown, moist	617.3		IAGP			1.1 (0.8-
-2.5	ML—SILT, little fine sand, trace gravel, trace clay, light brown to brown, moist  — slightly more clay, rootlets, gray, moist,		2" Ø	1GP			2ft)
<b>-</b> 5.0	fractured horizontally and vertically @ 2.0ft BGS - grading to silt and fine sand, trace gravel,	613.5	BOREHOLE	(IBGP	$\langle - \rangle$		27 (4– 4.5ft)
<b>-</b> 7.5	moist @ 4.0ft BGS  ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, gray, moist		BENTONITE GROUT	2GP			
-10.0	- slightly less clay, varving visible (horizontal) @ 9.5 to 10.0ft BGS  BOTTOM OF BOREHOLE @ 10.0ft. BGS	808.0		2AGP /	_		0 (9.5- 10ft)
-12.5	BOTTOM OF BONEFICEE & WORL. BUS						
-15.0							
-17.5							
-20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; RE WATER FOUND ¥ STATIC WATER LEVEL ▼	FER TO C	URRENT ELEVATION TABLE	- <u>-</u> -			

(WL-84) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

CHEMICAL ANALYSIS

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP45-01

DATE COMPLETED: FEBRUARY 3, 2001

EPTH . BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<u> </u>		AMPLE	
. 500	GROUND SURFACE	620.9		NUMBER	STATE	N' VALUE	PID (ppm
	ML-SILT (FILL), trace clay, trace fine sand, trace gravel, rootlets, low plasticity, brown to light brown, oxidized	619.4		IGP	V	<del>  -</del>	0
.5	ML-SILT, trace clay, fine sand, trace gravel, low to medium plasticity, brown		2" Ø				(2- 4ft)
.0	CL-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, gray, horizontally and vertically fractured	615.9	BOREHOLE	2AGP			1.0 (5- 6ft)
5	,		BENTONITE GROUT		$\langle \cdot \rangle$		
0.0	- slightly less clay @ 10.0 to 12.0ft BGS			3GP 3AGP	X		1.0
2.5	BOTTOM OF BOREHOLE @ 12.0ft. BGS	608.9			/\		(10- 12ft)
.0							
.5							
0.0							
2.5							
5.0			•				
7.5							
0.0							
2.5							
	IES: MEASURING POINT ELEVATIONS MAY CHANGE;						

(WL-109) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP47-01

DATE COMPLETED: FEBRUARY 3, 2001

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	
11, 803	GROUND SURFACE	620.6	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
	ML-SILT (FILL), little fine sand, trace gravel, rootlets, low plasticity, brown to dark brown, moist	620.3					
-2.5	ML-SILT, trace clay, little fine sand, trace gravel, medium plasticity, light brown to beige, moist, oxidation platlets, fractured horizontally and vertically		2" Ø BOREHOLE	IGP IAGP	$\bigwedge$		4.1 (3.5-
<b>-</b> 5.0	- slightly larger grained sand @ 3.5ft BGS - slightly more clay, gray, mild varving (horizontal) @ 4.0ft BGS	614.6		2AGP			4ft) 7.6 (5- 6ft)
-7.5	ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, low plasticity, gray, varving visible - slightly more clay @ 8.0ft BGS		BENTONITE GROUT	2GP	$\bigwedge$		
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	610.6		2BGP	/		0 (9.5- 10ft)
-12.5							
-15.0							
-17.5					ļ		
-20.0							
-22.5			į				
-25.0							
-27.5							
-30.0						ļ	
-32.5							
							j
N	OTES: MEASURING POINT ELEVATIONS MAY CHANGE; R WATER FOUND  ▼ STATIC WATER LEVEL ▼	EFER TO (	CURRENT ELEVATION TABLE		·		

(WL-85) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP48-01

DATE COMPLETED: FEBRUARY 3, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: D. MAPP

		Ţ		, <u></u>			
DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	ļ	S	AMPLE	<u> </u>
11. 503	GROUND SURFACE	620.6	INGTALLATION	NUMBER	STATE	N' VALUE	PID (ppm)
2.5	ML-SILT (FILL), little sand, trace gravel, trace clay, low to medium plasticity, light brown, moist  ML-SILT, trace clay, little fine sand, trace gravel, rootlets, low to medium plasticity, light brown to beige, moist, presence of oxidation	617.6		1GP IAGP	V		0.3
<b></b> 5.0	SM-SAND, some silt, trace clay, trace gravel, trace rootlets, low plasticity, gray to dark gray	615.1	2" Ø BOREHOLE	(BGP	$\left\langle \cdot \right\rangle$		(2.5- 3ft) 0.4 (4.5-
<b>-</b> 7.5	ML-CLAYEY SILT (LACUSTRINE), little fine sand, trace gravel, gray, moist, varving visible	0.0.7	BENTONITE GROUT	2GP			5ft)
-10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	610.6		2AGP			0 (9.5– 10ft)
-12.5							
-15.0							
-17.5							
-20.0							
-22.5							
-25.0					}		
-27.5							
-30.0							
-32.5							
- 1		ł	}	1	1		

WATER FOUND 

▼ STATIC WATER LEVEL 

▼

(WL-86) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP49-01

DATE COMPLETED: FEBRUARY 3, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR		S	AMPLE	
ft. BGS	GROUND SURFACE	ft. AMSL 625.5	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm)
2.5 5.0	ML-SILT (FILL), trace fine sand, trace gravel, rootlets, low plasticity, gray-brown, moist		2" Ø BOREHOLE	IGP IAGP			0.3 (3- 51t)
-7.5 -10.0	ML-SILT, little fine sand, trace gravel, rootlets, gray to light brown, moist, slight chemical odor  - trace fine sand, trace gravel, light brown to beige, slight chemical odor, moist, horizontal and vertical fractures @ 9.0ft BGS	617.5	BENTONITE GROUT	2GP 2AGP			1.8 (9– 101t)
_12.5	ML-CLAYEY SILT (LACUSTRINE), trace gravel, fow plasticity, gray to light gray, moist	612.5		3GP	$\bigwedge$		
-15.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	610.5		3BGP			2.4 (12.5~ 15ft)
-17.5							
_20.0							
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							
NO	ITES: MEASURING POINT ELEVATIONS MAY CHANGE: F	EFER TO C	CURRENT ELEVATION TABLE				

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND \$\Pi\$ STATIC WATER LEVEL \$\P\$\$ CHEMICAL ANALYSIS \$\infty\$

(WL-110) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP51-01

DATE COMPLETED: FEBRUARY 3, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: D. MAPP

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<u> </u>		MPLE	: 
	GROUND SURFACE	633.3	MOVERATION	NUMBER	STATE	'N' VALUE	P (p
,	ML-SILT (TOPSOIL), trace fine grained sand, trace gravel, rootlets, medium plasticity, dark brown, moist	632.9					
-2.5	ML—SILT, little fine sand, trace gravel, low plasticity, light brown to red brown, mild oxidation, moist, varving visible (horizontal)		2" Ø BOREHOLE	IGP	X		
5.0	- increase in clay, medium to high plasticity @ 4.0ft BGS			IAGP	$\langle - \rangle$		2. {4 51
-7.5	- increase in clay, high plasticity @ 6.0ft BGS  ML-SILT, little fine sand, trace clay, trace	626.1		2AGP	V		22
-10.0	gravel, low plasticity, light brown to medium brown, mild varving (horizontal), few vertical fractures		BENTONITE GROUT	26	$\bigwedge$		(7. 7.7
10.0	– some clay, high plasticity, brown @ 11.7ft BGS				$\setminus /$		
-12.5	CL-CLAYEY SILT, little fine sand, trace gravel, medium plasticity, moist	621.0		3GP 3AGP 3BGP	X		12 (11, 12,3
15.0	– less clay, varving visible (horizontal), low plasticity @ 15.5ft BGS						(13 13.5
17.5				4GP	X		0
20.0	- slightly more clay, medium plasticity @ 20.6ft BGS				$\langle \cdot \rangle$		(1E 201
22.5		600.8		5GP 5AGP	$\bigvee$		0
25.0	BOTTOM OF BOREHOLE @ 23.5ft. BGS	609.8					(22. 23.5
27.5							
30.0							
32.5							

WATER FOUND ¥ STATIC WATER LEVEL ¥



(WL-87) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP52-01

DATE COMPLETED: FEBRUARY 4, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

EPTH BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION			AMPLE Ш	<u> </u>
	GROUND SURFACE	633.0		NUMBER	STATE	N' VALUE	PII (pp
	ML-SANDY SILT (TOPSOIL), trace clay and gravel, few rootlets, dark brown, moist	632.0					
5	ML-SANDY SILT, trace clay and gravel, low plasticity, brown, moist, varving visible			IGP	X		
0			2" Ø BOREHOLE	IAGP	$\left\langle \begin{array}{c} \\ \\ \end{array} \right\rangle$		0 (3- 5ft
5		624.5	BENTONITE GROUT	2GP 2AGP	X		0 (6:
0.0	ML-CLAYEY SILT, trace gravel and fine sand, medium plasticity, gray, moist	024.5	GAGOT	28GP	<u>/                                    </u>		8.5f 0 (9- 10ft
.5	ML-SANDY SILT, some clay, trace gravel, low plasticity, brown, moist	621.0	<i>\( \( \( \( \( \) \) \)</i>	3GP 3AGP			0 (10- 12ft
.0	ML-SANDY SILT (LACUSTRINE), trace clay and gravel, low plasticity, gray, moist	618.0		3BGP	<u>/                                    </u>	}	0 (12- 14ft
.5				4GP 4AGP	X		0 (17- 1911
0.0	BOTTOM OF BOREHOLE @ 20.0ft, BGS	613.0		4BGP	_		0 (19- 20fi
2.5							
5.0							
7.5							
0.0							
2.5							

WATER FOUND 

STATIC WATER LEVEL 

▼

(WL-88) *Page 1 of 1* 

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP53-01

DATE COMPLETED: FEBRUARY 4, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<u> </u>		AMPLE	
., 555	GROUND SURFACE	632.0		NUMBER	STATE	N' VALUE	PID (ppm
2.5	ML-SANDY SILT (TOPSOIL), trace clay and gravel, presence of rootlets, dark brown, moist ML-SANDY SILT, trace clay and gravel, low plasticity, brown, moist	631.0	2" Ø	IGP IAGP		/	0.2
5.0 7.5	~ becoming medium plasticity, wet @ 7.0ft BGS		BOREHOLE	2GP	$\sqrt{}$		0.2 (3- 5ft)
10.0	CL-SILTY CLAY, trace sand, high plasticity, gray with pinkish veins	623.0	BENTONITE GROUT	2AGP 2BGP	$\frac{}{}$		0 (6- 8ft) 0 (8- 9ft)
12.5	AND CAMPA ON TAXABILITATION OF THE COMPANY OF THE C	618.0		3GP 3AGP	$\bigvee$		0 (11– 13ft)
15.0	ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, low plasticity, gray, moist			3BGP 4GP			0 (14– 15ft)
20.0	BOTTOM OF BOREHOLE @ 20.0ft. BGS	612.0		4AGP	$\bigwedge$		0 (18– 20ft)
22.5							
25.0							
7.5							
0.0							
32.5							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE WATER FOUND ♀ STATIC WATER LEVEL ♥

(WL-89) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP54-01

DATE COMPLETED: FEBRUARY 4, 2001

DEPTH t. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	-	<u>. S.</u>	AMPLE	
1. 865	GROUND SURFACE	621.6	INSTALLATION	NUMBER	STATE	N' VALUE	PID mqq)
2.5 5.0 –	ML-SANDY SILT, trace clay and gravel, low plasticity, brown, moist to wet, varving visible between 2.0 and 3.0ft BGS  - poor recovery @ 3.0 to 5.0ft BGS  ML-SANDY SILT, some clay, trace gravel, low plasticity, gray, moist, varving visible	616,6	2" Ø BOREHOLE BENTONITE GROUT	) }		-	0 (3- 51t) 2 (5- 71t)
10.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	606.6		3GP 3AGP 3BGP			0 (9- 10ft) 0 (11- 13ft) 0 (14- 15ft)
7.5							
20.0							
22.5							
25.0							
27.5							
30.0							
32.5							

(WL-90) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP55-01

DATE COMPLETED: FEBRUARY 4, 2001

DEPTH	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION		S	AMPLE	: <del></del>
ft. BGS	GROUND SURFACE	621.8	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm
	ML-SANDY SILT, some clay, trace gravel, medium plasticity, brown, wet			-	/		
-2.5 -5.0	- becoming gray/brown and moist @ 4.5ft BGS  ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, low plasticity, moist to dry, varving visible, no odor	619.3	2" Ø BOREHOLE	1GP 1AGP 1BGP			1 (3- 4ft) 1 (4- 5ft) 3
7.5			BENTONITE GROUT	2GP 2BGP	$\bigwedge$		(5.5- 7ft) 0
10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	611.8	<i>Canada</i>				(9- 10ft)
12.5							:
15.0			,				
17.5							
20.0							
22.5							
25.0					9		
27.5							
30.0							
32.5							

(WL-91) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP56-01

DATE COMPLETED: FEBRUARY 4, 2001

DRILLING METHOD: GEOPROBE CRA SUPERVISOR: L. PAQUETTE

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION			AMPLE	:
1 555	GROUND SURFACE	622.6	THO PALEATION	NUMBER	STATE	'N' VALUE	PID (ppm)
-2.5 -5.0	ML-SANDY SILT, some clay, trace gravel, low plasticity, brown, moist		2" Ø BOREHOLE	IGP 1AGP			0 (3- 5ft)
-7.5	ML-SANDY SILT, some clay, trace gravel, low plasticity, gray, moist, varving visible	618.6	BENTONITE GROUT	2BGP 2GP 2CGP	$\bigvee$		1 (5- 6ft) 4 (6.5- 8ft)
-10.0 -12.5	- becoming wet @ 10.0ft. BGS			3GP 3AGP			0.3 (11- 13ft)
-15.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	607.6					
-17.5					ļ		
-22.5							
-25.0							
-27.5							
-30.0							
-32.5							

NOTES: MEASURING POINT ELEVATIONS MAY CHANGE; REFER TO CURRENT ELEVATION TABLE

WATER FOUND 

STATIC WATER LEVEL 

CHEMICAL ANALYSIS 

○

(WL-92) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP57-01

DATE COMPLETED: FEBRUARY 4, 2001

DEPTH ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION		S.	AMPLE	: 
. 603	GROUND SURFACE	622.9	INSTALLATION	NUMBER	STATE	N' VALUE	PID (ppm
0.5	ML-SANDY SILT (FILL), some clay, trace gravel, low plasticity, brown, moist, varving visible from surface						
2.5	- compressed topsoil layers with roots @ 3.0ft. BGS  ML-SANDY SILT, some clay, trace gravel, low	619.9	2" Ø BOREHOLE	IGP (AGP)	$\bigwedge$		0
5.0	plasticity, brown, moist  ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, low plasticity, gray, varying	617.9	BUNEHOLE		$\langle \ \rangle$		(3– 5ft)
7.5	visible, no odor		BENTONITE GROUT	2GP 2AGP 2BGP	X		0 (5- 7ft) 0
10.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	612.9					(7.5- 9.5ft)
12.5							
15.0		-					
17.5						}	
20.0							
22.5							
25.0							
27.5							
30.0							
32.5							

(WL-93) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP58-01

DATE COMPLETED: FEBRUARY 4, 2001

ft. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION			AMPLE	<del></del>
11. 865	GROUND SURFACE	622.1	INSTALLATION	NUMBER	STATE	N' VALUE	PID mqq)
-2.5 -5.0 -7.5	ML-SANDY SILT (FILL), some clay, trace gravel, low plasticity, brown, moist, varving visible to 4.0ft BGS  - compressed topsoil with rootlets @ 4.0ft BGS  ML-SANDY SILT, some clay, trace gravel, low plasticity, brown to gray, moist - gray, varving visible @ 5.5 at 12.5ft BGS	618.1	2" Ø BOREHOLE	1GP 1AGP 2BGP 2AGP		-	0 (3- 4ft) 0 (4- 5ft) 0 (5.5- 7ft)
-10.0	- becoming wet @ 10.0ft BGS	800.6	GROUT	2BGP 3GP 3AGP			0 (9- 10ft) 0 (11-
-15.0	BOTTOM OF BOREHOLE @ 12.5ft. BGS	609.6					12ft)
-17.5							
20.0							
22.5							
25.0							
30.0							
32.5							

(WL-94) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

PROJECT NUMBER: 11676

CLIENT: FIELDS BROOK ACTION GROUP

WATER FOUND ¥

CHEMICAL ANALYSIS

STATIC WATER LEVEL \$

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP59-01

DATE COMPLETED: FEBRUARY 4, 2001

EPTH . BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV.	MONITOR INSTALLATION	<u></u>		MPLE	: 
. 803	GROUND SURFACE	622.1	INSTALLATION	NUMBER	STATE	'N' VALUE	PID (ppm
2.5	ML-SANDY SILT, trace clay, trace gravel, low plasticity, brown, moist, varving visible		2" Ø BOREHOLE	1GP	X		0
.5	ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, low plasticity, gray, moist, varving visible	616.6	BENTONITE GROUT	2AGP 2GP	X		(4- 5ft) 0 (5.5- 7ft)
0.0	BOTTOM OF BOREHOLE @ 10.0ft. BGS	612.1		2BGP			0 (9- 10ft)
2.5							
5.0							
7.5							
0.0							
2.5			-				
5.0							
7.5							
0.0							
2.5							

(WL-95) Page 1 of 1

PROJECT NAME: FIELDS BROOK SUPERFUND SITE

CHEMICAL ANALYSIS

PROJECT NUMBER: 11676


CLIENT: FIELDS BROOK ACTION GROUP

LOCATION: ASHTABULA, OHIO

HOLE DESIGNATION: GP60-01

DATE COMPLETED: FEBRUARY 4, 2001

DEPTH t. BGS	STRATIGRAPHIC DESCRIPTION & REMARKS	ELEV. ft. AMSL	MONITOR INSTALLATION	<u> </u>		AMPLE	: T
003	GROUND SURFACE	622.3	INOTALLATION	NUMBER	STATE	'N' VALUE	PIE (ppi
2.5	ML-SANDY SILT, trace clay and gravel, low plasticity, brown, moist, varving visible from surface		2" Ø BOREHOLE	1GP 1AGP			0 (3- 51t) 0.5 (5-
0.0	ML-SANDY SILT (LACUSTRINE), some clay, trace gravel, low plasticity, gray, moist, varving visible	615.8	BENTONITE GROUT	2GP 2BGP	$\bigwedge$		0.3 (8- 10ft)
2.5				3GP 3AGP			0.1 (12- 14ft
5.0	BOTTOM OF BOREHOLE @ 15.0ft. BGS	607.3					1410
7.5							
0.0						1	
2.5							
5.0							
7.5							
0.0							
2.5							



ELEVATION TOP OF RISER PIPE: 636.99	DRIL	LIN	G FII	RM: N	latec	Chemical Company DATE DRILLE o Drilling Company INSPECT CME HT75	D: 23 July 1990 OR: S. Basham
GROUND ELEVATION: 634.49	DEPTH (Ft)	i .	1	B./FT.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	SS	4	1.8	Soft, moist to wet, orange-brown Silty SAND (SM)	Lacustrine
		2	SS	10	2.0	Soft, moist, gray w/ orange mottling Silty CLAY (CL) Stiff, moist, gray with orange mottling Silty CLAY	
	5	3	SS	7	2.2	Firm, moist, light brown CLAY (CL); trace gray and black sand	
		4	SS	8	2.2	Firm,moist,it brown w/ trace orng mottling CLAY; trace black sand,gravel,& iron-stained partings	
	10	5	SS	10	2.2	heavier iron staining	
		6	SS	8	2.0		
	15	8	SS	14	2.2	Stiff, wet light brown with iron staining Sandy CLAY (CL)	
		9	SS	9		Stiff, moist, gray CLAY (CL); trace fine gravel	
		10	SS	9	2.2	shale fragments	
	20	11	SS	10	2.2	Stiff maint to wot grow OLAV (OL) stone to an firm	,
		12	SS	13	2.2	Stiff, moist to wet gray CLAY (CL); trace to no fine gravel	
	25	13	SS	11	1.4		Lacustrine
		14	SS	20		Stiff, wet, gray Silty CLAY (CL-ML) Very stiff, wet, gray Silty CLAY	Till
	30	15	SS	17	1.4		
		16	SS	8	2.2	Firm, moist to wet, gray SIIty CLAY	
		17	SS	4	2.2	Soft, wet, gray with black laminae Silty CLAY	
	35	18	SS	7		Firm, wet, gray, Silty CLAY fine sand lense	
		19	SS	7		Firm, moist, gray CLAY (CL)	
	40	J				Firm, moist, gray CLAY; trace gravel (no sample recovered due to driller error)	
				cici r		LOG OF BORING FBMW-2D	
CHECKED BY: JO	CL D	ATE:		V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 3

Daga Cat C	DEC.	1		T	1		
Page 2 of 2	DEPTH (Ft)	SMPL NO.	TYPE	B/Ft	ļ		COMMENTS
		20	SS	10	2.2	Stiff, moist, gray CLAY; trace gravel	
		21	SS	9	2.2		
	45	22	SS	16	1.8		
		23	SS	24	1.6		
	_	24	SS	23	1.6	Very stiff, moist, gray CLAY; some fine to medium grained gravel	
	50			>68	1.4	3	TiU
			NQ			Gray SHALE (51.5 ft.)	BEDROCK
==						Highly weathered, thin bedded.	
==	55						
		27	NQ		4.4		
==	60						
						End of boring at 60.5 feet.	
						Water encountered at 13.5 feet.	
	65						
	70						
	75						
	80						
	*********						
	85						
				FIEL		LOG OF BORING FBMW-2D ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL D	ATE:		OV 199		PROJECT No.: 86C3609D-230	FIGURE No.: 3

Woodward-Clyde Consultants

ELEVATION TOP OF RISER PIPE: 638.81 ft.	DRIL	LIN	3 FIF	RM: N	<b>Aatec</b>	Reach 11 DATE DRILLED: 1: o Drilling Company INSPEC ME 850	2, 13 June 1990 TOR: S. Shubat	1
GROUND ELEVATION: 635.61	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	1
		1	cs	4.5	4.4	Hard, moist, dk bwn CLAY (CL); trace sand	Lacustrine	1
						Hard, moist, light brown, iron stained, gray mottled Silty CLAY (CL); some gravel, trace organic material	OVA=BG	
	5	2	CS	4.5	5.0	increased iron staining	OVA=BG	
	10	3	cs	4.0	4.5	Moist, gray and tan mottled, fine SAND and SILT (ML)	OVA=BG	
						Moist, gray, fine SAND and SILT; clay content increasing with depth		
	15	4	cs		5.0	Moist, interbedded gray CLAY (CL) and gray fine SAND (SM)	OVA=BG	
						Moist gray CLAY (CL); lenses of fine sand		
	20	5	cs				Lacustrine	J
	_					Moist, gray Silty CLAY (CL-ML); lenses of fine sand and silt	OVA=BG Till	]
	25	6	cs			Moist, gray Silty CLAY (CL-ML); lenses of fine sand, silt, and iron staining	OVA≃BG	
				PP Ortograph is pro-	114 7-7-1-1-p N BAS ALLA	Hard, moist, gray, Silty CLAY; with fine gravel		しゅつ
	30	7	cs	4.5	5.0	Hard, moist, gray, Silty CLAY; trace coarse sand	OVA=BG	I till
	35	8	cs	4.5	5.0		OVA=BG	
	40	9	cs	4.5	5.0		OVA=BG	
				FIEL		LOG OF BORING FBMW-3D ROOK SOURCE CONTROL - ASHTABULA, OHIO		
CHECKED BY: JO	CL D	ATE:		V 199			FIGURE No.: 4	J

Page 2 of 2	DEPTH	PLIP					T
	(Ft)			P.P	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						Hard, moist, gray, Silty CLAY (ML-CL); trace	OVA=BG
		-				coarse sand	
	45	10	CS	4.5	5.0		
		1.0		7.0	0.0		
							Till
	50	11	CS	5.0	5.0	Gray SHALE (48.3 ft.) Fractured, unweathered (upper 2-inches	Bedrock
		''		0.0	3.0	weathered), thin bedded	
						, , , , , , , , , , , , , , , , , , ,	
==							
	55	12	cs				
	- 55	12	CS	2.0	2.0		
						End of boring at 56.0 feet.	1
				:		Water encountered during drilling at 19 feet.	
	60	}					
	65			- [			
				İ			,
	70						
				İ			
				1	ļ		
	75						
				Į			
					Í		
				1			
	80			ļ			
				[			
				1	ļ		
	85				1		
						LOG OF BORING FBMW-3D	
}				FIELD		ROOK SOURCE CONTROL - ASHTABULA, OHIO	·
CHECKED BY: J	CL D	ATE:	1 NC	V 199	0	PROJECT No.: 86C3609D-230	FIGURE No.: 4

DEPTH Survey (F) No. rive P.P. REC DESCRIPTION OF STRATIGRAPHY COMMENTS  See log of FBMW-3D for description of stratigraphy.  See log of FBMW-3D for description of stratigraphy.  15  15  20  20  30  30  40  LOG OF BORING FBMW-3S FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO	ELEVATION TOP OF RISER PIPE: 637.69 ft.	DRIL	LING	3 FIF	RM: N	latec		D: 13 June 1990 CTOR: S. Shubat
Stratigraphy.    Stratigraphy.	ELEVATION:	DEPTH	SMPL					COMMENTS
FIELDS BROOK SOURCE CONTROL – ASHTABULA, OHIO							stratigraphy.	
CHECKED BY: JCL DATE: 1 NOV 1990 PROJECT No.: 86C3609D-230 FIGURE No.: 5	CHECKED BY: J	ICL ID	ATE:			OS B	ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No. 5

ELEVATION TOP OF RISER PIPE: 633.82 ft.	DRIL	LING	FIF	RM: M	lateco	Reach 11 DATE DRILLED: 5 Drilling Company INSPEC ME 850	1-3 June 1990 TOR: S. Shubat
GROUND ELEVATION: 630.92	DEPTH (FI)		TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	CS	3.5	4.0	Very stiff, moist to dry, brown Clayey SILT (ML); some gravel	Fill OVA=BG
	5	2	CS	3.5	5.0	Very stiff, moist to dry, brown, mottled w/ gray & iron staining Clayey SILT (ML); some gravel Very stiff, moist, dark brown mottled with iron stain Silty CLAY (CL); with roots, trace fine to coarse sand	Fill
	10	3	cs	3.5	5.0	Very stiff, moist to dry, brown Silty CLAY grading to CLAY (CL); trace iron-stained lenses, some fine sand lenses	OVA=BG
	15	4	Ce	4.5	5.0	Hard, moist to dry, gray Silty CLAY (CL-ML); trace	Lacustrine
		4	US	,4. <b>5</b>	ວ.ບ	coarse sand	OVA=BG
	20	5	CS	4.5	5.0	Hard, moist to dry, gray Silty CLAY; trace medium to coarse sand, trace cobbles	
							OVA=70
		6	cs	4.5	5.0	Hard, dry, gray Silty CLAY; trace medium to coarse sand, trace cobbles	
	30	7	CS	4.5	5.0	Hard, dry, gray Silty CLAY; trace medium to coarse sand	
	35	8	cs	4.5	5.0	Hard, dry, gray Sandy Silty CLAY; trace cobbles	
	40	9	CS			Hard,moist/wet,gray Silty CLAY;some coarse sand	Till
	<del>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</del>					LOG OF BORING FBMW-4D	
CHECKED BY: J	Ci In	ATF.		FIELD V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 6
	- 0			- 100	•		1 1301 IL 110 0

Page 2 of 2	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		-		$\vdash$		Gray SHALE (40.2 ft.)	Bedrock
	_					Weathered, thin bedded	200,000
==		-					
==							
	45	10	CS			Unweathered, thin bedded, gray SHALE	
==							
	<b> </b>						
	<b>I</b> —	ŀ					
L	50		-			End of boring at 48.8 feet	-
	1 00	1				Water encountered during drilling at 40 feet.	
	I —					victor of control of any graming at 10 100t.	
	55	]					
							!
	l —						
	60						
	60						
	l —						
							_
	65						
					1		
	70			-			
				1			•
				}			
	75						
	-,3				- 1		
	80						
				j			
				ĺ			
	85						
				FIFI	S RE	LOG OF BORING FBMW-4D ROOK SOURCE CONTROL - ASHTABULA, OHIO	)
CHECKED BY:	JCL D	ATE:		V 199		PROJECT No.: 86C3609D-230	FIGURE No.: 6
							1

ELEVATION TOP OF RISER PIPE: 632.89 ft.	DRI	LLING	3 FIF	RM: M	latec		D: 3 June 1990 TOR: S. Shubat
GROUND ELEVATION: 630.92	DEPTI (Ft)			P.P.	REC		COMMENTS
						See log of FBMW-4D for description of stratigraphy.  LOG OF BORING FBMW-4S	
CHECKED BY: J	CL	DATE	1 N(	FIELI OV 199		PROJECT No.: 86C3609D-230	FIGURE No.: 7

ELEVATION TOP OF RISER PIPE: 631.66	DRIL	LIN	3 FIF	RM: N	<b>Natec</b>	Reach 11 DATE DRILLED: 1 o Drilling Company INSPEC ME 850	16,17 June 1990 TOR: S. Shubat	
GROUND ELEVATION: 629.16	DEPTH (FI)	SMPL NO.	ΤΎΡE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	
		1	cs	3.5	3.5	Very stiff, moist, brown & gray mottled, Silty CLAY (CL); trace roots	Lacustrine OVA=BG	
	5	2	cs	4.5		Wet, brown, fine SAND and SILT (SW-SM) Hard, moist, gray with brown mottling, Silty CLAY (CL); trace thin, fine sand lenses	OVA≖BG	
	10	3	cs	4.5		Hard, dry, gray with brown mottling, Silty CLAY; trace thin, fine sand lenses Hard, dry, gray Silty CLAY (CL-ML); silt content increases with depth	Lacustrine Till	
	15	4	cs	4.5		no comme?	OVA=BG OVA=0.5	<b>\</b> \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
	20	5	CS	4.5	5.0	Hard, dry, gray Silty CLAY; some coarse sand, trace fine gravel, granite cobble	OVA=BG	
	25	6	CS	4.5	5.0		OVA=BG	Piek/E
	30	7	cs	4.5	5.0			
	35	8	CS	4.5		Gray SHALE (31.9 ft.) Weathered, fractured, thin bedded	Till Bedrock	
	40	9	cs	4.5		Slightly weathered, fractured, thin bedded, gray SHALE  LOG OF BORING FBMW-5D		
CHECKED BY: JCL	D/	TF.		FIELD V 199	OS BF	ROOK SOURCE CONTROL - ASHTABULA, OHIO	FIGURE No.: 8	

Page 2 of 2	DEPTH (Ft)	SMPL NO.	TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
==		1				Gray SHALE	
== '		<b> </b> .		]	]	Slightly weathered, fractured, thin bedded	1
		1					,
				]		End of boring at 42.5 feet.	
	45	1					
J ·							
	<u> </u>						
	—						
	50						
		1					
	<u> </u>						
	55	-					
Í	<b>[</b>						
	<b>1</b>						
	l —						
	60						
		1					
ŀ							
	65	1					
	70						
		1					
)			1	j			
				ļ			
	75						
	75						
]							
			1				
	80		[				i
							'
1			ļ				
[	<u></u>						
	85						
				FIELD	OS BF	LOG OF BORING FBMW-5D ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL [	ATE:	1 NC	OV 199	0		FIGURE No.: 8

ELEVATION TOP OF RISER PIPE: 631.76	DRIL	LIN	3 FIF	RM: N	latec		D: 20 June 1990 CTOR: S. Shubat		
ground Elevation: 629.16	DEPTH (Ft)	1	1	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS		
						See log of FBMW-5D for description of stratigraphy.			
LOG OF BORING FBMW-5S FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO									
CHECKED BY: JO	CL D	ATE:		V 199		PROJECT No.: 86C3609D-230	FIGURE No.: 9		

DEPTH SMPL (Ft) No. TYPE P.P. REC DESCRIPTION OF STRATIGRAPHY COMMENTS    Comments									
Loose, moist, black fine to medium SAND with silt (SW-SM); FILL  3.8broken glassbroken glassr-inch decomposed brick layer  3.7some medium to large gravel  Very soft, moist to wet, grn-black CLAY (CL) OVA=280 ppm; Fill Very soft, moist, orng-brwn Silty CLAY; trace gravel Hard, moist, orng-brwn Silty CLAY; trace gravel Hard, moist to dry, gray Silty CLAY; trace sand lenses Hard, moist to dry, gray Silty CLAY; some gravel  1.55-inch medium gray clay layer  Till									
Sw-SM); FILL									
2 CS 3.8broken glassbroken glassbroken glassbroken glass7-inch decomposed brick layer  3 CS 3.7some medium to large gravel Very soft, moist to wet, grn-black CLAY (CL) OVA=280 ppm; Fill Stiff, moist, gray w/ tan mottling, Silty CLAY (CL-ML) Till Hard, moist, orng-brwn Silty CLAY; trace gravel Hard, moist/dry, gray Silty CLAY; trace sand lenses Hard, moist to dry, gray Silty CLAY; some gravel OVA=6 ppm  1.5 CS 4.5 5.05-inch medium gray clay layer5-inch medium gray clay layer									
broken glass7-inch decomposed brick layer5-inch decomposed brick layer5-inch decomposed brick layer5-inch decomposed brick layer5-inch medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome grav									
3 CS 3.77-inch decomposed brick layersome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium to large gravelsome medium sity cLAY (CL)some provide points to wet, grn-black CLAY (CL)some provide points to wet, grn-black CLAY (CL)some medium sity cLAY; trace gravelsome medium sity cLAY; trace gravelsome gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide points to dry, gray Silty CLAY; some gravelsome provide p									
3 CS 3.7									
some medium to large gravel  Very soft, moist to wet, grn-black CLAY (CL)  Stiff, moist, gray w/ tan mottling, Silty CLAY (CL-ML)  Hard, moist, orng-brwn Silty CLAY; trace gravel  Hard, moist/dry, gray Silty CLAY; trace sand lenses  Hard, moist to dry, gray Silty CLAY; some gravel  OVA=6 ppm  1.5 some medium to large gravel  Very soft, moist to wet, grn-black CLAY (CL)  Hard, moist, orng-brwn Silty CLAY; trace gravel  Hard, moist to dry, gray Silty CLAY; some gravel  OVA=6 ppm some medium to large gravel  Till									
Very soft, moist to wet, grn-black CLAY (CL)  Very soft, moist to wet, grn-black CLAY (CL)  Stiff, moist, gray w/ tan mottling, Silty CLAY (CL-ML)  Hard, moist, orng-brwn Silty CLAY; trace gravel  Hard, moist/dry, gray Silty CLAY; trace sand lenses  Hard, moist to dry, gray Silty CLAY; some gravel  OVA=6 ppm  1.5  1.5  1.5  1.5  Till									
4.5 Stiff,moist,gray w/ tan mottling,Silty CLAY (CL-ML) Till  4.5 Hard, moist, orng-brwn Silty CLAY; trace gravel Hard, moist/dry,gray Silty CLAY; trace sand lenses Hard, moist to dry, gray Silty CLAY; some gravel OVA=6 ppm  1.5 1.5 4.55-inch medium gray clay layer  Till									
4.5   Hard, moist, orng-brwn Silty CLAY; trace gravel Hard, moist/dry, gray Silty CLAY; trace sand lenses Hard, moist to dry, gray Silty CLAY; some gravel OVA=6 ppm  1.5   1.5  5-inch medium gray clay layer  20   Till									
Hard, moist/dry, gray Silty CLAY; trace sand lenses Hard, moist to dry, gray Silty CLAY; some gravel OVA=6 ppm  1.5 4.5 20 Till									
5 CS 4.5 5.0 1.5 1.5 4.5 20 Till									
1.55-inch medium gray clay layer 4.5 Till									
4.5 Till									
CS 3.7 Gray SHALE (20.3 ft.) Hard, moderately weathered, thin bedded									
Hard, slightly weathered, thin bedded, gray SHALE									
(sample lost in boring; boring completed without									
25   sampler in augers)									
'   <del></del>									
==   30									
End of boring at 33 feet.									
35									
40									
LOG OF BORING FBMW-7D									
FIELDS BROOK SOURCE CONTROL – ASHTABULA, OHIO HECKED BY: JCL   DATE: 1 NOV 1990   PROJECT No.: 86C3609D-230   FIGURE No.: 10									

ELEVATION TOP OF RISER PIPE: 640.18	LOCA DRIL DRIL	ATIC LING	N: F	RMI M RM: N G TYI	letals latec PE: C	o Drilling Company INSP ME 750	ILLED: 4 June 1990 ECTOR: S. Basham
GROUND ELEVATION: 637.85	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						See log of FBMW-7D for description of stratigraphy.  LOG OF BORING FBMW-7S	
CHECKED BY: JO	CL D	ATE:	1 NO	FIELD V 199	S BF	ROOK SOURCE CONTROL - ASHTABULA, OH PROJECT No.: 86C3609D-230	FIGURE No.: 11

ELEVATION TOP OF RISER PIPE: 646.98		LINC	FIF	RM: M	latec	DATE DRILLE D Drilling Company INSPECTOR: S. Bas ME 750	D: 30 May 1990 sham, S. Shubat
GROUND ELEVATION: 644.38	DEPTH (Ft)		TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		2	cs cs	2.2		Dry to moist, brown CLAY (CL); with roots Loose, moist, blk, med. to fine SAND (SM) Fill Firm, moist, med. gray with rust colored mottling Silty CLAY (CL); trace poorly sorted gravel Very stiff, moist, medium gray with rust-colored mottling, CLAY (CL);	Fill OVA=BG Lacustrine
	10			4.5		Hard, dry to moist, gray and brown mottled Silty CLAY (CL); trace coarse gravel Hard,dry/moist,gray Silty CLAY;trace c. graveloxidized fracture	Lacustrine Till OVA=BG OVA=BG
	15		cs	4.5	5.0	oxidized fracture	OVA=BG
==		6	cs	4.5	5.0	Gray SHALE (26.4 ft.) Highly weathered, soft, thin bedded	Till Bedrock
	30	7	CS	4.5	5.0	Moderately weathered, soft, thin bedded, gray SHALE	
	35 ————————————————————————————————————	8	cs	4.5	1.8	End of boring at 35.4 feet.	
	<u> </u>	•	,	FIEL	DS BI	LOG OF BORING FBMW-8D ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL D	ATE	1 NO	OV 199	<del>)</del> 0	PROJECT No.: 86C3609D-230	FIGURE No.: 12

ELEVATION TOP OF RISER PIPE: 647.13	LOCA DRIL DRIL	ATIC	N: F G FIF	RMI M RM: M G TYI	letals latec PE: C		ay – 1 June 1990 TOR: S. Basham
GROUND ELEVATION: 644.38	DEPTH (Ft)	SMPL		P.P.		DESCRIPTION OF STRATIGRAPHY	COMMENTS
	(Ft)	NO.	TYPE	P.P.	REC	See log of FBMW-8D for description of stratigraphy.	COMMENTS
	40			cici r	30 DF	LOG OF BORING FBMW-8S	
CHECKED BY: J	CL D	ATE:		V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 13

ELEVATION TOP OF RISER PIPE: 637.91 ft.		LING	3 FIF	RM: M	latec	DATE DRILLED: 2 D Drilling Company INSPECT ME 750	2, 23 May 1990 OR: N. Bigman
GROUND ELEVATION: 635.41	DEPTH (Ft)		TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	cs			Stiff, moist, dark gray with brown mottling, Silty CLAY (CL); trace to few sand and gravel Very stiff, dry to moist, light gray and brown mottled CLAY (CL); trace sand Hard, dry to moist, light gray and brown mottled	Lacustrine
						CLAY; trace sand and gravel	
	10		CS		5.0	Hard, dry to moist, light brown CLAY; trace sand and gravel Hard, dry to moist, gray CLAY; trace coarse sand and fine gravel	
	15 	4	cs		5.0	Dry to moist varves of fine gray Silty SAND (SM) and gray SILT (ML)  Very stiff, dry to moist, gray CLAY (CL); some fine sand partings	Lacustrine
	20	5	cs		5.0	Hard, moist, gray with trace red mottling, Silty CLAY (CL-ML); trace sand and gravel	Till
	25 	6	cs	And although the second	5.0	dark gray, coarse, angular, shale gravel	
	30	7	CS		5.0	Hard, moist, gray Silty CLAY; few gravel 1-inch gray, medium sand layer	OVA = 90 ppm
	35	8	CS		5.0	Hard, moist to dry, gray Silty CLAY; few gravel	OVA = 390 ppm
	40	9	cs		5.0		
				FIEL	OS BI	LOG OF BORING FBMW-11D ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL D	ATE:	1 NC	)V 1 <b>9</b> 9	0	PROJECT No.: 86C3609D-230	FIGURE No.: 14

Page 2 of 2	DEPTH	0145-					<u> </u>
1 496 2 01 2	(Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		-				Hard, dry to moist gray Silty CLAY (CL-ML); few gravel	
	45	10	cs		5.0		Till
						Gray SHALE (45.2 ft.)	Bedrock
==						Slightly weathered, thin bedded, moderately hard, fractured	RQD = 53%
	50	11	cs		4.5	Unweathered to slightly weathered, thin bedded moderately hard, fractured, gray SHALE	RQD = 74%
	55					End of boring at 53.5 feet.	
						Water found in sampler at 9 and 14 feet.	
	60						
	65						
	70						
	_						
	75				1		
<u> </u>					ĺ		
	80						
	_						
	85					LOG OF BORING FBMW-11D	
OUEOUES SU	O. T.		1.5:5	FIELD	S BF	ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: JO	CL D	ATE:	1 NO	V 199	)	PROJECT No.: 86C3609D-230	FIGURE No.: 14

ELEVATION TOP OF RISER PIPE: 637.91	DRI	LLING	3 FIF	Detrex RM: M G TYI	latec	DATE DRILLE o Drilling Company INSPEC ME 750	D: 24 May 1990 FOR: N. Bigman
ground ELEVATION: 635,41	DEPTI (Ft)	H SMPL		P.P.			COMMENTS
ELEVATION:				P.P.	REC	See log of FBMW-11D for description of stratigraphy.	COMMENTS
<b>.</b>	40						
						LOG OF BORING FBMW-11S	
CHECKED BY: J	CI	DATE		FIELI OV 199		PROJECT No.: 86C3609D-230	FIGURE No.: 15
OFFICIALD DT. J	UL.	UNIE	1 146	J# 150	~	F 1100E01 110., 0003003D=230	FRGUNE 140.; 15

ELEVATION TOP OF RISER PIPE: 636.53 ft.	DRIL	LOCATION: Detrex DRILLING FIRM: Mateco Drilling Company DRILLING RIG TYPE: CME 750  DATE DRILLED: 5,6 June 1990 INSPECTOR: S. Basham, N. Bigman										
GROUND ELEVATION: 633.63	DEPTH (Ft)		1	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS					
		1	cs	<b>4.5</b>	4.0	Very soft, moist, brn CLAY (CL); roots, trace sand Hard, moist, gray and brown mottled CLAY (CL); trace sandbecomes hard, moist to dry, brown with gray mottling	Lacustrine					
			Training of the state of the st	4.0		Very stiff, dry to moist, brown with gray mottling Silty CLAY (CL); varved with numerous silt partings						
	10 —	3	CS	4.2	5.0	4-inch orange-brown silt layer Hard,dry/moist,gray Silty CLAY; 5 inches of silt and sand interbeds2-inch gray fine sand layer						
	15 —	4	CS	2.5	4.6	Stiff, moist, gray with trace red mottling CLAY (CL); 5-inch sand pocket; planar partings on 1/4-inch scale						
	20	5	CS	2.2	5.2	Very stiff, dry to moist gray Silty CLAY (CL-ML); trace sand and gravel	Lacustrine Till					
	25 	6	cs			planar partings oriented 0-30°, one fine sand parting  Very stiff, dry to moist gray Silty CLAY;						
	30	7	cs	4.5	5.0	trace sand and coarse gravel Hard, dry to moist gray Silty CLAY; trace sand and coarse gravel						
	35	8	CS	4.5		Hard, dry to moist gray Silty CLAY;						
	40	9	cs		5.3	trace sand and few coarse gravel						
				FIELD	S BF	LOG OF BORING FBMW-12D ROOK SOURCE CONTROL - ASHTABULA, OHIO						
CHECKED BY: JO	CL D	ATE:		OV 199		SOO IFOT I	FIGURE No.: 16					

Woodward-Clyde Consultants

Very stiff, dry to moist, gray Slity CLAY (CL-ML) Gray SHALE (41.1 ft.) Soft, highly weathered, thin bedded Weathered, moderately soft, thin bedded, gray SHALE  10 CS 50 11 CS 50 11 CS 55	Page 2 of 2	DEPTH (Ft)	SMPL NO.	TYPE	B/Ft	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS			
Care SHALE (41.11)   Bedrock RQD=60%   RQD=60%   RQD=60%   RQD=82%   RQD=60%   RQD=6				1110							
Soft, highly weathered, thin bedded, gray HALE  Soft, highly weathered, moderately soft, thin bedded, gray RQD=82%  RQD=				_			Gray SHALE (41.1 ft.)				
==			[				Soft, highly weathered, thin bedded	RQD=60%			
So   11   CS   1.5   Mod. hard, slightly weath, thin bedded, gray SHALE   End of boring at 50.3 feet		<u> </u>				- 0		DOD 000/			
==		45	10	CS		5.2	SHALE	HQD=82%			
So											
So											
End of boring at 50.3 feet    Find of boring at 50.3 feet		50	11	CS		15	Mod hard slightly weath, thin hedded gray SHALE	BOD-0%			
55		- 30	' '	03		1.5	End of boring at 50.3 feet	1100-070			
60							-				
60	ł										
60		55			İ						
65 65 70 70 75 80 80 85  LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
65 65 70 70 75 80 80 85  LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO					ĺ						
65 65 70 70 75 80 80 85  LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
65 65 70 70 75 80 80 85  LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO		60									
TO  TO  TO  TO  TO  TO  TO  TO  TO  TO											
TO  TO  TO  TO  TO  TO  TO  TO  TO  TO											
TO  TO  TO  TO  TO  TO  TO  TO  TO  TO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO		65									
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO							:				
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO		70									
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO					1	ĺ					
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO	]										
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO		75									
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO	}					ļ					
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO	]										
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO		80									
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
	LOG OF BORING FBMW-12D FIELDS BROOK SOURCE CONTROL - ASHTARULA OHIO										
COUNTY TO THE PARTY OF THE PART	CHECKED BY: JO	CL D	ATE:	1 NO	V 199	0		FIGURE No.: 16			

ELEVATION TOP OF RIBER PIPE: 636.10 ft.	RISER PIPE: DRILLING FIRM: Mateco Drilling Company INSPECTOR: S. Basham, N. Bioma								
GROUND ELEVATION: 633.63	DEPTI (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	1	
						See log of FBMW-12D for description of stratigraphy.			
CHECKED BY: JO	ci lo	ATE		FIELD V 1990		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIOLIDE 11: 47		
~, IL. ~ ~ LD D1. JC	U	// I I I		4 133	اإ	1 110010 1 NO. 0000000 - 230	FIGURE No.: 17	۳	

ELEVATION TOP OF RISER PIPE: 628.45	DRIL	LIN	FIF		latec		): 11 June 1990 OR: N. Bigman
ground Elevation: 625.95	DEPTH (Ft)	1	TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	cs	1.5	3.7	Stiff, moist, mottled gray and brown Sandy CLAY (CL); trace cinders, gravel, brick fragments organic material and black sand pockets	Fill
	5	2	cs	2.0	4.3	Blk Sandy CLAY;trace cinder,grvl,sand,brick frags Interbedded brown and gray medium sand (SW); trace organic layers	Fill Lacustrine
	10	3	cs	0.2	4.3	Firm, moist, black CLAY (CL); with organic material trace roots3-inch gray clay layer Firm, moist, dark gray CLAY; trace organic mat. Firm, moist, black Sandy CLAY; w/ organic mat.	
	15	4	CS	4.2	5.0	Moist, gray, medium SAND (SW) Hard, moist, gray Silty CLAY (CL-ML); trace sand and fine to medium gravel	Lacustrine Till
	20	5	cs	4.5	5.0	Hard, moist, gray Silty CLAY (CL-ML); trace sand and fine gravelone 3-inch shale fragment. Hard, dry to moist gray Silty CLAY; trace sand and fine gravel	
	<b>2</b> 5	6	cs	4.5	5.0		
	30	7	cs	4.5	5.0	001115 (04.0.1)	Till
	35	8	cs		4.6	Gray SHALE (31.0 ft.) Highly weathered, thinly bedded, blocky to fractured, soft Weathered, thinly bedded, blocky to fractured, soft	Bedrock
	40	9	cs		1.6	6-inch very soft, highly weathered zonetwo 1-inch, very soft, highly weathered zones	End of boring at 40.1 ft.
<u> </u>			1	FIFI (		LOG OF BORING FBMW-13D ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL D	ATE:		V 199			FIGURE No.: 18

ELEVATION TOP OF PISER PIPE: 628.00		LOCATION: Detrex DRILLING FIRM: Mateco Drilling Company DRILLING RIG TYPE: CME 750  DATE DRILLED: 15 June 1990 INSPECTOR: N. Bigman								
GROUND ELEVATION: 625.95	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS			
	5 					See log of FBMW-13D for description of stratigraphy.	COMMENTS			
			*******	CICLO		LOG OF BORING FBMW-13S				
CHECKED BY: J	CL D	ATE:		V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 19			

ELEVATION TOP OF RISER PIPE: 642.90	DRIL	LOCATION: Acme Scrap Metals  DRILLING FIRM: Mateco Drilling Company DRILLING RIG TYPE: CME 750  DATE DRILLED: 16, 17 June 1990 INSPECTOR: S. Basham, N. Bigman										
GROUND ELEVATION: 639.90	DEPTH (Ft)	SMPL NO.	ŤŶΡΕ	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS					
		1	cs		3.6	Moist, brown SILT (ML); trace roots, some sand Loose, moist, light brown, fine SAND	Lacustrine					
	5	2	cs		4.7	Stiff, moist to wet, mottled tan to rust CLAY (CL) Wet, red-brown to tan SILT (ML) Stiff, moist, red-brown to rust, Silty CLAY (ML-CL) Loose, wet, brown, fine SAND and SILT (SW-SM)						
	10	3	CS	4.5	4.5	Hard, moist, medium gray Silty CLAY (CL-ML); some poorly sorted shale gravel	Lacustrine Till					
	15	4	CS	4.5	4.5							
	20	5	cs	4.5	4.0							
	25	6	cs		5.0	granite cobble						
	30	7	cs	***************************************	5.0	Hard, moist, medium gray Silty CLAY; trace sand, trace to few gravel						
	35	8	cs			Gray SHALE (33.1 ft.) Very soft, highly weathered, blocky, thin bedded Weathered to highly weathered, very soft to soft, fractured to blocky, thin bedded, gray SHALE	Bedrock, RQD=0 RQD=35%					
==	40	9	cs		3.5		RQD=57%					
				FIELD		LOG OF BORING FBMW-14D ROOK SOURCE CONTROL - ASHTABULA, OHIO						
CHECKED BY: J	CL D/	ATE:		OV 199		PROJECT No.: 86C3609D-230	FIGURE No.: 20					

Page 2 of 2	DEPTH						
	(Ft)			B/Ft	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						Gray SHALE	<u> </u>
▋▗▕▃▋▗		-				Slightly weathered, moderately soft, fractured,	
	<u> </u>					thin bedded End of boring at 42.5 feet	-
	45					2.10 of 50.111g at 42.0 100t	i
						·	
	<u> </u>						
	50						
	55						
		1					
	<b> </b> —						
	60	-					
	—						
	65			ļ			
							1
	70						
	70						
				İ			<b> </b>
	75						
				l	1		1
	80						1
					- 1		
	85						]
						LOG OF BORING FBMW-14D	
CHECKED BY: J	ici Io	ATC.	1 81/	FIELD OV 199	OS BF	ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	TELOUISE N
OFFICINED BY.	UL D	AIE.	1 140	JV 195	~ ∣	FROJECT NO.; 86C3609D-230	FIGURE No.: 20

ELEVATION TOP OF RISER PIPE: 629.32	LOCA DRIL DRIL	ATIC	N: S G FIF	CM F RM: N G TYF	Plant : lateco PE: C	2 DATE DRILLE o Drilling Company INSPECT ME HT75	D: 17 July 1990 OR: S. Basham
GROUND ELEVATION: 627.1	DEPTH (Ft)	SMPL		P.P.			COMMENTS
						See log of FBMW-15D for description of stratigraphy.	
CHECKED BY:	JCL	DATE	: 1 N	FIEL OV 19		PROJECT No.: 86C3609D-230	FIGURE No.: 23

ELEVATION TOP OF RISER PIPE: 638.59	DRIL	LIN	G FII	Ikem RM: M G TY!	latec		ED: 14 July 1990 TOR: B. Schmidt	7
GROUND ELEVATION: 636.1	DEPTH (Ft)			B/FT.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	
		1	SS	12	1.7	Stiff, moist, brown and tan CLAY (CL)	Lacustrine	1
		2	SS	10	2.0	becomes less silty with depth	OVA=BG OVA=BG	
	5	3	SS	12	2.0		OVA=BG	
		4	SS	14	2.0	Stiff,moist,bwn&tan CLAY;vertical fractures and iron stainingStiff, moist, gray CLAY (CL)	OVA=BG	l
	10	5	SS	11	2.0		OVA=BG	l
		6	SS	11	2.0	12-inches with increased silt content	OVA=BG	
		7	SS	9	2.0	Firm, moist, gray CLAY	OVA=BG	
	15	8	SS	8	1.8		OVA=BG	
		9	SS	11	2.0	Stiff, moist, gray CLAY; with silt layers, some red staining	OVA=BG	
	20	10	SS	8	1.3	Firm, moist, gray CLAY; silt layers, trace gravel, some red staining	OVA=BG	
		11	SS	14	2.0	Stiff, moist, gray CLAY; silt layers, trace gravel, some red staining	OVA=BG	Ì
	_	12	SS	11	2.0	iron nodule	OVA=BG	
	25	13	SS	14	1.8	gravel increases, staining decreases	OVA=BG	
		14	SS	8		Stiff, moist, gray CLAY; with coarse gravel, some red staining	OVA=BG Lacustrine	
	30	15	SS	14	2.0	Stiff, moist to dry gray Silty CLAY (CL-ML); with shale fragments, trace angular gravel	Till OVA=100	Ì
		16	SS	27		Very stiff, moist to dry gray Silty CLAY; with	OVA=400	
		17 18	SS SS	29 40	1.0	shale fragments, trace angular gravel	OVA=360	
		19	SS	39		Hard, moist to dry gray Silty CLAY; with shale fragments, trace angular gravel increasing with depth	OVA=670	
		20	SS	37	2.0	απο συρεί	OVA=600	
	40						OVA=1000	
				FIELD		LOG OF BORING FBMW-16D ROOK SOURCE CONTROL - ASHTABULA, OHIO		
CHECKED BY: JO	CL D	ATE:		V 199		PROJECT No.: 86C3609D-230	FIGURE No.: 24	

Page 2 of 2	DEPTH	SMPL	TVDE	B/Ft	BEC	DESCRIPTION OF STRATIGRAPHY	COMMENTS				
			l								
	(Ft)	21 22 23 24	SS		2.0	Gray SHALE (43.6 ft.) Thin bedded, with some highly weathered beds  Bottom of boring at 53.0 feet.	Bedrock RQD=0% RQD=7%,0VA=1000 RQD=0%				
	85 LOC OF BORING FRAW, 16D										
				FIEL	DS BI	LOG OF BORING FBMW-16D ROOK SOURCE CONTROL - ASHTABULA, OHIO					
CHECKED BY:	JCL D	ATE	: 1 NO	OV 199	90	PROJECT No.: 86C3609D-230	FIGURE No.: 24				

ELEVATION TOP OF RISER PIPE: 637.88	LOCAT DRILLI DRILLI	ING FI	RM: N	Aatec		ED: 16 July 1990 CTOR: N. Bigman
GROUND ELEVATION: 636.1	DEPTH si (Ft)	MPL NO, TŶPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
					See log of FBMW-16D for description of stratigraphy.	
CHECKED BY: Jo	CL DAT	ΓΕ: 1 NO		S BF	ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 25

ELEVATION TOP OF RISER PIPE: 640.33	LOCA DRIL DRIL	LING	i FIF	RM: M	latec	DATE DRILLED: 2 D Drilling Company INSPEC ME 750	7-29 June 1990 TOR: S. Shubat
griound Elevation: 637.63	DEPTH (Ft)	SMPL NO.	ΤΎΡΕ	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	cs	1.5 0.7	3.4	Firm to stiff, moist, brown Silty CLAY (CL); trace roots and coarse sand	Fill
	5	2	cs	1.5 3.7	4.6	Stiff,moist,brown w/ gray mottling,Sitty CLAY;w/elit, trace roots Very stiff, moist, brown with trace brown mottling and iron staining, CLAY (CL); some medium sand, increasing silt content with depth	Fill Lacustrine
	10	3	CS	2.5 2.5	4.8	Very stiff,moist,brown CLAY;w/silt,some sand Very stiff, moist gray with iron stain mottling, Silty CLAY (CL-ML); some fine sand, trace medium sand	Lacustrine Till
	15	4	cs	2.5	4.5		
	20					No samples retrieved due to loss of sample in boring.	
	<u>25</u>	5	cs	2.5 4.5	5.0	Very stiff, moist, gray Silty CLAY (CL-ML); some fine sand Hard, dry, gray Silty CLAY (CL-ML); some fine sand	
	30		CS NX	4.5	1.9	Hard, dry, gray Silty CLAY (CL-ML); some fine sand, trace shale fragmentsboulder  Gray SHALE (32.4 ft.)	Till Bedrock
	35	8	NX			Unweathered, thin bedded, with white and black beds and pyrite flakes Unweathered, thin bedded, with white and black beds, chert beds and pyrite flakes; deformed	
==	40					LOG OF BORING FBMW-17D	
CHECKED BY: JO	ci D	ATE:		FIELD V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	EIGHDE No : 26
OFFICINED BT: JO	) U	NIE;	INC	A 133	· .	FROJECT NO.: 000-30090-230	FIGURE No.: 26

Page 2 of 2	DEPTH		T		T		
-aye 2 01 2	(Ft)			B/Ft	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
==						Gray SHALE	1
==			,.			Unweathered, thin bedded, with white and black	
						beds, chert beds, and pyrite flakes; deformed	,
	<del></del>		ļ			End of boring at 42.7 feet.	
	45						
İ	<b> </b> —						
	<b> </b>						
	50						
	l						
	l —	1					
	55						
	l i						
	60						
	- 60						
							,
	65						1
							İ
				}			
	70						
	<del></del>						
	75	i		İ			
							ŀ
					1		
	80						
					İ		
				}			
							i
	85						
	- 55					LOG OF BORING FBMW-17D	
				FIELD	OS BF	ROOK SOURCE CONTROL - ASHTABULA, OHIO	1
CHECKED BY: J	CL D	ATE:	1 NC	V 199	0		FIGURE No.: 26

ELEVATION TOP OF RISER PIPE: 639.91	LOCAT DRILLI DRILLI	NG FI	RM: M	tateco		D: 29 June 1990 TOR: S. Shubat				
GROUND ELEVATION: 637.63	DEPTH si	MPL 10. TŸPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS				
					See log of FBMW-17D for description of stratigraphy.					
	5									
	10									
==	15									
	20									
	25									
	30									
	35									
	40									
	LOG OF BORING FBMW-17S FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO									
CHECKED BY: J	CL DAT	ΓΕ: 1 NO		_		FIGURE No.: 27				

ELEVATION TOP OF PASER PIPE: 630.99	DRIL	LIN	3 FII	Vyger RM: N G TYI	<b>Aatec</b>		ED: 20 June 1990 ECTOR: S. Shubat			
GROUND ELEVATION: 628.49	DEPTH (Ft)		1 -	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS			
	5	2	cs	4.5 4.5	5.0	Stiff, moist, brown to dark brown Sandy CLAY (CL); trace roots and vegetation near surface6-inch sand and slag layer Hard, dry to moist, gray, Silty CLAY (CL-ML); trace sand and gravelbecomes dry	Fill OVA=BG Fill Till			
	10	3	cs	4.5	5.0	1.5-inch shale fragment				
	15	4	cs	4.5	5.0	2-inch spherical quartzite cobble	OVA=BG			
	20	5	cs	4.5	3.0	Gray SHALE (20.3 ft.)	Till Bedrock			
==		6	cs		2.0	Hard, blocky, slightly weathered, thin bedded12-inch soft zone	Dod Ook			
	25	7	cs		5.0	6-inch soft zone				
	30	8	CS		1.0	End of boring at 30 feet	_			
	35									
	40									
	LOG OF BORING FBMW–18D  FIELDS BROOK SOURCE CONTROL – ASHTABULA, OHIO									
CHECKED BY: J	CL D	ATE:	1 N	OV 199	90	PROJECT No.: 86C3609D-230	FIGURE No.: 28			

DEPTH MAIN TYPE P.P. REC DESCRIPTION OF STRATIGRAPHY COMMENTS  See log of FBMW-18D for description of stratigraphy.  See log of FBMW-18D for description of stratigraphy.	ELEVATION TOP OF RISER PIPE: 630.48	LOCATION: Vygen DRILLING FIRM: Mateco Drilling Company DRILLING RIG TYPE: CME 750 DRILLING RIG TYPE: CME 750 DATE DRILLED: 26 June 19 INSPECTOR: S. Shull								
See log of FBMW-18D for description of stratigraphy.	ELEVATION:	DEPTH	SMPL					COMMENTS		
							stratigraphy.			
CHECKED BY: JCL DATE: 1 NOV 1990 PROJECT No.: 86C3609D-230 FIGURE No.: 29	CHECKED BY:	JCL I	DATE	: 1 N			ROOK SOURCE CONTROL - ASHTABULA, OHIO	FIGURE No.: 29		

ELEVATION TOP OF RISER PIPE: 645.60	DRIL	LIN	3 FII	SCM F RM: M G TY	Matec		D: 14 July 1990 OR: S. Basham	7			
GROUND ELEVATION: 643.1	DEPTH (Ft)	1	1	B/FT.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS				
		1	SS	8	2.0	Loose, orange Silty SAND (SM)	Fill	1			
			-	10		Loose, brown Silty SAND; trace gravel		ı			
		2	SS	12	2.2	Loose,orng w/red-orng stain Silty SAND;trace grvl3-inch black sand lense		ı			
	5	3	SS	6	2.0	Loose, moist, orange-brown Silty SAND		ı			
						Loose, wet, orange-brown Silty SAND		ı			
	4 SS 4 2.0 Very loose, wet, orange-brown Silty SAND Fill Firm, moist, gray CLAY (CL); trace grayel:										
	Firm, moist, gray CLAY (CL); trace gravel; Lacustrine										
	5 SS 7 1.6 increases to some gravel with depth										
		6	SS	11	2.2		OVA≃5	ı			
		_									
		7	SS	9	1.8		OVA=25	1			
	15	8	SS	8	1.9		OVA=25				
							Lacustrine	l			
		9	SS	22	2.1	Very stiff, moist to dry, gray Silty CLAY (CL-ML);	Till	1			
		40	-	40		some fine to medium gravel	OVA=20	ı			
	20	10	SS	40	2.2	3-inch thick shale cobble	OVA=70	•			
		11	SS	30	2.2	o-mon thick state copple	OVA=5				
							5 · / - 5	L			
		12	SS	22	1.9						
	25	13	SS	27	2.2						
<b>                                     </b>		13	33	21	2.2						
		14	SS	>88	1.7						
							Till				
	30	15	NX		•		Bedrock	ľ			
<del>==</del>		16	NX			Weathered, thin bedded Unweathered, thin bedded, gray SHALE		ı			
				}		omodinorod, film bodded, gray of face		l			
==								ĺ			
<b>                                     </b>	35										
		17	NX		1.5			1			
		.,		1				Į			
				ł		End of boring at 36.8 feet.		ı			
]	Water encountered at 4.9 feet.										
LOG OF BORING FBMW-19D FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO											
CHECKED BY: JO	CL D/	ATE:		V 199			FIGURE No.: 30				
							, TO OTHE 110 30				

ELEVATION TOP OF RISER PIPE: 645.12	LOC/ DRIL DRIL	LING	FIF	RM: N	atec	DATE DRILLE D Drilling Company INSPECT ME 750	D: 15 July 1990 OR: S. Basham			
GROUND ELEVATION: 643.1	DEPTH (Ft)		TÝPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS			
ELEVATION:			TYPE	P.P.	REC	DESCRIPTION OF STRATIGRAPHY  See log of FBMW-19D for description of stratigraphy.	COMMENTS			
	LOG OF BORING FBMW-19S									
	- <u>-</u>					ROOK SOURCE CONTROL ~ ASHTABULA, OHIO				
CHECKED BY: J	CL C	ATE:	1 NO	OV 199	ю	PROJECT No.: 86C3609D-230	FIGURE No.: 31			

	OF RISE	ION TOP R PIPE: 1.39	DRIL	LIN	3 FIF	RM: N	Meta latec PE: C		D: 23 July 1990 OR: N. Bigman		
	GROUND ELEVATI 638	ON:	DEPTH (Ft)		1	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS		
				1	SS	11	1.9	Stiff, moist, dark brown, Sandy CLAY (CL); trace	Lacustrine		
				2	SS	7	1 8	roots & organic material  Medium dense, lt. brown SAND and GRAVEL (SP)	OVA=BG		
				-	00	'	1.0	Firm, moist, it brwn & gry Sandy CLAY (CL)			
			5	3	SS	10	2.0	Medium dense, moist, light brown, fine SAND (SW)			
				4	SS	14	2.0	Stiff, dry to moist, med. brown SILT (ML); some			
				_				rust colored, fine sand partings; varved			
			10	5	SS	14	2.0	Stiff, dry to moist, gray SILT; with few sand partings, trace sand seams			
				6	SS	12	2.0	Med. dense, moist, gry, fine SAND (SW), trace iron	OVA=BG		
				_	00	40		stainingbecomes wet, without staining	<b>)</b>		
				7	SS	19	2.0	Stiff, dry to moist, gray SILT (ML); some sand8-inch moist, gray clay layer			
			15	8	SS	10	0.1	8-inch moist to wet, gray, fine sand			
				9	SS	4.0		Stiff,dry to moist,de-tinted gray SILT; some sand	Lacustrine		
				9	55	16	2.0	Very stiff, dry to moist, gray Silty CLAY (CL-ML); trace sand and fine to medium gravel	Till		
				10	SS	13	2.0	and said and the to mediant grave.			
			20	11	SS	18	2.0	Very stiff, dry to moist, gray Silty CLAY (CL-ML);	Ţ		
						.0	2.0	few sand and trace fine to medium gravel			
				12	SS	15	2.0	_			
			25	13	SS	11	2.0	1-inch shale fragment; Very stiff, dry to moist,			
					-	25		gray Silty CLAY; trace sand and gravel			
				14	SS	25	1.2		j		
			30	15	SS	25	2.0		1		
			30	16	ss	21	2.0	2-inch layer of shale gravel (broken cobble) Very stiff, dry to moist, gray Silty CLAY (CL-ML);			
								trace sand and few fine to medium gravel			
				17	SS	28	2.0				
			35	18	SS	31		Very stiff, dry, gray Silty CLAY (CL-ML); trace	į		
				19	ss	32	2.0	sand and few fine to medium gravel			
			40	20	SS	30	2.0				
	702	0.0000					1	LOG OF BORING FBMW-20D			
	LOG OF BORING FBMW-20D  FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO										
СН	ECKE	BY: JO	CL D	ATE:	1 NO	V 199	0	PROJECT No.: 86C3609D-230	FIGURE No.: 32		

Page 2 of 2	DEPTH	SMPL				:					
	(Ft)	NO.	TYPE	B/Ft		DESCRIPTION OF STRATIGRAPHY	COMMENTS				
		21	SS	>65	2.0	Very stiff, dry, gray Silty CLAY (CL-ML); trace	Till				
		22	SS	>150	2.0	sand, few fine to medium gravel Gray SHALE (42.5 ft.)	Bedrock				
==						Unweathered, blocky, thin bedded, gray and dark					
==	45	23	NX		1.9	gray beds	RQD=0%				
==		24	NX		4.7	Unweathered, blocky to fractured, thin bedded	RQD=25%				
==						SHALE; gray and dark gray beds					
==	50										
End of boring at 51 feet.											
	End of boring at 51 feet.  Water encountered at 11.0 feet										
	55										
	33										
	60										
	65										
]		1									
	70										
	75										
	80										
85											
LOG OF BORING FBMW-20D											
	FIELDS BROOK SOURCE CONTROL - ASHTABULA, OHIO										
CHECKED BY: J	CL D	ATE	1 NO	OV 199	ю	PROJECT No.: 86C3609D-230	FIGURE No.: 32				

ELEVATION TOP OF RISER PIPE: 640.72	DRIL	LIN	3 FII	RM: N	Meta latec PE: C	als DATE DRILL o Drilling Company INSPECTOR: N. Big ME 750	ED: 25 July 1990 gman, B. Schmidt	
GROUND ELEVATION: 638.9	DEPTH (Ft)	SMPL NO.		P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS	1
						See log of FBMW-20D for description of stratigraphy.		
CHECKED BY: JC	L DA	ATE:		FIELD V 199	SBF	OOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 33	

ELEVATION TOP OF RISER PIPE: 641.91	LOC/ DRIL DRIL	LINC	FIF	RM: N	latec		D: 12 July 1990 OR: S. Basham
GROUND ELEVATION: 639.21	DEPTH (Ft)	1	TŸPE	B/FT	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	SS	7	1.4	Firm, moist, gry w/ iron staining CLAY (CL); trace	Lacustrine
						orange, orang-bwn, lt. bwn and iron stained layers	
		2	SS	10	1.9	Stiff CLAY; trace gravel	
		3	SS	11	1.9	Stiff CLAY; some silt lenses Stiff CLAY; some silt/fine sand	
		"	33	11	1.5	Still OLA (, Solite Silvinie Salid	
	—	4	SS	11	2.3	Stiff CLAY; trace gravel and silty sand lenses	
		5	SS	15	2.0	Stiff gray CLAY; vertical iron staining, trace	
	10			40		shale gravel	
		6	SS	12	2.2		
		7	SS	16	2.2	Very stiff gray CLAY; vertical iron staining, trace	
		'	J			shale gravelshale cobble	
	15	8	SS	19	2.1		OVA=2.0
							Lacustrine
		9	SS	33	2.3	Hard, moist to dry, gray Silty CLAY (CL-ML);	Till
		10	SS	30	2.1	some shale gravel	
	20	10	33	30	۱ . ــ		
		11	SS	33	2.1		
		12	SS	>70	1.5		Till
	-05	10	110			Gray SHALE (23.0 ft.)	Bedrock
	25		NQ NQ		1.2 5.1	Highly weathered, blocky, thin bedded	
==		'	110		3.1		
==		1					
==							
==	30	1					
==		15	NQ		1.5		
						End of boring at 31.6 feet.	
	35						
	40						
		<u> </u>		C.C	20.5	LOG OF BORING FBMW-21D	
	CL C	DATE				ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 34

Woodward-Clyde Consultants

ELEVATION TOP OF PISER PIPE: 641.52	DRIL	LIN	3 FIF	Elkem RM: N G TYI	fatec		ED: 13 July 1990 CTOR: S. Basham
GROUND ELEVATION: 639.21	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						LOG OF BORING FBMW-21S	
CHECKED BY: J	CL D	ATE:		V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 35

ELEVATION TOP OF RISER PIPE: 641.46	DRIL	LIN	3 FIF		latec		D: 2,3 July 1990 TOR: S. Shubat
GROUND ELEVATION: 639.26	DEPTH (FI)		1	B/FT	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	SS		2.0	Soft, moist, brown, Silty CLAY (CL); roots,	Lacustrine
						some fine sand	OVA=BG
		2	SS		0.1	Soft, moist, brown and gray mottled, CLAY (CL); roots	8.0=AVOO
	5	3	SS	3	1.4	Soft,moist,gray mottled,CLAY;roots & trace fine sa Very loose, wet, brown SILT and fine SAND (SM)	OVA=1.51
		4	SS	17	2.0	Very stiff,moist,bwn,iron stained Silty CLAY; (CL)	OVA=0.2
			V. stiff,moist,gry,iron stained Silty CLAY;some sand				
	10	5	SS	9	2.0	Stiff,moist,gry,iron stained Silty CLAY;some sand	OVA=0.6
		6	SS	7	1.9	Stiff, moist, gray CLAY (CL); trace fine sand	OVA=1.2
		7	SS	9	2.0		OVA=18
	15	8	SS	9	1.8		OVA=2.0
	l —		-				Lacustrine
		9	SS	18	2.0	Very stiff, moist, gray Silty CLAY (CL-ML); trace fine sand	Till OVA=50.0
		10	SS	28	2.0	Inte Sand	OVA=50.0
	20	'		20	2.0		O 7 A = 30.0
		11	SS	48	2.0	Hard, moist, gray Silty CLAY; trace fine sand	OVA=55.0
		12	SS	31	2.0		OVA=90.0
	25	13	SS	29	2.0	Very stiff, moist, gray Silty CLAY; trace fine sand	
		14	SS	52	2.0	Hard, moist, gray Silty CLAY; trace fine sand	
		1.5		-7.5	0.0		
	30	15	SS	75	2.0		Till
	<u></u> -	16	NQ		1.3	Grav SHALE (29.8 ft.)	Bedrock
						Highly weathered, thinly bedded, with some black	RQD=0%
==						bedsbecomes unweathered, with cone in cone	
==						structures	
==	35						
==		17	NQ		1.3		RQD=0%
==							
		18	NQ		2.1	End of boring at 40 feet.	RQD=10%
	40	.				Water encountered at 4.9 feet.	100
	1	٠	Ļ			LOG OF BORING FBMW-24D	
				FIELI	DS BI	ROOK SOURCE CONTROL - ASHTABULA, OHIO	
ECKED BY:	JCL E	ATE	1 NO	OV 199	90	PROJECT No.: 86C3609D-230	FIGURE No.: 36

ELEVATION TOP OF RISER PIPE: 640.90	LOCA DRILI DRILI	ATIC LINC	N: F G FIF G RIC	Plastic RM: N G TYI	colors Mateco PE: C	27112 = 1111	LED: 3 July 1990 CTOR: S. Shubat
GROUND ELEVATION: 639.26	DEPTH (Ft)		1 1	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
639.26						See log of FBMW-24D for description of stratigraphy.	
CHECKED BY: JO	CL DA	NTE:		FIELD V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 37

ELEVATION TOP OF RISER PIPE: 645.18	LOCA DRIL DRIL	LING	FIF	RM: N	lateco	1 DATE DRILLE D Drilling Company INSPECT ME HT75	D: 10 July 1990 OR: S. Basham
GROUND ELEVATION: 642.8	DEPTH (Ft)	1	TYPE	B/FT	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
		1	SS	17	0.9	Brown TOPSOIL	Lacustrine
		2	SS	13	2.3	Stiff,moist/dry gray w/ orange CLAY (CL); tr. grav.	
	5	3	SS	10	1.5	Stiff, moist, yel-bwn w/ blk mottling Sandy CLAY Stiff, moist, brown CLAY and sand; tr. f. gravel	
		4	SS	15	2.1	Stiff, brown to gray, with trace black and iron-stained partings CLAY and sand; trace fine	
	10	5	SS	12	2.2	gravelthree layers of yellow sand	
		6	SS	20	2.2	Very stiff CLAY and sand; trace fine gravel Very stiff Sandy CLAY; trace fine gravel	Lacustrine
		7	SS	21	2.1	Very stiff, moist to dry, gray Silty CLAY (CL-ML); trace fine gravel	Till
	15	8	SS	29	2.2	ado mo grava	
		9	SS	26	2.2		
	20	10	SS	67	1.8	Hard, moist to dry, gray Silty CLAY; trace f. gravel Gray SHALE (19.0 ft.)	Till Bedrock
		11	SS NQ	>55	1.3 3.5	Highly weathered, blocky, thin bedded	
	25		NQ		5.0		
==							
	30					End of boring at 28.5 feet.	
	35						
					Ĵ		
	40						
				EIE''		LOG OF BORING FBMW-25D	
CHECKED BY: J	CL D	ATE:		OV 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 38

GROUND			G RIG	G TY	PE: C	D Drilling Company INSPEC ME HT75	ED: 11 July 1990 TOR: S. Basham
ELEVATION: 642.8	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						See log of FBMW-25D for description of stratigraphy.	
CHECKED BY: J	CL D	ATE:		FIELD V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 39

	ELEVATION TOP OF RISER PIPE: 640.74	DRIL	LIN	3 FII		fatec	o Drilling Company INSPECT ME HT75	D: 25 July 19 OR: S. Basha
	ground elevation: 638.3	DEPTH (Ft)			B/FT	REC	DESCRIPTION OF STRATIGRAPHY	COMMENT
			1	SS	7	1.9	Firm, moist to dry, brown with orange and gray mottling, CLAY (CL)	Lacustrine
			2	SS	5	2.2	Firm, moist, gray with iron staining CLAY	
		5	3	SS	5	2.2	Firm, moist, gry w/ iron staining Silty CLAY (CL)	
			4	SS	10	2.0	Stiff, wet, dark brown Silty CLAY Stiff, wet, gray Silty CLAY	
		10	5	SS	4	2.2	Interbed., soft, moist, gray, CLAY and Silty CLAY (CL)	
			6	SS	6	2.2	interbedded, firm, moist, gray, CLAY and Silty CLAY5-inch orange silty sand layer .	
			7	SS	7	2.0	Firm, moist, gray CLAY (CL); trace gravel	
		15	8	SS	4	1.9	Soft, moist, gray CLAY; trace gravel	
			9	SS	7	1.5	Firm, moist, gray CLAY; trace gravel	5
		20	10	SS	3	2.0	Soft, moist, gray CLAY; trace gravel	
			11	SS	15	2.2	Stiff, moist, gray CLAY; trace gravel Stiff, moist to dry, gray Silty CLAY (CL-ML); some	Lacustrine Till
			12	SS	17	1.8	gravelbecomes very stiff	ļ · ···
	1   1	25	13	SS	19	2.0		
			14	SS	32	2.2	Hard, moist to dry, gray Silty CLAY; some gravel	
		30	15	SS	38	2.0		
			16	SS	27		Very stiff, moist to dry, gray Silty CLAY; some gravel	
		_	17	SS	40		Hard, moist to dry, gray Silty CLAY; some gravel	
		35		SS NQ	>69	1.0 5.0	Gray SHALE (35.0 ft.)	Till Bedrock
	==	_				J. J	Highly weathered, thin bedded Slightly weathered, thin bedded, gray SHALE	
Į	==	40						
					FIEL	OS BE	LOG OF BORING FBMW-26D ROOK SOURCE CONTROL - ASHTABULA, OHIO	
ı	CHECKED BY: J	ICL D	ATE:		OV 199		PROJECT No.: 86C3609D-230	FIGURE No.: 4

-

Page 2 of 2	DEPTH	SMPL						7
	(Ft)		<u> </u>	B/Ft	l	<u></u>	COMMENTS	
		20	NQ		5.0	Gray SHALE Slightly weathered, thin bedded		
==		-	-				•	
	45							
						End of boring at 45.0 feet.		ı
						Water encountered at 5.5 feet.		ı
								ı
	50							
								l
	55							ı
	33							1
								1
	60							
								l
	65							
	05							
					Ì			
	70							
<u> </u>								
								$\sim$
	75							
1	75							
			ļ					
					-	•		
	80							
	85					OC OF BODING FRAME COD		
			F	FIELD	S BR	LOG OF BORING FBMW-26D OOK SOURCE CONTROL - ASHTABULA, OHIO	, J	ł
CHECKED BY: JO	CL DA	TE:	1 NO	V 1990	) [	PROJECT No.: 86C3609D-230	FIGURE No.: 40	l

ELEVATION TOP OF RIBER PIPE: 640.33	LOCA DRIL DRIL	ATIC LINC	N: L	inche RM: M G TYI	m fateci PE: C	DATE DRILLE o Drilling Company INSPECT ME HT75	D: 26 July 1990 OR: S. Basham
ground ELEVATION: 638.3	DEPTH (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						See log of FBMW-26D for description of stratigraphy.	
				FIEL	os Br	LOG OF BORING FBMW-26S ROOK SOURCE CONTROL - ASHTABULA, OHIO	
CHECKED BY: J	CL D	ATE:		V 199		PROJECT No.: 86C3609D-230	FIGURE No.: 41

DEPTH		1 :	P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
3.20	1	cs	4.5	3.6	Hard, dry, gray, brown and iron stained mottled, Silty CLAY (CL); roots, worms, magnesium oxide flakes	Fill
5	2	cs	4.5	3.4	Moist Silty CLAY; roots and coarse gravel	Fill
					Hard, moist, gray, brown and olive green mottled, Silty CLAY (CL); some coarse shale sand	Lacustrine
10	3	cs	4.5	3.8		Lacustrine
					Gray Shale (9.6 ft.) Highly weathered, thin bedded	Bedrock
15	4	NX		1.0	Unweathered, thin bedded, gray SHALE	
					End of boring at 18.3 feet.	
20					Water encountered at 9.6 feet.	
				j		
				1		
25			ĺ			
30						
]						
35						
40						

Woodward-Clyde Consultants

ELEVATION TOP OF RISER PIPE: 645.02	DRII	LLING	3 FIF	RM: M	latec	K ROAD AT R.R. TRACKS DATE DRILL o Drilling Company INSPEC ME 750	ED: 1 July 1990 TOR: S. Shubat
ground Elevation: 643.2	DEPTI (Ft)			P.P.	REC	DESCRIPTION OF STRATIGRAPHY	COMMENTS
						See log of FBMW-28D for description of stratigraphy.	
CHECKED BY: J	CL [	DATE:		FIELD V 199		ROOK SOURCE CONTROL - ASHTABULA, OHIO PROJECT No.: 86C3609D-230	FIGURE No.: 43

TEST BORING LOG AWARE BORING NO. FBMW-65 INCORPORATED 314 SHEET NO 1 01 1 PROJECT NO. 6726 PROJECT: Hydroseologic Lovestischers
CLIENT: PMT Company - Extrason Plant
CONTRACTOR: Matter - Associety Fic
RISER INTAKE ORIL EQUIPMENT . C EQUIPMENT: CME 550

DRILLING METHOD: H. Now 5th outer

CASING SAMPLER CORE TUBE GROUND WELL PROTESS
ELEV.: (37).2 (33.2 TYPE Stainless Stanless DATE STARTED: 9-2-77 DIAMETER TYPE DATE COMPLETED: 9-3-8:
DRILLER: Jim Greens
INSPECTOR: Bacry Branch COUPLING Flysh Flush DIAM WEIGHT WELL CONSTRUCTION SAMPLE DEPTH BLOWS PER 6 inches CLASSIFICATION REMARKS NO. TYPE 0 No samples collected; For Cement/Bentonile Grout -2"strinkes steel Casing Classification, see Log For Well 305 - End boing 22'

RU	IC		F			TE	ST B	ORIN	G LO	G	BORING NO.
incor							_	1-61			305
PROJEC			scola	ic 1	nvestigati	177	· NP(W	/ · · · · · · · · · · · · · · · · · · ·			SHEET NO 1 of 1
CLIENT	: (20	ήT. C	.~~6	0 F	xtrusium (	Chart _	EQUIPMEN	·			PROJECT NO. 6726
CONTRAC	CTOR	. <u>(Mc</u>	SER.	dod f	ssociales NTAKE		ING METH		GROUND WELL PROTOSO		
TYPE			cles		19101055		CASING	SAMPLER	CORE	TUBE	ELEV.: 610.3 633.1
DIAMETE	R	2	if		2"	TYPE		Berrel	<b> </b> _		DATE STARTED: 4-14-27
COUPLIN		-Fu			-Tush	DIAM	<del> </del>	_3"	ļ	<del> </del>	DATE COMPLETED: 4-14-37 DRILLER: Chuck Harriss
CONSTR	RUCTIO	N E		SAM	PLE	FALL	<u> </u>				INSPECTOR: BACKY BEAUTE
[F	7]	DEPTH	NO.	TYPE	BLOWS PER 6 inches		CLA	SSIFICA	TION		REMARKS
<u></u>	-++-	-+0	-	<del>                                     </del>			7.5	(SOIL			
		Ī				)]		AL TILL			j
		-	1	Grap		3′_ <sup>M</sup> •	Tria oran	و-منعاط <i>-</i>	- SICT		
		-5	2	Grab		5' Me	d brown Si Sand, Fras,	ct with (	Clay, lith	le Shele	Vertical fractures with Oxidized surfaces
		ŀ					to slight				
Cement/Bentonite Grout		·	3	Grab		9'					
- Cement/Bentonite Go. C. C. Chi. Ilong School Co.	5	+10	1			(M	led gray				Vertical fractives 9-11'
ا عُدُ	5	ŀ						fragments <		hved	with oxidized surfaces
ا کھے ا	3	· [					Shale,	Stightly	Wels L'		
T 3	양발	-15	4	Greb		15'					
3 1	رة ع	F	}								
)   (	Sentonite Pellet Sea	ţ					Med Sray	CLAV II	 !!a \$!+	<del></del>	
	1 3	-2	5	GAB		മം'	Fracture	d shale.	tragment	, and	Soil "pills" while drilled
			6	Grab		22'	gende teion	to tot	. Stylty		
Î,		-				~	led gray Shale. G	•		red	
Filter Pack	1 kgs	-2:	5				Shale ! G	rades to	weather	rd	
ا نز ا	2"54mkss	-	7	Grab		27.5	<del></del>	elic bedð Rock	<u>5.500</u>		27.0
4 =	1 2 3	<u> </u>	1			ļļ.			1 1		
<del> </del>	نها	[-3<				G	ray SHA	CE, CIA	A 204	Sary	-End baring 29.5'
j		-									1
		-									
		[		1							
		-3	5								
]		Ţ									
		}									
		-4									
		F	7								
		}									
		Ţ		}							
}		[a	s								
L				<u> </u>		ll					

INCOAR INCOAR	RRE	F	T BORING		NO. RM.	<del> </del>		
PROJECT: KCK	A FACILITY	INVESTIGA	TION	PROJECT NO. 6/20				
ILIENT: RMI	SOBIUM PLA	NT	·	24.451.15				
0.01	LING DATA				NG METHODS CORE			
CONTRACTOR: Pa	ENNIVL VANIA D	RILLING CO.		SAMPLER				
	RNIE GOLL	HUP	TYPE		S coat spect TUBE			
DRILLER: BU	KNIB W	OD AULES	DIAMETER		4"			
EQUIPMENT: AC	71/4/1		OTHER			Inpot co		
METHOD:	LL CONSTRUCT	ION	WELL DEV	ELOPMENT	GROUND			
W		INTAKE	METHOD: Com.	PRESSED AIR	ELEV 641.2	643.61		
	RISER		DURATION: /	hr.	DATE STARTED	10-13 -85		
MATERIAL	PVC	PYC	YIELD:		DATE COMPLET	ED: 10-17 - 88		
DIAMETER	2"	THEADED	OTHER: at a clea	1	INSPECTOR: R	OB QUIDEY		
COUPLING	THECADED							
WELL CONSTRUCTION	NO. TYPE	BLOWS PER	CLASSIFICA	TION ER. 1959)	REMARKS			
AU HOLEN WILL			EE RMI-7D REDLORIC DES	for CRIPTION	Cover and	FILL		
William III			AF VOOT VIE					
	-5 -				7.11			
	2				WEATHERET	TILL		
1	-10 -				10.3			
\$ =	3				UNWEATHERE	DTILL		
	15		END OF		5'			
			E NO 01					
	-20				•			
	- 25							
	-30							
	-							
	-35							
1								
	-40							

INCOR	JARE PORRTED	f	T BORING		NO. RMI	-70		
PROJECT: KC	A FACILI	TY INVESTIGA	TION		PROJECT NO. 1 01 2			
	I SOBIUM		γ	544044				
		DRILLING CO.		SAMPLER	TUBE CORE			
DRILLER: BO			TYPE	SAMPLER	S'cont. SPLIT TUBE	CORE		
FOULPMENT:	OTACY 1	3"OD Augerto 59'	DIAMETER		4"			
METHOD:		1' bit to 76.65'	OTHER		<del> </del>			
	ELL CONSTRI	<del></del>	WELL DEVI	ELOPMENT	GROUND	WELL PROTES		
	RISER	INTAKE	METHOD: Come		ELEV 641.3			
MATERIAL	PVC	PVC	DURATION: 4	45 min	DATE STARTED			
DIAMETER	ス"	2"	YIELD: went	DRY	DATE COMPLETE	D: 10-17 -88		
COUPLING	THECADED	THREADED	OTHER:		INSPECTOR: Re	B GUIDEY		
CONSTRUCTION	SA CONTY	PE BLOWS PER	CLASSIFICAT		REMARKS	[		
	-5	cond	sles, Gravel, Su rrete, fine San NCOMSOLIDATED	۵.	cover and	FILL		
	2	1004	Y SILTY CLAY Ily surted Ganue exidized famil	L,	WEATHELED 7			
	-15 4	6	eay CLAY, trac	e (-) GRAVEI	UNWEATHERED	TILL		
	-20 — 5 -25 —		grocsto	٠				
	-30		GREY CLAY+: fine Sand	SILT, tence(-)				
	-35 — B	Ang	13' Small Rep GLA BLACK laminae	rnesad 37:3'				
	40 -	64	lavel					

AWARE INCORPORATED	TEST BORING LOG	NO. RMI - 7D
PROJECT: KCRA FACILITY INVE	STIGATION	ISHEET NO. 2 of 2 PROJECT NO. 4/20
CLIENT: KMI SODIUM PLANT WELL CONSTRUCTION TO SAMPLE	0.45050000	PROJECT NO. 2728
CONSTRUCTION TO TYPE BLOWS PORTION	CLASSIFICATION (AFTER BURMISTER, 1959)	REMARKS
9.	GRAY SILTY CLAY, trace fine Gravel	
145 - 10	ANGULAR SHALE FRAGMENTS INCREASE IN SIZE AND FREQUENCY	
50 -	Modium to Conair SAND, little 52.3'  Clayey SILT, thace Knowel  FRAY SILTY CLAY, take fine KRAW	
/2	GRAY SHALE BEDROCK	CHAGRIN SHALE
-65	SOFT DRILLING	
	SOPT DRILLING	
70		
-75	THE OF BORING	
80		
	, ,	

AMA	RTED	F	EST BORING BMW-105	S LOG	NO. RMI	
PROJECT: RCRA	FACILITY	INVESTI	GATION		PROJECT NO. E	<u> </u>
CLIENT: RMI S	NG DATA	N T		04.404.4		120
CONTRACTOR: PENNS		<b>4</b>			NG METHODS	
				SAMPLER	TUBE	CORE
	E GOLLI	HUP	TYPE	<del></del>	5 cont. SPLIT TUBE	ļ
EQUIPMENT: KOTA	<u> </u>		OTHER	<del></del>	<del>4</del>	
METHOD:	CONCTRUCT	ON	WELL DEVI	EL OBLIENT	1000000	
<del></del>	CONSTRUCTI		METHOD: Com		FI SI ( )	WELL PROTOSO
<del></del>	RISER	INTAKE			ELEV 637,2	1639.99
	<u> </u>	PVC	DURATION: /.	3 hrs	DATE STARTED	
DIAMETER COUPLING THE	CADID		OTHER: Ute		DATE COMPLETE	
WELL I	LAULD	THREADED	OTHER: Whe	coaj	INSPECTOR: Re	D GUIDET
CONSTRUCTION THE LAND	NO. TYPE	LOWS PER SINCHES	CLASSIFICAT		REMARKS	
			SEE RM1-41 FEOLOKIC DE		1.71 CLAY CAP	
-5	2		PEOTORIC DE	FS C RIPT ION	реатнехед	TILL
					8.1	
					UN WE ATHER	
	3					
15	<u> </u>			15'		
}			END OF	BORING		
-						
-20					·	
- 25						
-						
+ 1						
-30						}
1					1	
t 1						
-35						
-33						
- [ ]						
}	1 -					
<del>-40</del>	.   }-					1
}	1					ł
}	-	<del></del>				1
			<del></del>		<u> </u>	

			<del></del>								Ł
AU	JARE	=		TES	T BORING	LOG	NO.	RMI			1
	PORATE										
PROJECT : ACA				STIGA	MW - 10 D		ISHEET	NO I	01 2		1
	I SOBIU		ent		r		PROJEC	T NO. E	120		1
CONTRACTOR: P	PENNSELVA		RILLING	Co		SAMPLIN SAMPLER	G METHO	BE		RE	4
	IRNIE 6				TYPE	SAMPLER	5 cont.			A C	ĺ
EQUIPMENT: A				to 48.8'	DIAMETER		4.				1
METHOD:	5	% B11	to 64.		OTHER						]
W	ELL CONS		~		WELL DEVI			GROUND		PROTICSG	4
MATERIAL	PVC	н	PVC	AKE	METHOD: Comp			637.4			4
DIAMETER	2"		7 7 7 7 7 7 7		OURATION: /, YIELD:	5 hrs		TARTED : OMPLETE			1
COUPLING	THECAD	εD	THREA	DED		e SILTY	INSPECT	OR: R	B GUI	DET	1
WELL CONSTRUCTION	ΞE	SAMP	LE	1	CLASSIFICAT	ION				***************************************	1
<u>Johnson Content</u>	OEPTH (FEET)	TYPE	BLOWS PER		(AFTER BURMISTE		R	EMARKS			1
PPTT	-07	1	• INCHES		ROWN SILTY CLAY	·	<del>                                     </del>				1
						1.7	CLAY	CAP		4	
$ \mathcal{N} $ $ \mathcal{N} $	-   '				LACK PEAT	2'	1				
	-	}		1	ED BROWN AND BEAT	- •	WEAT	HERED "	TILL "		
1/1/1/1/	-5 -			0	XIDIZED FRACIURI	ES PARISENT 5.4'					ĺ
rriri	-				FROWN SILT	6.4	]				
	2			Mottles fine far	seems and song SILT OXIDITED FRE	VCLAY, CARCE(-)	ł				1
ИИ ИИ					Y SILTY CLAY,		<del> </del>				
	-10			4:	a Bravec	- 222 (-)					1
111111	.						1				
VVIVI	.   3	-					UNWI	eathexe	DTILL		
. [ ] ] ] }	-	-					}		- N		l
	•					14.41					İ
YYIYY	-15 -			GRAY Cla	gey SILT, teace fo	ine 54mb /5.3	1			ļ	ł
	. 4				AY CLAY						
				5^	abes to		j				. Ma
	.			68-4	SILTY CLAY, tem	e fine Sanb ,	ŀ				/ /
	-20 -	}-			fine SAND		İ				
VVIVI		F		LAMINA	TEN fine SANA O	- <u>- 31'</u>	l				
	[5]			SILTY C	THE TIME SAND C	my in color	Ì				
		L		· ·	Common or a common	23,7					
[	-25 -	-		nke	SILTY CLAY, E	eack fine Sand					
1111 VY	. }	}-								Í	
YYIII	6	-									
		F									
VVITI	-30 —								ĺ		
11111	-30									l	
$ \mathcal{N} $ $ \mathcal{N} $	7	-							1		
r 1		-							ł	ļ	
11/1/1/1		<b> </b>				35			ĺ	j	
PYIYIT	-35 -	1		GRAV	SILTY CLAY, +	CACE (4) Family					
1 1 1 1 1 1 1	8					U) DIKAVEL			j	and the second second second	en e
'//   / / l	0	_							}		41.
		-				j					1167 7
11/11 KH	40 -	}-							[		i r
Y I I I I I											,
									1		

PROJECT: RCRA FACILITY INVESTIGATION SHEET NO 2 of 2 CLIENT: KML SOPIUM PLANT PROJECT NO 4/20		~
CLIENT: IMI SANUM PLANT	INCORPORATED FBMW-1015	<i>J</i>
WELL TO PROJECT NO 2720	CLIENT: AMI SANUM PLANT	
CONSTRUCTION THE SAMPLE CLASSIFICATION REMARKS	CONSTRUCTION TO SAMPLE CLASSIFICATION REMARKS	
	GRAY SHALE BEDROCK  CHAGRIN SHALE  GRAY SH	

\_

FISMW- LLS WELL 201 TOP OF CASING ELEVATION - CAP 642.92 GRADE ELEVATION 640.60 GRADE (FEET) CEMENT GROUT --2"4 - SCH 40 THREADED BROWN AND GRAY BILTY CLAY (CL) COMPACTED NATIVE SILT/CLAY BACKFILL - W 6" AUGER HOLE -COMPACTED BENTONITE -GRAY SILT 2"4- SCH. 40 THREADED PVC CASING - 10 SLOT. -- 20 5 FOOT LONG SCREEN-SAND PACK -GRAY CLAYEY SILT (ML) - 25 - PLUS MONITORING WELL

FBMW- 220

LDCAT	IDN	MAF	<del></del>	<del></del> -		ENG	INEE	RING	-SCIEN	ICE W	/ELL	LDC	;	PAGE	1	OF .	3
						VELL NUMBE	, 30	)1			LDCATI	DN L	-TEC,	ASH.	TABUL	Α.	
	SEE	FIG	URE	1		MIE		-20-8	7		VEATH	Ot .					
			650		7	LOCAT	DO J.	M. ST	ANGL		DRILLE	Э <sub>М</sub>	EG				
	SER			9.4		METHO	MG HD	ILLOV	STEM	AUGER	R		SAMPLING HETHOD	SP	LIT S	POON	
ELEVA	ATIO	N_				PACK		ARSE	QTZ S	AND			SEAL		ואסדא		
CASING	TYPE	Р	VC						<b>NUMETER</b>	2.0*		LDIGT	53.0	,	MOLE MA	•	
SCHEEDS	TYPE	Р	vc			\$LOT	10		TAMETER	2.0*		LEHGTI	5.0′		TUTAL MOPTH	54.0	
MOESTUME CONTENT	SOUTHING	MONETTY	PLASTICETY	THE THE	Uncardo VAPORS OFFIO	E S	SAPLE RECOVERY	POGTRATED	Į	.ITHOL	.DGY/	'REHA	RKS		,	VELL PLETI STICK	
						•			ROAD	GRAV	FI			_	-   - 5	UP	`  _
						,-	_		FILL	<u> </u>	~~					4	
1														+		1	
						` -	-							7		1	
			}			3-	_							1			
	-					•-								$\pm$	-	l	
`						<b>5</b>	_	3						Ŧ	- (**)	1	
							_	13						#			
l						,_											
						1	-	$\vdash \dashv$	BROVI	N SILT	T AN	D GR	AVEL	+			
						•7	_		FILL	RUST	STA	INS		#			
						<b>'</b>	_							$\pm$			
						10-	-	7						+			
					} }	$n \rightarrow$	-	28						#			
						12	_							$\pm$			
						4	•							+			
l						ם בי	-		STEEL	BLUE	SIL	T AN	D	$\Rightarrow$			
ļ	ĺ					×-	-		CLAY	SLIGH	IT TR	RACE	DF	+			
						<b>13</b>	_	23 34	VERT	LINE	2HU1	<b>U</b>		#			
						× -	_	41						土			
						,, +	-							+			
						17 +	-							Ŧ			
	. 4			4		"			ور ديون در	e s⊃				士			
·					. 1	19				* * '	•	•		· T	[4.4]		L
* . } -						" ]								7	·   5		
1900			EWB			CASDIC	-	30 F. F.	GROUT			RENTO		Ŧ			

:

FBMW. 22D (cont LOCATION MAP ENGINEERING-SCIENCE WELL LDG PAGE 5 3 301 LOCATION L-TEC, ASHTABULA MIE 8-20-87 VEATHER SEE FIGURE 1 LOCATED J. M. STANGL MEG m. METHERS METHERS METHOD SPLIT SPOON HOLLOV STEM AUGER PACK ELEVATION COARSE QTZ SAND BENTONITE HILL CASDIG TYPE PVC NAMETER 2.0' **LIDIGTH 53.0'** TOTAL 54.0' PVC MAKETER 2.0" **LIDNOTH 5.0' SLOT** 10 SCREEN TYPE WELL COMPLETION ACTION CONTRACT MORETTY LITHOLOGY/REMARKS E 20 NA 22 23 16 30 28 25'-27' SAME AS ABOVE GREATER SAND CONTENT 24 27' SAME AS ABOVE MORE SILT AND CLAY TRACE GRAVEL 22 27 29.5' SAME AS ABOVE GRAVEL CONTENT INCREASES SLIGHT INCREASE IN SAND GRAY SILT AND SILT SOME GRAVEL, DAMP 25 GRAY SILT AND GRAVEL 37 BROWNISH-GRAY SILT AND GRAVEL SAND 4 to 1 CONTENT INCREASE 40.0-40.3 LCSCO 540 CHOLT PENTUNCTE ZZZZ MONTELL DECEMBER OF THE PERSON VATER LEVEL

.

FBMW-22D (cot LOCATION MAP ENGINEERING-SCIENCE VELL LDG PACE 3 MEDES VELL LICATION L-TEC, ASHTABULA 301 8-20-87 BATE VEATHER SEE FIGURE 1 LOCATION MELLO J. M. STANGL MEG MED LINE SAPLINE SPLIT SPOON HOLLOV STEM AUGER GRAVEL. PACK ELEVATION CDARSE QTZ SAND BENTONITE SEAL. PVC HOLE CASDIG TYPE MAKETER 2.0" LIDISTN 53.0° TOTAL 54.0' PVC **stori** 10 SCHOOL TYPE MARTER 2.0" LEDISTN 5.0" VELL COMPLETION LITHOLDGY/REMARKS Ĕ GRAY SILT AND GRAVEL SOME SHALE FRAGMENTS 45' GRAVEL AND SHALE FRAGHENTS INCREASE 50' INCREASE AIN SHALE GRAGHENTS, PEBBLES 33 SHALE BORE HOLE TERMINATED AT 54,0' TL800 CASE **STO**UT LTECHIC LI B/E/W MONTONETTE ZZZZ MONTELL THE COURT SCREEDS VATER LEVEL

FRMW1- 23D


	r <u>k</u>	MN	<u></u>	235	>	,											
LDCA	MOIT	MAP						RING-	-SCIEN	CE '	WELL	LDG	<u> </u>	PACE	1	<b>o</b> r :	3
						MAGE	31	4			LOCATION L-TEC, ASHTABULA						
	SEE	FIG	URE 1	ì		DATE		18-87			VEATHER						
GRE	on-d		641.			LOCAT	B J,	M. ST	ANGL		MILLI M	D M	EG				
RISER 443.63						METHO	MG HO	LLOV	STEM	AUGE	R		SAPLIN	SP	LIT SI	PDDN	
ELEV	ATIO	N				PACK	2 CD		QTZ S				SEAL	BE	NTONI.	TE	
CASDIG	TYPE	P	VC						DIMETER	2.01		LENGTH	42		HOLE		
SCREEDY	TYPE	P۱	VC			SLDT	10		DIAMETER	2.01		LDIGIT	5.0'			47.5′	
KORTUNE	SCRTDS	Mount	PLASTICATY	SWELL IS.	CREAMIC VAPORS OFFIO	MOPTH	SAMPLE RECOVERY	POSTRATION	L	ITHO	LDGY.	/REMA	ARKS		CDMF	VELL PLETII STICK	
						•		2	GRASS	. Tn	P 20.	ti			-	UP	}
						1-	<u> </u>	3_5						$\dashv$	-		
		,		ļ		2.	_		BROW	N GR	ADIN	S TO	TAN	#	_		
							_										
			Ì			_	-							+			
		i	}			1	_		!					7			
1						5-		6						士	-		
					] ,	6-	-	6						$\mp$	-		Ł
						,_	_							#	_		
- 1							_							土			
						-	-							+			
	ļ					,-		8	STEEL	BLI	JE SI	LTY (	CLAY	7			P
						10		16						1			, °
	ļ					n-	_	17						+	-		
						12-	<u> </u>							#	- 3		
1						13	-										
1						14	-		TZIOM	AT	14.01			+			
	Ì					-	F ,	12	LIGIS	n I	47.0			7			
						15-	_	22 23						士			
						26	_	53						+	-		
						17	<u> </u>							7	- 3		2
228.		- ,শুন্দা	***\$;~4	orași de se	<b>33</b> 2 3	'u ^		<b>19</b> (0) (1	ध्ये क्ले.					* 1	4	A. F. 350 TA	4
				r		79	<u> </u>		STEEL	BLI	JE VI	ERY F	INE	+			
						-	-	3	WET	AT 18	3.01			Ŧ			
EGD(D		*******				CAST	G	5	акоит			DENTO	MITE			LŢI	مو د
	- 2		MOOT	LL.		SCREE	DN .		CD-C07		<u>¥</u>	VATD	rever			ית ה	L E/94

Art or

FBMW. 23D LOCATION MAP ENGINEERING-SCIENCE WELL LDG PAGE 2 3 VEL SE 314 LOCATION L-TEC, ASHTABULA 8-18-87 MATE SEE FIGURE 1 VEATHER LDCATED BRILLED J. M. STANGL MEG BRILLING METHER ENPLES SPLIT SPOON HOLLOW STEM AUGER GRAVEL PACK ELEVATION COARSE QTZ SAND BENTONITE SEAL. HELE PVC CASSES TYPE MANETER 2.0' LENGTH 42.0' PVC TOTAL 47.5' SCHOOL TYPE **SLOT** 10 MANETER 2.0" **LIDIOTH 5.0'** VELL COMPLETION MORETTY Toward Park Chicken VAPORS OTTO LITHOLOGY/REMARKS STEEL BLUE VERY FINE SAND 8 21 23 STEEL BLUE SILT TO CLAYEY SILT 12 STEEL BLUE CLAY STEEL BLUE CLAYEY SILT GRAY SHALE GRAY SILT WITH FINE GRAVEL × 35.5' PEBBLES AND GRAVEL 37 36-40 LESS PERRIES il COL 100 18 LESED 4 1 MO CARDIG **GROUT** MONTENETE LITERALIS LI BAZAN ZZZZ MONTEL TOO EE \$CREDI VATER LEVEL

FBMW. 23 D (cost) LOCATION MAP ENGINEERING-SCIENCE VELL LOG PACE 3 3 VELL MAGES LOCATION L-TEC, ASHTABULA MIE 8-18-87 VEATHER SEE FIGURE 1 LICATES J. M. STANGL MATTER MEG HOLLOV STEM AUGER METHER SPLIT SPOON GRAVEL PACK ELEVATION COARSE QTZ SAND BENTONITE SEAL, PVC CASDIE TYPE MANETER 2.0" LDMTH 42.0" TUTAL 47.5' SCHEEN TYPE PVC **SLOT** 10 MANETER 2.0" **LIDISTH** 5.0' SWELLE RECOVER VELL COMPLETION MONETTY Seeric Greens Orro LITHOLDGY/REMARKS 28 46 SAME AS ABOVE LIGHT GRAY SHALE GRAY CLAYEY SILT, LITTLE GRAVEL GRAY SILT WITH GRAVEL 45 WEATHERED SHALE SHALE 47 BURE HOLE TERMINATED The second of th **沙文 1987 中央** . . . . . PEODO: :40 Par mour CASSES LTE LD B/2/M **STREETIGE** ZZZZ MOOTEL SCREED пово выш VATER LEVEL

The state of the s



WELL FBMW. 235 214 TOP OF CASING ELEVATION - CAP 641.78 GRADE ELEVATION 639.80 DEPTH BELOW GRADE (FEET) CEMENT GROUT TOPSOIL 2" - SCH 40 THREADED, PVC BLANK CASING ----- 5 BROWN AND GRAY SILT (ML) COMPACTED NATIVE SILT/CLAY BACKFILL -- p S" AUGER HOLE -GRAY SILT - 15 COMPACTED BENTONITE -(ML) 2"4- SCH. 40 THREADED PVC CASING - 10 SLOT, -- 20 5 FOOT LONG SCREEN-SAND PACK -GRAY SILTY CLAY (CL) -- 25 - PLUG MONITORING WELL LINDE WELDING HEMSERNIC SCHOOL E.B.